


NOTES:

1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER APPLICABLE CONTRACT DRAWINGS.
2. ALL TRAFFIC CONTROL OPERATIONS SHALL BE CARRIED OUT TO AT LEAST THE MINIMUM STANDARDS AS SET FORTH IN BOOK 7 (ONTARIO TRAFFIC MANUAL).
3. LOCATION, OFFSET, HEIGHT, ETC., OF ALL SIGNAGE SHALL BE IN ACCORDANCE WITH BOOK 7.
4. ALL SIGNAGE AND TEMPORARY CONCRETE BARRIERS/BARRICADES WILL BE REQUIRED FOR THE ENTIRE DURATION OF CONSTRUCTION.
5. THE FINAL LOCATION AND OVERALL NUMBER OF SIGNS SHALL BE ADJUSTED BASED ON FIELD REQUIREMENTS. THE SIGNAGE LAYOUT AS SHOWN ON THIS DRAWING SHALL BE USED FOR BIDDING PURPOSES.
6. BRIDGE/ROADWAY CLOSURE AND DETOUR ROUTE SIGNING SHOWN ON THIS DRAWING APPLIES TO ROAD CLOSURE/TRAFFIC DETOUR AND IS NOT TO BE CONSTRUED AS A COMPLETE OR EXHAUSTIVE DEPICTION OF ALL TRAFFIC CONTROL REQUIRED DURING CONSTRUCTION. ALL OTHER REQUIRED TRAFFIC CONTROL AS PER BOOK 7 (i.e., CONSTRUCTION ZONE SIGNING, FLAG PERSONS FOR LOADING/UNLOADING OF MATERIALS, ETC.) TO PROTECT AND MAINTAIN THE SAFETY OF THE GENERAL PUBLIC AND INDIVIDUAL WORKERS REMAINS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE INCLUDED IN THE CONTRACTOR'S SUBMITTED TRAFFIC CONTROL/TRAFFIC MANAGEMENT PLAN.
7. TC-67 SIGN TEMPLATE TO READ AS FOLLOWS:
"UNION BRIDGE CLOSED AT UNION CREEK BETWEEN QUEENS LINE AND RED STREET / XXXXX XX, 20XX TO XXXXXXX XX, 20XX"
PRIOR TO THE FABRICATION OF THE SIGNS, THE CONTRACTOR SHALL SUBMIT A SIGN TEMPLATE TO THE CONTRACT ADMINISTRATOR FOR REVIEW.
8. THE CONTRACTOR IS RESPONSIBLE FOR ALL CONSTRUCTION AND DETOUR SIGNAGE FOR THIS CONTRACT. THE CONTRACTOR SHALL SUBMIT A TRAFFIC MANAGEMENT PLAN INCLUDING DRAWINGS SHOWING ALL CONSTRUCTION AND DETOUR SIGNS AND DEVICES TO THE CONTRACT ADMINISTRATOR TWO (2) WEEKS PRIOR TO STARTING WORK.
9. THE CONTRACTOR SHALL INSPECT ALL TRAFFIC CONTROL AND DETOUR SCHEMES AND ENSURE PROPER INSTALLATIONS ARE MAINTAINED FOR THE DURATION OF THE CONTRACT. INSPECTIONS SHALL BE PERFORMED PER BOOK 7 BUT NO LESS THAN ONCE PER DAY. THE CONTRACTOR SHALL MAINTAIN A DAILY LOG OF INSPECTIONS AND MAKE THE LOG AVAILABLE TO THE CONTRACT ADMINISTRATOR.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH DAILY RELOCATION OF TEMPORARY BARRIER OR OTHER TRAFFIC APPURTENANCES TO ALLOW CONSTRUCTION ACCESS AS REQUIRED.

SIGN ID	SIGN TYPE	TOTAL NUMBER REQUIRED
1	TC-67, TC-10	3
2	TC-10C w / DETOUR TAB	2
3	TC-10C w / DETOUR TAB	6
4	TC-10AL w / DETOUR TAB	2
5	TC-10AR w / DETOUR TAB	2
6	TC-10BL w / DETOUR TAB	3
7	TC-10BR w / DETOUR TAB	3
8	RB-62 c/w FLASHER	2
9	TC-7, TC-7TA, c/w FLASHER	2
10	TC-63A BARRICADE	2
11	TC-6	3



NO.	REVISION	BY	DATE
1	ISSUED FOR TENDER	T.D.	04/10/21

CLIENT	COUNTY OF PETERBOROUGH
PROJECT TITLE	UNION CREEK BRIDGE REPLACEMENT
DRAWING TITLE	DETOUR ROUTE SIGNING

DATE:	OCTOBER 2021
Drawn:	M.P. C.B. T.D.
Scale:	AS SHOWN
Des.:	M.P. C.B. T.D.
CONTRACT NO.	T-15-2021
SHEET	10 OF 11
DWG. NO.	09