

Hydrogeological Assessment, Woodview Golf Subdivision



June 8, 2023

Prepared for:
Eric Challenger

Cambium Reference: 15101-001

CAMBIUM INC.

866.217.7900

cambium-inc.com

Peterborough | Barrie | Oshawa | Kingston



Table of Contents

1.0	Introduction.....	1
1.1	Site Description	2
2.0	Geological and Hydrogeological Setting	3
2.1	Topography and Drainage.....	3
2.2	Physiography.....	3
2.3	Geology	4
2.4	Vulnerable and Regulated Areas.....	4
3.0	Methodology	5
3.2	Test-Pit Investigation.....	5
3.3	Test Well Selection and Installation.....	6
3.4	Hydraulic Pumping Tests	7
4.0	Results.....	14
4.1	Subsurface Conditions	14
4.2	MECP Well Records Assessment	15
4.3	Hydrogeological Conditions.....	16
5.0	Wastewater Assessment	18
5.1	Available Dilution.....	18
5.2	Predictive Assessment	20
5.3	Conceptual Wastewater Design	22
6.0	Water Supply Assessment	24
6.1	Hydraulic Pumping Test Results	24
6.2	Water Sustainability Discussion	29
6.3	Water Quality Results.....	30
7.0	Conclusions and Recommendations	32



8.0	Closing	34
9.0	References	35
10.0	Standard Limitations.....	37

List of Tables

Table 1	Test and Monitoring Well Information Summary	7
Table 2	Grain Size Analysis Results.....	15
Table 3	Summary of Surrounding Water Well Record Information	16
Table 4	Fracture Depths	16
Table 5	Test Well and Monitoring Well Information	17
Table 6	Available Dilution Calculations.....	20
Table 7	Predictive Assessment of Nitrate Concentration.....	21
Table 8	Pumping Test Details.....	24
Table 9	Summary of Water Quality Parameter Exceedances.....	30

List of Figures

Figure 1	Regional Site Location Map
Figure 2	MECP Well Records
Figure 3	Test Pit and Test Well Location Plans
Figure 4	Pumping Test – Test Well 1
Figure 5	Pumping Test – Test Well 2
Figure 6	Pumping Test – Test Well 3
Figure 7	Pumping Test – Test Well 4
Figure 8	Pumping Test – Test Well 5



List of Appendices

- Appendix A Land Information and Conceptual Development Plan
- Appendix B Test Pit Logs
- Appendix C Test Well Records
- Appendix D Grain Size Analysis
- Appendix E MECP Well Records
- Appendix F Water Budget
- Appendix G Water Quality Sampling Results



1.0 Introduction

Cambium Inc. (Cambium) was retained by Woodview Golf Course (the Client) to undertake a hydrogeological assessment for a proposed subdivision development located on 65 Northeys Bay Road, in the Township of North Kawartha (herein referred to as the Site; Figure 1).

The total area of the property is approximately 121.9 ha (301.2 acres). It is proposed that the 26.8 ha (66.2 acre) potential development portion of the Site would be developed in to 58 new residential lots and a 1.4 ha commercial lot. Cambium understands that the existing property to the north of the potential development area will remain residential.

A conceptual site plan of the proposed development is included in Appendix A. Cambium undertook a geotechnical investigation to determine geotechnical parameters and recommendations for the design and construction of roads and buildings for the proposed development (Cambium, 2023).

There are no municipal water or wastewater services available near the property; therefore, the Site has to be privately serviced. As such, a hydrogeological assessment was undertaken for the required on-site wastewater services and water supply, in accordance with the Ministry of the Environment and Climate Change (MECP) Guidelines D-5-4 and D-5-5.

The suitability of the development area for on-site disposal of wastewater was determined by identifying and characterizing the native soils and bedrock, the location of the shallow water table, and surficial slopes across the Site. Additionally, a predictive assessment of the attenuation capacity of Site for the potential nitrate contamination from on-site wastewater systems was conducted.

The water supply assessment included the installation and hydraulic testing of test wells and water quality testing of the granite bedrock aquifer to determine the sustainability of on-site groundwater resources.

Cambium used the results of the wastewater and water supply assessments to calculate the maximum number of residential lots for the Site considering its specific conditions (i.e., soil type, bedrock depth, terrain, and groundwater characteristics).



1.1 Site Description

The Site is irregular in shape and is bound by Northey's Bay Road to the west, Otis Northey Road to the northwest, and Fire Route 35 to the northeast. The regional location map of the Site is represented in Figure 1.

Most of the Site is identified as forested land with unevaluated wetlands throughout the eastern portion of the Site. The areas to the east and south of the Site are undeveloped woodlot (Figure 2). The land on the western portion of the Site is currently developed as a golf course.

The Township requested that the County of Peterborough (as part of their Official Plan Update) adjust the Woodview Hamlet Area to include the entire golf course. The request was approved by both the County and Township and can be seen in the Township of North Kawartha Land Use Schedule of the new County Official Plan (Appendix A).

On June 29, 2022, Peterborough County Council adopted the new County Official Plan through By-law Number 2022-47. The inclusion of the entire golf course (including the entirety of the potential development area) within the Woodview Hamlet area and the corresponding Rural Settlement land use designation will come into effect when the Official Plan receives approval from the Minister of Municipal Affairs and Housing.



2.0 Geological and Hydrogeological Setting

2.1 Topography and Drainage

As shown on the Ministry of Natural Resources and Forestry (MNRF) topography map in Appendix A, the Site generally slopes inward towards the EC wetland zone and an unnamed pond in the middle of the property which has a minimum elevation of approximately 259 m above sea level (masl).

There is a topographic high point at the northwest portion of Site with an elevation of 272 masl. The land gently slopes from the northwestern corner toward the unevaluated wetland and the unnamed pond in the center of the Site. Topography near the eastern border of the Site has a maximum elevation of 265 masl. From this local high point, the land slopes west toward the wetland and pond (MNRF, 2023).

Runoff is assumed to follow local topography and flow from both east and west into the wetland at center of the Site. From this wetland water will flow into the unnamed pond and ultimately discharge via an unnamed creek flowing southeast into Stony Lake, located approximately 2.4 km from the Site.

2.2 Physiography

The Site is located along the boundary of two physiographic regions. Most of Site falls within the Physiographic region known as the Georgian Bay Fringe (Chapman, 1984). This region is described as having very shallow soil and bare rock knobs and ridges. The region is a broad belt bordering Georgian bay that was separated the Algonquin Highlands. The region stretches from Parry Sound in the west to northern Kawartha Lakes where the Site is located. Glacial Lake Algonquin inundated much of the eastern portion of the region; however the area of North Kawartha Lakes was never inundated. This resulted in land with shallow soils of fine sand, silt, and clay in valleys with the other areas being exposed bare rock.

The southwest corner of the Site falls within the Dummer Moraines physiographic region. This region is characterized by rough stoney land with bedrock consisting of sedimentary limestone.



The moraines in the Kawartha Lakes have angular fragments, abundant Precambrian rocks, and limestone blocks (Chapman, 1984).

The physiographic landforms across most of the Site area are mapped as fringe bare rock ridges and shallow till with limestone plains identified in the southwest portion of the Site (Chapman, 2007)

2.3 Geology

The northeast portion the Site is overlain by a clay, silt, sand, and gravel veneer with primarily Paleozoic bedrock (Ontario Geological Survey, 2010). The west portion of the Site is characterized as a stony carbonate-derived glacial silty sand to sandy silt textured till on Paleozoic terrain. The southern center of the Site is classified as a wetland organic part, muck, and marl soil.

The Paleozoic bedrock in the area is primarily from the Middle Ordovician and identified as the Gull River Formation, which is composed of light grey to brown limestone with dolostone towards the base (OGS, 2007). The east portion of the Site is underlain by a crystalline Precambrian basement formation.

2.4 Vulnerable and Regulated Areas

The Site is situated within Otonabee – Peterborough Source Protection Area as per the Ministry of the Environment, Conservation and Parks (Ministry) Source Water Protection Information Atlas (SPIA) (MECP, 2022).

The Site is not located in a municipal well head protection area, or significant groundwater recharge area. However, the proposed development is in the following:

- Completely located within a Highly Vulnerable Aquifer (HVA) with a vulnerability score of 6
- Partially located within an Intake Protection Zone 3 (IPZ-3).

The Site area does not fall under regulated areas by a Conservation Authority. The Site is not located within any Areas of Natural and Scientific Interest (ANSI) (Ministry of Natural Resources and Forestry, 2022). The SPIA mapping is included in Appendix A.



3.0 Methodology

This section describes the methodology undertaken to complete the hydrogeological assessment.

3.1 Background Information

A thorough review of the available relevant background information was undertaken for this study, which included the following:

- Chapman, L.J. and D.F. Putnam. (1984). The Physiography of Southern Ontario: Ontario Geological Survey, Special Volume 2
- Ontario Geological Survey, 2010. Surficial Geology of Southern Ontario, available in digital format at 1:50 000 Scale.
- Ontario Geological Survey, 2011. Scale Bedrock Geology of Ontario, available in natural heritage digital format at 1:250 000 scale.
- Source Protection Area Mapping provided by the Ministry of Environment, Conservation and Parks (MECP)
- Natural Heritage Areas Mapping, available online through the Ministry of Natural Resources and Forestry.
- Topographic Mapping, available online through the Ministry of Natural Resources and Forestry.
- Water Well Information System (WWIS) provided by the MECP.

3.2 Test-Pit Investigation

On November 4, 2022, Cambium geotechnical staff attended the Site to complete a test pit investigation. The test pits were completed to determine the shallow subsurface conditions across the developable (western) area of the Site. The test-pits were excavated using a track-mounted excavator under the supervision of a Cambium technologist.



A total of 33 test pits, designated as TP101-22 through TP133-22 were advanced throughout the Site (Figure 3). Dynamic probe penetration tests (DPT) were completed at each test pit to determine compaction coefficient of the encountered soil.

In addition to DPTs, soil samples were collected from all test pits. Samples were logged for soil colour, texture, structure, moisture content, and consistency/compaction. Each sample was handled only by the technologist using dedicated nitrile gloves. Open test pits were backfilled with the excavated soils and compacted with the backhoe bucket. The test pit logs are provided in Appendix B.

3.3 Test Well Selection and Installation

The proposed development area is 26.8 ha in size, which is greater than 25 ha but less than 40 ha; therefore, 5 test wells for water supply assessment were required according to D-5-5 Technical Guideline for Private Wells: Water Supply Assessment (MECP, 1996). Four test wells, denoted as Test Well 1 (TW1), Test Well 2 (TW2), Test Well 3 (TW3), and Test Well 4 (TW4), were selected from the existing water supply wells distributed across the Site area and an adjacent property. One well, denoted Test Well 5 (TW5), was drilled by Burgess Well Drilling on November 11, 2022, to satisfy the five test well requirement from Guideline D-5-5. The well locations can be seen on Figure 3.

All five test wells were drilled into granite bedrock, with fractures observed from 7.6 metres below ground surface (mbgs) to 91 mbgs, with a mean depth of 34.4 mbgs. The overburden at the test well locations was relatively thin, ranging from 0 mbgs (exposed bedrock) to 6.1 mbgs, with an average thickness of 1.5 mbgs. The depths of the test wells varied from 13.1 mbgs to 91.0 mbgs, with a mean of 48.6 mbgs.

Section 4.2 iv of Guideline D-5-5 requires that test wells be located and constructed in such a way as to allow for the prediction of groundwater quantity. The test wells each had a pumping rate greater than 13.7 L/min, which is the minimum allowable pumping test rate according to Guideline D-5-5. Details of the five test wells are summarized in Table 1. The well records for the test wells are presented in Appendix C.



Table 1 Test and Monitoring Well Information Summary

Test Well ID	Thickness of Overburden (m)	Water Found Depth (mbgs)	Well Completion Material	Depth of the Well (mbgs)	Pumping Rate from Well Yield Test (L/min)
TW1	0.5	91.0	Granite Bedrock	91.0	40.0
TW2	0	61.0	Granite Bedrock	88.4	22.7
TW3	6.1	11.0	Granite Bedrock	13.1	45.4
TW4	0	17.7	Granite Bedrock	19.8	68.1
TW5	0.9	7.6	Granite Bedrock	30.5	37.9
MW1	Unknown	8.5	Unknown	30.5	Unknown
MW2	0	30.5	Granite Bedrock	31.9	4.5

1 – Well record for MW1 not found in MECP Well records database

3.4 Hydraulic Pumping Tests

On October 31, November 1, November 2, and November 3, 2022, Cambium staff completed a series of 6-hour pumping tests on each of the four existing on-site test wells. Cambium returned to complete a pumping test for the newly installed test well (TW5) on November 23, 2022.

Two additional pre-existing water supply wells were selected for monitoring at the Site and denoted MW1 and MW2. While one test well was undergoing a pumping test, the two monitoring wells and the other four on-site test wells (TW1 to TW5) were monitored for the duration of the pumping tests. The location of the wells is shown on Figure 3.

Water levels during the pumping tests were measured using Solinst™ pressure transducer Leveloggers installed in each of the five test wells. Barometric pressure was monitored using a Solinst™ Barologger and the collected data was used for water level data compensation purposes.

Manual water level readings were recorded for the test well being evaluated using a water level tape in the event of a malfunction with the logger. Additionally, manual measurements were taken of surrounding wells every hour throughout the duration of the test to see if the pumping well had influence on the water levels of the other test wells and monitoring wells.



3.4.1 Test Well 1

On October 31, 2022, Cambium met with the Client to complete a pumping test for TW1. Field staff denoted the well “Neighbours House” on the day of the investigation. This name was changed to TW1 after the field investigation was complete.

The Client had a pump preinstalled and ready for TW1. The pump was set at a depth of approximately 38 mbgs. A pressure transducer Levelogger was installed above this depth to measure water levels within the well. Water levels were also measured manually to mitigate against potential equipment failure. Disinfectant bleach was added to the well water prior to testing. The discharge end of the hose was disinfected by Cambium staff.

The static water level of well TW1 was 9.35 mbtoc. The well casing stickup of TW1 was 0.60 meters, therefore the static water level was 8.75 mbgs. The depth of the well from the MECP well record is 91 mbgs. Well depth was not verified in the field. The available depth of drawdown was 28.7 m prior to the commencement of the pumping test.

The pumping test commenced at 10:43. The discharge outlet was placed at about 50 m to the northwest of TW1. The pumping rate was measured at a flow rate of 25 to 30 L/min at the beginning of the test from 0 to 4 minutes. The flow rate was adjusted to establish a sustainable pumping rate for the duration of the test; adjustments were made during the initial stage of the pumping test with a rate decrease down to 14 L/min from 4 to 12 minutes and a subsequent increase to 16 L/min for the remainder of the test.

Water levels were measured in test wells TW1 to TW4 and the two monitoring wells denoted Monitoring Well 1 (MW1) and Monitoring Well 2 (MW2) during the pumping of TW1. The water levels were recorded using pressure transducers and measured manually on hourly intervals. Additionally, every hour turbidity and residual chlorine measurements were measured for the pumping well by Cambium staff.

The pump was turned off after 6 hours at 16:43 and water level recovery was monitored until 17:43, allowing for 97% recovery in 1 hour.



3.4.2 Test Well 2

On November 1, 2022, Cambium staff arrived at the Site for a pumping test on TW2. Field staff denoted the well “Pro Shop” during the field investigation. This name was changed to TW2 after the pumping test was complete.

The Client had a pump preinstalled and ready for the pump test for TW2. The pump was set at a depth of approximately 84 mbgs. A pressure transducer Levelogger was installed above this depth to measure water levels within the well. Water levels were also measured manually to mitigate against potential equipment failure. Disinfectant bleach was added to the well water prior to testing, on October 31, 2022. The discharge end of the hose was disinfected by Cambium staff.

The static water level of well TW2 was 9.20 mbtoc (the casing stickup of TW2 was 0.38 m, therefore the static water level was 8.82 mbgs). The depth of the well from the MECF well record is approximately 88.4 mbgs. Well depth was not verified in the field. The available depth of drawdown was 74.8 m prior to the commencement of the pumping test.

Pumping commenced at TW2 at 09:30 on November 1, 2022. The flow was set to a constant rate of approximately 14 L/min for the duration of the 6-hour test.

Water levels were measured in test wells TW1 to TW4 and the two monitoring wells (MW1 and MW2) during the pumping of TW2. The water levels were recorded using pressure transducers and taken manually on hourly intervals. Additionally, every hour turbidity and residual chlorine measurements were measured for the pumping well by Cambium staff.

The discharge outlet was located approximately 20 m to the southeast of TW2. The pump was turned off at 15:30 and the well recovery was monitored manually until 17:00, reaching approximately 98% recovery in 1.5 hours.

3.4.3 Test Well 3

On November 2, 2022, Cambium staff arrived at Site for a pumping test for TW3. Cambium staff named the well “North Well” on the day of the pumping test. This name was later changed to TW3 after the field investigation was complete.



The Client had a pump installed in the well already for irrigation use for the golf course. The pump was set at a depth of approximately 12 mbgs. A pressure transducer Levelogger was installed above this depth to measure water levels within the well. A pressure transducer Levelogger was installed below this depth to measure water levels within the well. Water levels were also measured manually to mitigate against potential equipment failure. Disinfectant bleach was added to the well water prior to testing, on October 31, 2022. The discharge end of the hose was disinfected by Cambium staff.

The static water level of well TW3 was 5.23 mbtoc (the casing stickup of TW3 was 0.26 m, therefore the static water level was 4.97 mbgs). The depth of the well from the MECP well record is approximately 13.1 mbgs. Well depth was not verified in the field. The available depth of drawdown was 6.8 m prior to the commencement of the pumping test.

A pumping test for TW3 was attempted at 9:00 on November 2, 2023; however, the generator malfunctioned, and the Client had to source another generator. The well was left to recover back to static conditions as seen in Figure 6. Pumping for the test re-commenced at 10:00 on November 2, 2022. The flow was set to a constant rate of approximately 22.7 L/min or 5 imperial gallons per minute (igpm) for the duration of the 6-hour test.

Water levels were measured in test wells TW1 to TW4 and the two monitoring wells (MW1 and MW2) during the pumping of TW3. The water levels were recorded using pressure transducers and measured manually on hourly intervals. Additionally, every hour turbidity and residual chlorine measurements were measured for the pumping well by Cambium staff.

The discharge outlet was located approximately 80 m to the south of TW3 into a pond on the Site. The pump was turned off at 16:00 and the well recovery was monitored manually until 17:00 at 60% recovery. Cambium left the data logger recording the levels in the well to measure the water levels to full recovery. The well reached 95% recovery at approximately 02:30 on November 3, which is 9.5 hours from the end of the pumping test (see Figure 6).



3.4.4 Test Well 4

On November 3, 2022, Cambium staff arrived at the Site for a pumping test on TW4. Field staff named the well “West Pond” on the day of the investigation. This name was changed to TW4 after the field investigation was complete.

The Client had a pump installed in the well already for irrigation use for the golf course. The pump was set at a depth of approximately 18 mbgs. A pressure transducer Levelogger was installed above this depth to measure water levels within the well. Water levels were also measured manually to mitigate against potential equipment failure. Disinfectant bleach was added to the well water prior to testing, on October 31, 2022. The discharge end of the hose was disinfected by Cambium staff.

The well casing stickup of TW4 was measured as 0.37 m, therefore the static water level was calculated at 8.87 mbgs. Manual well depth was not measured in the field. The depth of the well from the MECF well record is approximately 19.8 mbgs. The available depth of drawdown was 8.8 m prior to the commencement of the pumping test.

A pumping test for TW4 was commenced at 8:33 on November 3, 2022. The flow was set to a constant rate of 22.7 L/min (5 igpm) for the duration of the 6-hour test.

Water levels were measured in test wells TW1 to TW4 and the two monitoring wells (MW1 and MW2) during the pumping of TW4. The water levels were recorded using pressure transducers and measured manually on hourly intervals. Additionally, every hour turbidity and residual chlorine measurements were measured for the pumping well by Cambium staff.

The discharge outlet was located approximately 15 m to the east of TW4 into a pond on the Site. The pump was turned off at 14:33 and the well recovery was monitored manually until 15:58 at approximately 95% recovery in 1 hour and 25 minutes.

3.4.5 Test Well 5

On November 23, 2022, Cambium staff arrived at the Site for a pumping test for TW5. The pump was set to a depth of 29 mbgs. A pressure transducer Levelogger was installed above this depth to measure water levels within the well. Water levels were also measured manually



to mitigate against potential equipment failure. Disinfectant bleach was added to the well water prior to testing. The end of the hose was disinfected by Cambium staff.

The static water level of well TW5 was 4.58 mbtoc. The well casing stickup of TW4 was measured as 0.65 m, therefore the static water level was calculated at 3.93 mbgs. Manual well depth was measured at 31.92 mbtoc. Cambium staff set up the pump at approximately 29.0 mbtoc.

A pumping test for TW5 was commenced at 11:13 on November 23, 2022. The flow was set to a constant rate of 24 L/min for the duration of the 6-hour test.

Water levels were measured in TW2, TW3, and TW4 during the pumping of TW3. The water levels were recorded using pressure transducers for TW3 and TW4 and measured manually on hourly intervals for TW2, TW3, and TW4. Additionally, every hour turbidity and residual chlorine measurements were measured for the pumping well by Cambium staff.

The discharge outlet was located approximately 30 m to the southeast of TW5 into an area that was topographically lower than the test well. The pump was turned off at 17:13 and the well recovery was monitored manually until 18:58 at approximately 91% recovery in 1 hour and 45 minutes.

3.4.6 Groundwater Quality Sampling

Each test well was disinfected prior to sampling between October 31 and November 3, 2022, and on November 23, 2022.

Each test well was pumped until there was no residual chlorine in the discharge water, prior to collecting the water quality samples. Groundwater samples were taken from each test well in the last half hour of the pumping tests. The samples were collected from the disinfected outlet hose and handled using nitrile gloves. The samples were put on ice in a sample cooler provided by SGS Canada Inc. in Lakefield, Ontario. Samples were stored at a temperature between 0°C and 10°C prior during transport to SGS.



The samples were submitted to SGS Canada Inc. for analysis of the physical, general chemical, and microbiological parameters in Guideline D-5-5. SGS is certified by the Canadian Council of Independent Laboratories (CCIL).



4.0 Results

4.1 Subsurface Conditions

The results of the geotechnical investigation indicate that the developable area of the Site is characterized by relatively shallow overburden. Where present, dark brown topsoil overlies glacial till deposits, which, in turn, overlie the limestone and granite formations encountered during test wells drilling. All test pits were open and dry upon the termination on bedrock.

The till is generally composed of either cohesive or non cohesive glacial deposits.

Non-cohesive soils were predominantly sandy silt to silty sand, and the cohesive deposits were composed of brown clayey silt with trace sand and noted trace gravel in some locations.

Cobbles and boulders were encountered in within the glacial till deposits.

Grey, weathered and fractured limestone bedrock was encountered at all the test pit locations, ranging in depth from 0 mbgs (outcropping at ground surface) to a depth of 1.35 mbgs. Test pits that had bedrock at ground surface were localized to the northwestern and western portions of the developable area and included TP104-22–TP107-22 and TP112-22 (Figure 3).

Fissures were noted on the bedrock surface following excavation of the test pits at seven locations located along the western edge of the developable area (TP104-22 through TP107-22, TP112-22, TP114-22, and TP115-22). The fissures measured approximately 0.2 m in width, based on field observations, and may be indicative of localized karst topography.

For a more detailed description of the subsurface investigation, see the attached test pit logs (Appendix B) and the companion geotechnical investigation report (Cambium, 2023).

Cadmium notes in the geotechnical investigation report that the extent of the fissures underlying septic beds can be investigated to determine design restrictions for the septic system and groundwater supply wells. If supplemental work is done as a part of the geotechnical investigation in the western site area, Cambium can incorporate the new information into a revised hydrogeological assessment.



4.1.1 Grain Size Analysis

Laboratory particle size distribution analyses were completed on seven samples of the native soil taken from the boreholes and depths shown in Table 2. The grain size distribution results are provided in Appendix D.

Table 2 Grain Size Analysis Results

Test Pit	Depth (mbgs)	Soil	% Gravel	% Sand	% Silt	% Clay	T-Times (min/cm)
TP102-22, GS2	0.30-0.40	Clayey silt, trace sand	0	5	69	26	45
TP103-22, GS2	0.30-0.40	Sandy silt, some gravel, some clay	11	26	52	11	30
TP124-22, GS2	0.25-1.10	Silty gravel, some clay, trace sand	50	7	26	17	20
TP125-22, GS2	0.25-0.65	Silt and clay, some sand, trace gravel	1	11	46	42	>50
TP126-22, GS2	0.25-1.10	Sandy gravel, some silt, trace clay	54	28	10	8	10
TP129-22, GS1	0.00-0.45	Sandy silt, trace clay, trace gravel	1	28	63	8	25
TP131-22, GS2	0.20-0.40	Silty sand, some clay	0	51	32	17	35

The soil percolation rates ranged from 10 min/cm to >50 min/cm. The geometric mean of the percolation rate was estimated at 27.5 min/cm. These results indicate a moderate to low infiltration capacity of the native soils, depending on whether the coarse-grained till or fine-grained unit is encountered.

4.2 MECP Well Records Assessment

The MECP Water Well Information System (WWIS) database was accessed to review water well records located within 500 m of the Site.

A total of 23 water well records were located within 500 m of the Site, as shown on Figure 2. The water well records are attached in Appendix E. All 23 well records were listed as supply wells with varying uses which include domestic, commercial irrigation, or public. Further details are summarized in Table 3, below.



Table 3 Summary of Surrounding Water Well Record Information

		Total Depth (mbgs)	Depth Water Encountered (m)	Static Water Level (mbgs)	Recommended Pumping Rate (L/min)
Bedrock Wells Count: 23	Min	10.1	6.7	0.0	2.0
	Max	91.4	91.0	17.0	73.0
	Avg	42.9	35.8	7.4	32.3

All of the searched and recorded wells are used as water supply wells.

The records indicate that all the water wells are installed in fractured limestone or granite bedrock. This is consistent with the thin overburden cover in the region. Bedrock was encountered from surface level to a depth of 13.7 mbgs, with an average of 1.7 mbgs. Bedrock wells varied in depth from 10.1 mbgs to 91.4 mbgs and were on average 42.9 mbgs deep.

The static water levels varied from 0 mbgs to 17.0 mbgs. The average static water level was 7.4 mbgs. The recommended pumping rate for the bedrock supply wells range from 2.0 litres per minute (L/min) to 50 L/min, with a geometric mean of 32.3 L/min.

The water bearing fractures were encountered between the depths of 6.7 mbgs to 91.0 mbgs, with an average depth of approximately 35.8 mbgs. There was no significant correlation between fracture depth and flow rate. The number of fractures encountered during the installation of bedrock wells, at various depth ranges, were summarized below in Table 4.

Table 4 Fracture Depths

Fracture Depth Ranges (mbgs)	Number of Fractures Encountered
0 - 10	2
10 - 20	8
20 - 30	2
30 - 40	2
40 - 50	2
50 - 60	2
60 - 70	2
70 - 80	1
80 - 90	1
90 - 100	1

4.3 Hydrogeological Conditions

All wells within the monitoring network are completed in granite bedrock aquifers. The static water level, top of well casing, and ground surface elevations are presented in Table 5.



Similar to the variable fracture depth noted in the off-site MECP well records, fractures where water was first found in the test wells ranged from 7.6 mbgs for TW5 to 91.0 mbgs for TW1. Therefore, it is not assumed that the bedrock wells are completed in the same aquifer or are hydraulically connected. Rather, groundwater flow was inferred based on the observed relationship between topography and the static water levels in the wells (Table 5).

Table 5 Test Well and Monitoring Well Information

Well		TW1	TW2	TW3	TW4	TW5	MW1	MW2
Top of Pipe Elevation (masl)		107.79	110.92	102.94	104.53	103.64	108.00	103.34
Ground Surface Elevation (masl)		107.19	110.54	102.68	104.16	102.99	107.36	102.97
Stick-up (m)		0.60	0.38	0.26	0.37	0.65	0.64	0.37
October 31, 2022	Water Level (mbgs)	8.75	8.77	4.88	8.87	-(1)	8.83	5.42
	Groundwater Elev.(masl)	98.44	101.77	97.78	95.28	-(1)	98.52	97.54
November 1, 2022	Water Level (mbgs)	8.73	8.82	4.90	8.87	-(1)	8.46	5.41
	Groundwater Elev.(masl)	98.46	101.71	97.76	95.28	-(1)	98.89	97.55
November 2, 2022	Water Level (mbgs)	8.78	9.00	4.96	8.87	-(1)	8.47	5.43
	Groundwater Elev.(masl)	98.41	101.53	97.70	95.28	-(1)	98.88	97.53
November 3, 2022	Water Level (mbgs)	8.76	8.92	4.94	8.87	-(1)	8.71	5.46
	Groundwater Elev.(masl)	98.43	101.61	97.72	95.28	-(1)	98.64	97.50
November 23, 2022	Water Level (mbgs)	-(2)	9.05	-(2)	8.91	3.92	-(2)	-(2)
	Groundwater Elev.(masl)	-(2)	101.48	-(2)	95.24	99.07	-(2)	-(2)

1. TW5 installed after the October 31 – November 3 monitoring, therefore manual measurements were not possible.
2. TW5 pumping test on November 23, 2022, only monitored TW2, TW4 and TW5.

The topographic high of the development area corresponds to the highest recorded static water levels (in TW2). The well is located on a crest that slopes down to the northwest, west, and southwest toward the east boundary of the developable area and the unevaluated wetland in the center of the Site. The remaining wells were installed at lower elevations and have correspondingly lower static water levels. Therefore, groundwater flow in the granite bedrock is inferred to follow topography.



5.0 Wastewater Assessment

As per Guideline D-5-4 Technical Guideline for Individual On-Site Sewage Systems: Water Quality Risk Assessment (MECP, 1996) an assessment was completed to determine the feasibility of utilizing on-site sewage disposal for the development.

Guideline D-5-4 requires the septic effluent plume at the Site boundary to be less than the Ontario Drinking Water Quality Standards (ODWQS) limit of 10 mg/L for nitrate to prevent contamination of adjacent properties. Although natural processes and soil interaction can result in nitrate being attenuated in the receiving aquifer system, Guideline D-5-4 states that only dilution can be used as the attenuation mechanism to predict future nitrate concentrations. As such, a mass balance calculation is used to predict the impact of developing residential lots on the Site.

5.1 Available Dilution

The total available dilution for the Site is estimated by the following equation:

$$Q_i = A \times S \times I$$

Where: Q_i – Volume of Available dilution water

A – Area of the Site

S – Water surplus

I – Infiltration factor

To calculate the water surplus, the thirty year climate normal data collected between 1981 and 2010 at the Peterborough Trent U (ID 6166455) weather station was used. The data was accessed through the Environment Canada website (Environment Canada, 2022). The total yearly precipitation, on average, was 882 mm.

The Thornthwaite method was used to determine the amount of evapotranspiration that will occur at the Site (S. Lawrence Dingman, 2008). The calculated depth of evapotranspiration was 527 mm/year and the water surplus was calculated to be 355 mm per year (0.974 mm/day). The evapotranspiration calculations are attached in Appendix F.



To determine the fraction of surplus water that infiltrates into the soils at the Site, the volume of surplus water is multiplied by an infiltration factor. The infiltration factor varies between 0 and 1 and is estimated based on topography, soils, and cover as per the Stormwater Management Planning and Design Manual (Ministry of the Environment, 2003).

In addition to calculating the infiltration factor, the areas of the proposed development and nondevelopment areas were measured to determine the total volume of available dilution water generated in each portion of the Site. From the development plan, the total development area is 268,000 m² and the non development area is 956,918 m².

The volume of dilution water was calculated based on the post-development permeable area. The areas of the roads and standing surface water were assumed to be impermeable. For road areas, water was assumed to run-off towards the permeable areas of the Site. The proposed roofed area was included in the permeable area as it is assumed that roof leaders will direct any roof runoff to landscaped areas as is typical in rural subdivisions and therefore will not contribute to a post-development recharge deficit.

The non infiltrating area for the development area was determined to be 39,603 m², based on the road area and stormwater pond area in the concept plan. The non-infiltrating area for the nondevelopment area was determined to be 478,158 m², based on surface water and wetland areas in the concept plan.

The calculations of the available dilution water for each portion of the Site are outlined below Table 6.



Table 6 Available Dilution Calculations

Infiltration Factor				
	Development Area		Non-Development Area	
Topography	Flat land = 0.3		Flat land = 0.3	
Soil	Medium combinations of clay and loam = 0.2		Tight impervious clay = 0.1	
Cover	Cultivated and woodland mix =0.15		Cultivated=0.1	
Infiltration Factor (I)	0.65		0.50	
Volume of Precipitation Water				
Parameter	Symbol	Units	Development Area	Non-Development Area
Dilution Area	A	m ²	228,397	472,925
Surplus	S	m/day	0.000973	0.000973
Volume of Surplus Water (Per Day)	A * S	m ³	222.14	459.96
Volume of Available Dilution Water (Per Day)	A * S * I	m ³	144.39	229.98
Volume of Runoff Water (Per Day)	A * S * (1-I)	m ³	77.74	229.98

5.2 Predictive Assessment

As per the procedure in Guideline D-5-4, a nitrate loading of 40 grams/lot/day is required to simulate the effluent loading from conventional septic systems on the receiving groundwater system. Total nitrogen (all species) ultimately converts to nitrate through the wastewater treatment process, so nitrate is the critical contaminant in sewage effluent. Each proposed lot is anticipated to generate an average discharge of 1,000 L/day of sewage effluent which contributes to the dilution of the total nitrate load.

To determine if the proposed lot density is adequate for nitrate dilution, a mass balance calculation is used to determine the sewage loading for nitrate on the property boundary. The mass balance calculations are outlined below as:

$$Q_t C_t = Q_e C_e + Q_i C_i$$

Where: Q_t = Total volume ($Q_e + Q_i$)

C_t = Total concentration of nitrate at the property boundary

Q_e = Volume of septic effluent



C_e = Concentration of nitrate in effluent (40 mg/L)

Q_i = Volume of available dilution water

C_i = Concentration of nitrate in dilution water (0.1 mg/L)

To determine the concentration of nitrate at the property boundary (C_t), the above mass balance equation can be arranged as follows:

$$C_t = \frac{Q_e C_e + Q_i C_i}{Q_t}$$

This equation was used to determine the dilution of wastewater by including infiltration on both the developable and non-developable portions of the Site. The results of the equation have been outlined in Table 7 below:

Table 7 Predictive Assessment of Nitrate Concentration

Variable	Value
Number of Lots	60
Q_e (L)	60,000
C_e (mg/L)	40
Q_i (L)	374,375
C_i (mg/L)	0.1
Q_t (L)	434,375
C_t (mg/L)	5.53

At the time of the assessment, the proposed development includes the construction of 58 new residential dwellings and 1 commercial lot to be developed in the future. The existing lot to the north will remain residential.

The predicted nitrate concentration at the Site boundary based on this 60-lot density using the calculated dilution volume, is 5.53 mg/L, which is less than the maximum allowable limit of 10 mg/L. Therefore, the Site can accommodate the proposed 59 new lots according to Guideline D-5-4.

The actual nitrate concentration is anticipated to be even lower due to the natural attenuation that will occur within the soil since this calculation only assumes dilution. In addition,



conservative estimates were used for infiltration factors for the non development area with the limited information on soil characteristics in the area.

5.3 Conceptual Wastewater Design

Section 8 of the *Ontario Building Code* (OBC) details the design, construction, operation, and maintenance of sewage systems. No proposed lot specific development information is available at this time. As such, the following assumptions were used in the conceptual on-site sewage system design:

- Four-bedroom dwelling.
- Percolation rate of >50 min/cm (accounts for worst-case soils)
- Minimum lot area of 3,000 m² (Lot 18 and Lot 21)

According to Table 8.2.1.3.A of the OBC, a four-bedroom dwelling has a daily sewage design flow volume of 2,000 L/day. Based on the design flow for residential occupancy, the proposed septic tank capacity was calculated as follows in accordance with section 8.2.2.3. of the OBC:

$$\text{Volume (V): } V = 2 * Q$$

$$V = 2 * 2,000 \text{ L}$$

$$V = 4,000 \text{ L}$$

A single two compartment septic tank with capacity of 4,500 L would be suitable to achieve the minimal capacity requirements.

The estimated percolation times from the soil samples for the proposed lots across the Site were between 10 and >50 min/cm. A percolation rate of 50 min/cm was considered as a worst case.

Furthermore, bedrock was encountered at depths ranging from ground surface to 1.35 mbgs. A conventional leaching bed will require a minimum vertical separation of 0.9 m between the bedrock contact as per the OBC; as such, the proposed leaching beds may be required to be either partly or fully raised. An advantage of partially or fully raised filter beds with a minimum



vertical separation of 0.9m is that it mitigates some of the risk of the isolated fractured bedrock in the western portion of the proposed development area.

Considering worst-case conditions ($T > 50$ min/cm, bedrock at the surface, and the smallest proposed lot of 3,000 m²), a conceptual sewage system design using a raised filter bed was explored. The total required footprint is determined by the allowable sewage loading rate based on Table 8.7.4.1. of the OBC. Using a soil percolation time of 50 min/cm, the maximum loading rate is 4 L/m²/day, the following calculations described the required footprint of the conceptual filter bed components:

Effective Filter Area: $A = Q / 75$
 $A = (2,000 \text{ L/d}) / 75$
 $A = 26.7 \text{ m}^2$

Loading Area: $A = Q / LR$
 $A = (2,000 \text{ L/d}) / (4)$
 $A = 500 \text{ m}^2$

Based on a daily sewage design flow of 2,000 L/day, the loading area (total footprint) of the proposed raised leaching bed needs to be a minimum of 500 m². Considering worst-case percolation rates for soils and the lot with the smallest area, 2,500 m² would remain for the development of a residential dwelling.

The large area of the Site will provide adequate space for the installation of on-site wastewater treatment systems and should be able meet the required setback distances (i.e., structures, property lines, wells etc.) outlined in OBC Tables 8.2.1.6.A and 8.2.1.6.B. However, each lot should be considered and evaluated independently for each Site-specific sewage system design. The Site conditions appear feasible to install on-site wastewater systems.



6.0 Water Supply Assessment

6.1 Hydraulic Pumping Test Results

Table 8 provides a summary of the key parameters measured during the pumping tests including pumping rates, well details, and recorded final drawdowns at each well.

Table 8 Pumping Test Details

Well Identification	Pump Depth (mbtoc)	Pumping Rates (L/min)	Static Water Level (mbtoc)	Observed Drawdown (m)	Available Drawdown (m)
TW1	38	16	9.35	2.28	28.7
TW2	84	14	9.20	39.89	74.8
TW3	12	22.7	5.23	1.17	6.8
TW4	18	22.7	9.24	1.98	8.8
TW5	29	24	4.58	1.34	24.4

Note: mbtoc – metres below top of casing

Based on the data above, the drawdown in the wells during a 6-hour pumping test ranged from 1.17 m to 38.89 m, while the available drawdown in the wells at respective pump set depths ranged between 6.8 m to 74.8 m.

6.1.1 TW1 Pumping Test – Test Well 1

The water level drawdown and recovery curve of the pumping test are outlined on Figure 4. During the pumping test the water level lowered from 9.35 mbtoc to 11.63 mbtoc (a drawdown of 2.28 m) at the time the test was concluded (16:43). In total, 5,790 L of water was withdrawn from well TW1 during the pumping test.

The water level recovery was monitored manually until 17:43, allowing for approximately 97% recovery. The data logger captured the remaining recovery after Cambium left the Site.

The water withdrawal rate of well TW1 was demonstrated to be sustainable upon completion of TW1 Pumping Test (see Section 6.2).



6.1.1.1 Monitoring Well Influences

Water level fluctuations of all other monitored wells (TW2 to TW4, MW1 and MW2) during the test are outlined on Figure 4. There was no water level response noted at TW2–TW4 or MW2 during the TW1 pumping test on October 31, 2022. This can be seen as on Figure 4 from the straight-line response shown in the monitoring well water levels during the pumping of TW1.

From the logger data, the water levels at MW1 appears to show fluctuations at 11:00, 12:58, 13:36, and 16:09 during the pumping test at TW1. It is Cambium’s opinion that domestic water use was the cause of these fluctuations as the sudden drops and subsequent recoveries in water level are consistent with intermittent residential well use rather than increasing drawdown from the pumping test.

In summary, the water withdrawal from TW1 on October 31, 2022, did not induce a measurable water level response at any of the monitored wells.

6.1.2 Pumping Test – Test Well 2

The water level drawdown and recovery curve of the pumping test are outlined on Figure 5.

During the pumping test the water level lowered from 9.2 mbtoc to 49.1 mbtoc (a drawdown of 39.9 m) at the time the test was concluded (15:30). In total, 5,040 L of water was withdrawn from well TW2 during the pumping test.

The water level recovery was monitored manually until 17:00, allowing for approximately 98% recovery. The data logger captured the remaining recovery after Cambium left the Site.

The water withdrawal rate of well TW2 was demonstrated to be sustainable upon completion of TW2 Pumping Test (see Section 6.2).

6.1.2.1 Monitoring Well Influences

Water level fluctuations of all other monitored wells (TW1, TW3-TW4, MW1-MW2) during the test are outlined on Figure 5. There was no observed influence on monitoring well water levels in TW1, TW3-TW4, MW1-MW2 during the duration of the pumping test. The drawdown graph



for the monitoring wells shows a straight-line relationship for all of the wells indicating no water level fluctuation due to the pumping of TW2.

From the logger data, the water levels at MW1 appears to show a lowering of 0.80 m at 17:30. This is attributed to domestic water use which occurred after the pumping test concluded. Logger data for TW1 show a 1.57 m sudden drawdown change at 9:34 which returned to static at approximately 9:42. This rapid change in water level corresponds with the time period the Client told Cambium staff that they pulled the TW1 pump from the well used for pumping test on October 31, 2022, to return the well to a functioning condition for the homeowner. The Client advised Cambium the pump was pulled between the times of 9:15-10:00 and that the logger got caught and pulled up with the pump during this time. The Client returned the logger once it was found to be moved with the pump.

In summary, the water withdrawal from TW2 on November 1, 2022, did not induce a measurable water level response at any of the monitored wells.

6.1.3 Pumping Test – Test Well 3

The water level drawdown and recovery curve of the pumping test are outlined on Figure 6.

During the pumping test the water level lowered from 5.23 mbtoc to 6.40 mbtoc (a drawdown of 1.17 m) at the time the test was concluded (16:00). In total, approximately 8,183 L of water was withdrawn from TW3 during the pumping test.

The water level recovery was monitored manually until 17:00 allowing for approximately 60% recovery with the data logger capturing the remaining recovery after Cambium left the Site. According to the logger data, well water levels returned to static conditions at approximately 02:30 on November 3, 2022, 9.5 hours after the end of pumping.

The water withdrawal rate of well TW3 was demonstrated to be sustainable upon completion of TW3 Pumping Test (see Section 5.6).



6.1.3.1 Monitoring Well Influences

Water level fluctuations of all other monitored wells (TW1 to TW2, TW4, MW1, and MW2) during the test are outlined on Figure 6. There was no observed influence in water levels for the other monitored wells during the duration of the pumping test. The drawdown graph for the monitoring wells shows a straight-line relationship for all the wells indicating no water level fluctuation due to the pumping of TW3.

The data on Figure 6 was extended to November 3, 2022, to show the recovery of TW3 after the pumping ceased and Cambium was no longer on-site to take manual measurements. From the logger data, the water levels at MW1 appears to show domestic water use which occurred after the pumping test concluded. Logger data for TW4 also shows an approximate 1.0 m drawdown at 17:47, which occurred after the test had concluded. Water was taken from TW4 at this time to pre-set the flow rate for the pumping test occurring for TW4 on November 3, 2022.

In summary, the water withdrawal from TW3 on November 2, 2022, did not induce a measurable water level response at any of the monitored wells.

6.1.4 Pumping Test – Test Well 4

The water level drawdown and recovery curve of the pumping test are outlined on Figure 7.

During the pumping test the water level lowered from 9.24 mbtoc to 11.22 mbtoc (a drawdown of 1.98 m) at the time the test was concluded (14:33). In total, approximately 8,183 L of water was withdrawn from well TW4 during the pumping test. The water level recovery was monitored manually until 15:58 allowing for 95% recovery.

The water withdrawal rate of well TW4 was demonstrated to be sustainable upon completion of TW4 Pumping Test (see Section 6.2).

6.1.4.1 Monitoring Well Influences

Water level fluctuations of all other monitored wells (TW1 to TW3, MW1, and MW2) during the test are outlined on Figure 7. There was no observed influence on monitoring well water levels



during the duration of the pumping test. The drawdown graph for the monitoring wells shows a straight-line relationship for all the wells indicating no water level fluctuation due to the pumping of TW4.

From the logger data, the water levels at MW1 appear to be recovering from domestic water use which occurred before the pumping test started. The MW1 well recovered back to static conditions at approximately 09:30 and remained at static conditions for the duration of the test. Logger data for TW1 also shows an approximate 1.2 m immediate step response at 10:57 and subsequent rapid increase back to static around 11:54. The step response occurred at the same time as Cambium took a manual water level measurement at 10:57. The logger rope got tangled in the well and had to be reinstalled back to the same level upon coming back to the well to take the next water level at 11:54. Therefore it is Cambium's opinion that the step response is not indicative of a hydraulic response to pumping, but rather captures the issue with the logger.

Overall, the water withdrawal from TW4 on November 3, 2022, did not induce a measurable water level response at any of the monitored wells.

6.1.5 Pumping Test – Test Well 5

The water level drawdown and recovery curve of the pumping test are outlined on Figure 8.

During the pumping test the water level lowered from 4.58 mbtoc to 5.92 mbtoc (a drawdown of 1.34 m) at the time the test was concluded (17:13). In total, approximately 8,640 L of water was withdrawn from well TW4 during the pumping test.

The water level recovery was monitored manually until 18:58 allowing for approximately 92% recovery.

The water withdrawal rate of well TW5 was demonstrated to be sustainable upon completion of TW5 Pumping Test (see Section 6.2).



6.1.5.1 Monitoring Well Influences

For the TW5 pumping test on November 23, 2022, TW2 and TW4 were used as monitoring wells to potential observe water level fluctuations. The drawdown curve for TW5 and water levels of TW2 and TW4 can be seen on Figure 8.

There was no observed influence on monitoring well water levels in TW2 and TW4, during the duration of the pumping test. The drawdown graph for the monitoring wells shows a straight-line relationship for TW2 and TW4 indicating no water level fluctuation due to the pumping of TW5.

The pumping of TW5 on November 23, 2022, did not induce a measurable water level response at any of the monitored wells.

6.2 Water Sustainability Discussion

The results of TW1 to TW5 pumping tests indicate that water withdrawal at the rates used did not influence adjacent wells. The absence of influences is outlined on Figure 4 to Figure 8. All pumping tests had pumping rates greater than the minimum requirement from Guideline D-5-5 of 13.7 L/min. Pumping tests for TW2 and TW3 did not reach steady state conditions, however, TW1, TW4 and TW5 appear to have plateaued close to approximate steady state conditions.

6.2.1 Minimum Yield Assessment

Guideline D-5-5 provides minimum daily yield rates for private supply wells intended to service single residential family dwellings. As per Guideline D-5-5, the per-person water requirement is referenced as 450 liters per day (L/day). Further, the number of people living in a dwelling is equal to the number of bedrooms plus one. The number of bedrooms is assumed to be 4, unless otherwise specified. As such, the total daily water withdrawal volume required is assumed to be 2,250 L/day (i.e., 5 people x 450 L/day). Regardless of this calculation, D-5-5 states that the minimum pumping rate shall not be lower than 13.7 L/min.

The daily minimum volume available from wells TW1 to TW5 is greater than 2,250 litres per day and all wells recovered to at least 95% of the pre-test static water level within 24 hours.



Therefore, the results of the TW1–TW5 pumping tests indicate that the wells could sustain the quantity of water required for the development of the Site.

6.3 Water Quality Results

Raw water samples were collected from each test well in the last half hour of the pumping test. Lab reports are included in Appendix G. All samples were submitted to SGS Canada Inc. in Lakefield for analysis of general organic and inorganic chemistry.

The water quality results were compared with ODWQS Tables (O. Reg. 169/03) as well as objectives in D-5-5 (Private Well: Water Supply Assessment (MECP, 1996)). Table 9, below, summarizes the parameters which exceeded the corresponding ODWQS operational guidelines or aesthetic objectives during sampling events in October and November 2022.

Table 9 Summary of Water Quality Parameter Exceedances

Parameter	Ontario Drinking Water Standard	TW1	TW2	TW3	TW4	TW5
Hardness	100 mg/L	531⁽¹⁾	515	345	375	38.3
Sodium	20 mg/L as CaCO ₃	56.9	64.2	3.12	8.50	13
Total Dissolved Solids (TDS)	500 mg/L	-	743	420	477	494

1. *Bolded entries indicate parameters reported at concentrations greater than ODWQS Criteria*

In all samples, hardness comprises the largest component of total dissolved solids (TDS). Concentrations of hardness, sodium, and TDS in TW2 were greater than the ODWQS aesthetic objectives or operational guidelines. Hardness and sodium exceeded the applicable criteria in TW1. Although TW1 was not analyzed for TDS, similarities in chemistry between it and TW2 suggest that TW1 may also exceed the aesthetic objective for TDS.

Exceedances for hardness were reported for TW3 and TW4. TW5 had no reported exceedances.

Hardness, sodium, and TDS are parameters which may be naturally elevated in bedrock aquifers. Therefore, water quality should be confirmed for each lot prior to installation of a water supply and treatment system.



Measured concentrations of sodium in TW1 and TW 2 exceed the limit which serves as a warning to individuals on sodium restricted diets (20 mg/L). The concentration of sodium was less than the aesthetic limit and maximum concentration that is treatable (200 mg/L), which indicates that the water is still potable at the measured concentrations.

It will be the Client's duty to notify purchasers of the proposed lots that sodium may be present in groundwater at concentrations greater than 20 mg/L which would affect individuals on sodium reduced diets. This notification should be added to the title deeds for each applicable property.

Hardness can be amended with residential water treatment units such as water softeners. Use of water softeners using a sodium exchange resin to treat hardness could result in water with elevated sodium levels. If a sodium exchange method is used to reduce hardness, a separate tap which supplies unsoftened water should be installed for drinking at those lots with elevated sodium concentrations (MECP, 1996).

TDS is listed an aesthetic rather than a health-related criterion under the ODWQS. TDS does not have a maximum treatable concentration (MECP, 1996), but Guideline D-5-5 requires written rationale that corrosion, encrustation, or taste problems will not occur.

Since the TDS concentration at the Site is driven by hardness, treatment for hardness by removing calcium and magnesium from the water, as recommended above, should also reduce the corrosivity of water from the wells. However, given the elevated concentrations of sodium measured in some test wells, it is Cambium's recommendation that consideration should be given to systems that reduce hardness without a commensurate increase in sodium.



7.0 Conclusions and Recommendations

Conclusions and recommendations based on the results presented in this hydrogeological assessment are summarized below.

- The wastewater assessment indicates that the proposed development of 1 commercial lot and 58 lots with single family homes with private, on-site wastewater disposal, in addition to the existing residential development, would result in a nitrate concentration of 5.61 mg/L at the property boundary, which is less than the Ontario Drinking Water Quality Standard of 10 mg/L. The proposed development is therefore expected to maintain acceptable nitrate concentrations at property boundaries.
- The conceptual wastewater design indicates that shallow soils at the Site may require raised filter beds as part of the private wastewater systems. Single department septic tanks with a volume of 4,500 L would be appropriate for the minimum capacity requirement. The required footprint for a raised filter bed was calculated to be 500 m², leaving at least 2,500 m² of available area for building houses (estimated using the smallest proposed lot) Each lot should be considered and evaluated independently for each site-specific sewage system design.
- Raised filter beds could mitigate some risk associated with surface bedrock fissures observed in the western portion of the proposed development area during the geotechnical investigation by having a 0.9 m minimum vertical separation between the filter bed and bedrock contact.
- Hydraulic testing of TW1, TW2, TW3, TW4 and TW5 indicate the wells are able to produce sustainable yields greater than minimum 13.7 L/min requirement for the MECP Guideline D-5-5 assessment procedure. It is therefore determined that the granite aquifer at the Site can provide an adequate volume of water to supply the proposed development.
- Water quality results indicate the water from the test wells is of generally good quality, with the exceptions of hardness, sodium, and total dissolved solids. These parameters were reported at concentrations which exceed ODWQS objectives and guidelines; however, they



are all amendable with residential water treatment units. All other analyzed parameters were within acceptable ranges.

- It is noted that, although sodium concentrations are within aesthetic guidelines, they are present in quantities that exceed warning levels for individuals on sodium reduced diets. It will be the Client's duty to notify purchasers of the proposed lots that sodium may be present in groundwater at concentrations greater than 20 mg/L, which would affect individuals on sodium reduced diets.



8.0 Closing

We trust that the information in this submission meets your current requirements. If you have any questions regarding the contents of this report, please contact the undersigned.

Respectfully submitted,

Cambium Inc.

Warren Young, B.Eng., EIT
Junior Hydrogeologist / EIT



Kyle Horner, Ph.D., P.Geo.
Senior Hydrogeologist/Senior Project
Manager



9.0 References

- Cambium. (2023). *Geotechnical Investigation Report 65 Northey's Bay Road, North Kawartha, ON*. Peterborough.
- Chapman, L. a. (1984). *The Physiography of Southern Ontario: Ontario Geological Survey, Special Volume 2*.
- Chapman, L. a. (2007). *The Physiography of Southern Ontario*. Miscellaneous Release--Data 228: Ontario Geological Survey.
- Environment Canada. (2022). *Canadian Climate Normals 1981-2010 Station Data*. Retrieved 02 04, 2017, from http://climate.weather.gc.ca/index_e.html
- MECP. (1996). *D-5-4 Individual On-Site Sewage Systems: Water Quality Impact Assessment*. Ministry of the Environment, Conservation and Parks.
- MECP. (1996). *D-5-5 Private Wells: Water Supply Assessment*. Ministry of Environment, Conservation and Parks.
- MECP. (2022). Retrieved from Ministry of Environment, Conservation, and Parks - Source Protection Information Atlas:
<https://www.lioapplications.lrc.gov.on.ca/SourceWaterProtection/index.html?viewer=SourceWaterProtection.SWPViewer&locale=en-CA>
- Ministry of the Environment. (2003). *Stormwater Management Planning and Design Manual* .
- Ministry of Natural Resources and Forestry. (2022). *Natural Heritage System Areas*. Peterborough, Ontario: Ontario Ministry of Natural Resources and Forestry.
- MNRF. (2023). *Make a Topographic Map*. Ontario, Canada.
- OGS. (2007). *Paleozoic Geology of Southern Ontario; Miscellaneous Release -- Data 219*. Ontario Geological Survey.
- Ontario Geological Survey. (2010). *Surficial geology of Southern Ontario*. Ontario Geological Survey, Miscellaneous Release - Data 128 - Revised.



S. Lawrence Dingman. (2008). *Physical Hydrology, Second Edition*.



10.0 Standard Limitations

Limited Warranty

In performing work on behalf of a client, Cambium relies on its client to provide instructions on the scope of its retainer and, on that basis, Cambium determines the precise nature of the work to be performed. Cambium undertakes all work in accordance with applicable accepted industry practices and standards. Unless required under local laws, other than as expressly stated herein, no other warranties or conditions, either expressed or implied, are made regarding the services, work or reports provided.

Reliance on Materials and Information

The findings and results presented in reports prepared by Cambium are based on the materials and information provided by the client to Cambium and on the facts, conditions and circumstances encountered by Cambium during the performance of the work requested by the client. In formulating its findings and results into a report, Cambium assumes that the information and materials provided by the client or obtained by Cambium from the client or otherwise are factual, accurate and represent a true depiction of the circumstances that exist. Cambium relies on its client to inform Cambium if there are changes to any such information and materials. Cambium does not review, analyze or attempt to verify the accuracy or completeness of the information or materials provided, or circumstances encountered, other than in accordance with applicable accepted industry practice. Cambium will not be responsible for matters arising from incomplete, incorrect or misleading information or from facts or circumstances that are not fully disclosed to or that are concealed from Cambium during the provision of services, work or reports.

Facts, conditions, information and circumstances may vary with time and locations and Cambium's work is based on a review of such matters as they existed at the particular time and location indicated in its reports. No assurance is made by Cambium that the facts, conditions, information, circumstances or any underlying assumptions made by Cambium in connection with the work performed will not change after the work is completed and a report is submitted. If any such changes occur or additional information is obtained, Cambium should be advised and requested to consider if the changes or additional information affect its findings or results.

When preparing reports, Cambium considers applicable legislation, regulations, governmental guidelines and policies to the extent they are within its knowledge, but Cambium is not qualified to advise with respect to legal matters. The presentation of information regarding applicable legislation, regulations, governmental guidelines and policies is for information only and is not intended to and should not be interpreted as constituting a legal opinion concerning the work completed or conditions outlined in a report. All legal matters should be reviewed and considered by an appropriately qualified legal practitioner.

Site Assessments

A site assessment is created using data and information collected during the investigation of a site and based on conditions encountered at the time and particular locations at which fieldwork is conducted. The information, sample results and data collected represent the conditions only at the specific times at which and at those specific locations from which the information, samples and data were obtained and the information, sample results and data may vary at other locations and times. To the extent that Cambium's work or report considers any locations or times other than those from which information, sample results and data was specifically received, the work or report is based on a reasonable extrapolation from such information, sample results and data but the actual conditions encountered may vary from those extrapolations.

Only conditions at the site and locations chosen for study by the client are evaluated; no adjacent or other properties are evaluated unless specifically requested by the client. Any physical or other aspects of the site chosen for study by the client, or any other matter not specifically addressed in a report prepared by Cambium, are beyond the scope of the work performed by Cambium and such matters have not been investigated or addressed.

Reliance

Cambium's services, work and reports may be relied on by the client and its corporate directors and officers, employees, and professional advisors. Cambium is not responsible for the use of its work or reports by any other party, or for the reliance on, or for any decision which is made by any party using the services or work performed by or a report prepared by Cambium without Cambium's express written consent. Any party that relies on services or work performed by Cambium or a report prepared by Cambium without Cambium's express written consent, does so at its own risk. No report of Cambium may be disclosed or referred to in any public document without Cambium's express prior written consent. Cambium specifically disclaims any liability or responsibility to any such party for any loss, damage, expense, fine, penalty or other such thing which may arise or result from the use of any information, recommendation or other matter arising from the services, work or reports provided by Cambium.

Limitation of Liability

Potential liability to the client arising out of the report is limited to the amount of Cambium's professional liability insurance coverage. Cambium shall only be liable for direct damages to the extent caused by Cambium's negligence and/or breach of contract. Cambium shall not be liable for consequential damages.


Personal Liability

The client expressly agrees that Cambium employees shall have no personal liability to the client with respect to a claim, whether in contract, tort and/or other cause of action in law. Furthermore, the client agrees that it will bring no proceedings nor take any action in any court of law against Cambium employees in their personal capacity.



Figures

O:\GIS\XDS\15100-15199\15101-001 Woodview Golf - Eric Challenger - Hydrog & Geo - Woodview Golf Subdivision\2022-1-21 FIG 1 - Regional Location Map.mxd



HYDROGEOLOGICAL ASSESSMENT
ERIC CHALLENGER
 65 Northeys Bay Road,
 Woodview, Ontario

LEGEND

- Highway
- Major Road
- Minor Road
- Railroad
- Watercourse
- Water Area
- Provincial Park
- Wooded Area
- Built Up Area

Notes:
 - Base mapping features are © Queen's Printer of Ontario, 2019 (this does not constitute an endorsement by the Ministry of Natural Resources or the Ontario Government).
 - Distances on this plan are in metres and can be converted to feet by dividing by 0.3048.
 - Cambium Inc. makes every effort to ensure this map is free from errors but cannot be held responsible for any damages due to error or omissions. This map should not be used for navigation or legal purposes. It is intended for general reference use only.




194 Sophia Street
 Peterborough, Ontario, K9H 1E5
 Tel: (705) 742.7900 Fax: (705) 742.7907
 www.cambium-inc.com

REGIONAL SITE LOCATION MAP




Project No.:	15101-001	Date:	June 2023
Scale:	1:100,000	Projection:	NAD 1983 UTM Zone 17N
Created by:	DBB	Checked by:	KW
Figure:			1

O:\GIS\MXDs\15100-15199\15101-001 Woodview Golf - Eric Challenger - Hydrog & Geo - Woodview Golf Subdivision\2022-11-25 FIG 3 - Well Record Map.mxd



**HYDROGEOLOGICAL
ASSESSMENT**
ERIC CHALLENGER
65 Northeys Bay Road,
Woodview, Ontario

LEGEND

-  Water Well Records
-  Study Area (500m)
-  Site (approximate)


Notes:
 - Benchmark is the steel foundation stick-up of the road sign for Highway 56 (shown on map labelled "SIGN"), with an assumed elevation of 100.0 m.
 - Base mapping features are © Queen's Printer of Ontario, 2019 (this does not constitute an endorsement by the Ministry of Natural Resources or the Ontario Government).
 - Distances on this plan are in metres and can be converted to feet by dividing by 0.3048.
 - Cambium Inc. makes every effort to ensure this map is free from errors but cannot be held responsible for any damages due to error or omissions. This map should not be used for navigation or legal purposes. It is intended for general reference use only.



194 Sophia Street
Peterborough, Ontario, K9H 1E5
Tel: (705) 742.7900 Fax: (705) 742.7907
www.cambium-inc.com

MECP WELL RECORDS

Project No.:	15101-001	Date:	June 2023
Scale:	1:15,000	Rev.:	
Created by:	PAS	Projection:	NAD 1983 UTM Zone 17N
Checked by:	KW	Figure:	2







O:\GIS\XDS\15100-15199\15101-001 Woodview Golf - Eric Challenger - Hydrog & Geo - Woodview Golf Subdivision\2022-12\21 FIG 2 - Test Pit and Test Well Location Plan.mxd



HYDROGEOLOGICAL ASSESSMENT
ERIC CHALLENGER
 65 Northeys Bay Road,
 Woodview, Ontario

LEGEND

-  Monitoring Well
-  Test Pit
-  Test Well
-  Site (approximate)

Notes:
 - Benchmark is the steel foundation stick-up of the road sign for Highway 56 (shown on map labelled 'SIGN'), with an assumed elevation of 100.0 m.
 - Base mapping features are © Queen's Printer of Ontario, 2019 (this does not constitute an endorsement by the Ministry of Natural Resources or the Ontario Government).
 - Distances on this plan are in metres and can be converted to feet by dividing by 0.3048.
 - Cambium Inc. makes every effort to ensure this map is free from errors but cannot be held responsible for any damages due to error or omissions. This map should not be used for navigation or legal purposes. It is intended for general reference use only.



194 Sophia Street
 Peterborough, Ontario, K9H 1E5
 Tel: (705) 742.7900 Fax: (705) 742.7907
 www.cambium-inc.com

TEST PIT AND TEST WELL LOCATION PLAN

Project No.:	15101-001	Date:	June 2023
Scale:	1:5,000	Rev.:	
Created by:	DBB	Projection:	NAD 1983 UTM Zone 17N
Checked by:	KW	Figure:	3




Figure 4: Pumping Test - Test Well 1




Figure 5: Pumping Test - Test Well 2




Figure 6: Pumping Test - Test Well 3




Figure 7: Pumping Test - Test Well 4







Figure 8: Pumping Test - Test Well 5



Appendix A
Land Information and Conceptual Development Plan



LEGEND

- [Dashed line] EXISTING SUBJECT PROPERTY
- [Thin solid line] EXISTING PARCEL FABRIC
- [Green hatched area] EXISTING UNEVALUATED WETLAND (RETRIEVED FROM LIO)
- [Dotted line] EXISTING DRIVEWAY
- [Thin solid line] EXISTING STRUCTURE
- [Blue line] EXISTING WATERCOURSE
- [Yellow dashed line] EXISTING WETLAND BUFFER (30m)
- [Pink dashed line] WETLAND SETBACK (30m) (PROVIDED BY PALMER ENVIRONMENTAL CONSULTING - EIS)
- [Red dashed line] EXISTING WATERBODY (30m) AND WATERCOURSE (30m) BUFFER
- [Dotted line] TOP OF BANK (APPROX.)
- [Dotted line] BOTTOM OF BANK (APPROX.)
- [Diagonal hatched area] EXISTING HAMLET DESIGNATION
- [Dashed line] EXISTING ENVIRONMENTAL CONSTRAINT DESIGNATION
- [Grey shaded area] POTENTIAL DEVELOPMENT AREA

LOT/BLOCK No.	AREA (sq.m)	FRONTAGE (m)	DESCRIPTION
LOT 1	4783.57	61.15	SINGLE RESIDENTIAL
LOT 2	3408.64	30.00	SINGLE RESIDENTIAL
LOT 3	3300.13	30.00	SINGLE RESIDENTIAL
LOT 4	3301.11	30.00	SINGLE RESIDENTIAL
LOT 5	3314.76	30.29	SINGLE RESIDENTIAL
LOT 6	3237.29	33.01	SINGLE RESIDENTIAL
LOT 7	3339.38	40.02	SINGLE RESIDENTIAL
LOT 8	3270.67	46.71	SINGLE RESIDENTIAL
LOT 9	3388.28	39.18	SINGLE RESIDENTIAL
LOT 10	3466.92	30.00	SINGLE RESIDENTIAL
LOT 11	3453.61	30.74	SINGLE RESIDENTIAL
LOT 12	3365.67	30.00	SINGLE RESIDENTIAL
LOT 13	3306.61	36.28	SINGLE RESIDENTIAL
LOT 14	3858.06	30.00	SINGLE RESIDENTIAL
LOT 15	4263.06	30.00	SINGLE RESIDENTIAL
LOT 16	3558.58	30.00	SINGLE RESIDENTIAL
LOT 17	3012.91	31.56	SINGLE RESIDENTIAL
LOT 18	3000.00	30.00	SINGLE RESIDENTIAL
LOT 19	3613.75	30.00	SINGLE RESIDENTIAL
LOT 20	3084.62	30.50	SINGLE RESIDENTIAL
LOT 21	3000.00	30.00	SINGLE RESIDENTIAL
LOT 22	3211.25	30.00	SINGLE RESIDENTIAL
LOT 23	3229.44	30.00	SINGLE RESIDENTIAL
LOT 24	3023.03	30.00	SINGLE RESIDENTIAL
LOT 25	3187.62	34.00	SINGLE RESIDENTIAL
LOT 26	3282.71	50.00	SINGLE RESIDENTIAL
LOT 27	3456.28	78.29	SINGLE RESIDENTIAL
LOT 28	3001.71	30.00	SINGLE RESIDENTIAL
LOT 29	3042.31	33.51	SINGLE RESIDENTIAL
LOT 30	3008.95	33.00	SINGLE RESIDENTIAL
LOT 31	3040.53	32.00	SINGLE RESIDENTIAL
LOT 32	3001.98	30.00	SINGLE RESIDENTIAL
LOT 33	3325.57	30.00	SINGLE RESIDENTIAL
LOT 34	3494.84	30.00	SINGLE RESIDENTIAL
LOT 35	3099.62	31.00	SINGLE RESIDENTIAL
LOT 36	3058.54	33.00	SINGLE RESIDENTIAL
LOT 37	3013.89	35.00	SINGLE RESIDENTIAL
LOT 38	3152.30	38.00	SINGLE RESIDENTIAL
LOT 39	3038.45	38.00	SINGLE RESIDENTIAL
LOT 40	3464.75	52.02	SINGLE RESIDENTIAL
LOT 41	3990.02	45.00	SINGLE RESIDENTIAL
LOT 42	3830.12	54.95	SINGLE RESIDENTIAL
LOT 43	3387.85	53.32	SINGLE RESIDENTIAL
LOT 44	3221.57	44.47	SINGLE RESIDENTIAL
LOT 45	3189.74	46.11	SINGLE RESIDENTIAL
LOT 46	3161.21	45.60	SINGLE RESIDENTIAL
LOT 47	3802.31	45.29	SINGLE RESIDENTIAL
LOT 48	3021.52	45.98	SINGLE RESIDENTIAL
LOT 49	3049.31	40.00	SINGLE RESIDENTIAL
LOT 50	3145.97	40.00	SINGLE RESIDENTIAL
LOT 51	3165.29	40.00	SINGLE RESIDENTIAL
LOT 52	3128.95	40.00	SINGLE RESIDENTIAL
LOT 53	3311.66	79.55	SINGLE RESIDENTIAL
LOT 54	3460.12	30.00	SINGLE RESIDENTIAL
LOT 55	3683.40	30.71	SINGLE RESIDENTIAL
LOT 56	3168.84	75.20	SINGLE RESIDENTIAL
LOT 57	902990.54	423.24	EXISTING SINGLE RESIDENTIAL
LOT 58	13858.65	111.39	COMMERCIAL
LOT 59	3554.31	50.05	SINGLE RESIDENTIAL
LOT 60	3340.48	46.96	SINGLE RESIDENTIAL
BLOCK 1	34810.91	N/A	R.O.W (20.0m)
BLOCK 2	19530.98	N/A	OPEN SPACE - STORM WATER MANAGEMENT
BLOCK 3	57653.41	N/A	OPEN SPACE - ENVIRONMENTAL CONSTRAINT AREA
BLOCK 4	3059.81	N/A	OPEN SPACE - ENVIRONMENTAL CONSTRAINT AREA
TOTAL	1224918.37		
	121.9ha		

NOTES:
 1. Property boundaries are approximate
 2. Potential development area: ±26.8ha

EcoVue Consulting Services Inc.


 311 George St. N., Suite 200
 Peterborough ON K9J 3H3
 Tel: 705-876-8340 Fax: 705-742-8343
 www.ecovueconsulting.com

DRAWN BY:	PROJECT No.:
MC/TB	21-2207
APPROVED BY:	HORIZ. SCALE:
	1:2000
REVISION DATE:	PLOT DATE:
MAY 02, 2023	MAY 02, 2023

WOODVIEW GOLF SUBDIVISION
 ERIC CHALLENGER
 65 NORTHEY'S BAY ROAD
 PART OF LOTS 6 AND 7, CON 6 SOUTHERN DIVISION
 GEOG. TWP. OF BURLEIGH
 TOWNSHIP OF NORTH KAWARTHA
 COUNTY OF PETERBOROUGH

Map NK-1


Township of North Kawartha Land Use Schedule



- ### Land Use Designation
- Commercial
 - Crown Lands & Provincial Parks
 - Extractive Industrial
 - Natural Core Area
 - Parks & Conservation
 - Recreation Commercial
 - Rural
 - Rural Settlement
 - Trailer Park
 - Waste Management Area
 - Waterfront Residential
 - Aggregate Resource Overlay

- ### Overlays
- Waste Management Assessment Area
 - Special Sections
 - First Nations
 - Settlement Areas
 - Floodplain
 - Aggregate Resource Overlay


- ### Base Features
- Railroad Track
 - Road
 - Road Jurisdiction
 - County Roads
 - Provincial Highways
 - Private Roads
 - Township Roads
 - Watercourse
 - Municipal Boundaries
 - Parcel
 - Lots and Concessions
 - Waterbody
 - Aggregate Resource Overlay






Disclaimer:
Description Official Plan for the Municipality of Trent Lakes
Credits This map is illustrative only. Do not rely on this map for legal administrative purposes. Do not rely on it as being a precise indicator of routes, locations of features, or as a guide to navigation. This map may contain cartographic errors or omissions.

The information on this map adheres to the County of Peterborough's Disclaimer and Terms of Use & Disclaimers as outlined on the Peterborough County website, <https://www.ptbcocounty.ca/en/governing/terms-of-use--disclaimers.aspx>.

Map data compiled from various sources.
Projection: Universal Transverse Mercator, Zone 17
Datum: North American Datum 1983





Projection: Web Mercator 


The Ontario Ministry of Natural Resources and Forestry shall not be liable in any way for the use of, or reliance upon, this map or any information on this map. This map should not be used for: navigation, a plan of survey, routes, nor locations.

Imagery Copyright Notices: Ontario Ministry of Natural Resources and Forestry; NASA Landsat Program; First Base Solutions Inc.; Aéro-Photo (1961) Inc.; DigitalGlobe Inc.; U.S. Geological Survey.

© Copyright for Ontario Parcel data is held by King's Printer for Ontario and its licensors and may not be reproduced without permission.



SPIA-HVA Map




Legend

- Source Protection Areas
- Highly Vulnerable Aquifers
- Assessment Parcel with Address

This map should not be relied on as a precise indicator of routes or locations, nor as a guide to navigation. The Ontario Ministry of Environment, Conservation and Parks (MECP) shall not be liable in any way for the use or any information on this map, of, or reliance upon, this map.



SPIA-IPZ Map



Legend

- Source Protection Areas
- Intake Protection Zone 1
- Intake Protection Zone 2
- Intake Protection Zone 3
- Assessment Parcel with Address

This map should not be relied on as a precise indicator of routes or locations, nor as a guide to navigation. The Ontario Ministry of Environment, Conservation and Parks (MECP) shall not be liable in any way for the use or any information on this map, of, or reliance upon, this map.



Key Map
1:30,000

LEGEND

- [Dashed line] EXISTING SUBJECT PROPERTY
- [Thin grey line] EXISTING PARCEL FABRIC
- [Green hatched area] EXISTING UNEVALUATED WETLAND (RETRIEVED FROM LIO)
- [Dashed line] EXISTING DRIVEWAY
- [Thin grey line] EXISTING STRUCTURE
- [Blue line] EXISTING WATERCOURSE
- [Yellow dashed line] EXISTING WETLAND BUFFER (30m)
- [Pink dashed line] WETLAND SETBACK (30m) (PROVIDED BY PALMER ENVIRONMENTAL CONSULTING - EIS)
- [Red dashed line] EXISTING WATERBODY (30m) AND WATERCOURSE (30m) BUFFER
- [Dotted line] TOP OF BANK (APPROX.)
- [Dotted line] BOTTOM OF BANK (APPROX.)
- [Diagonal hatched area] EXISTING HAMLET DESIGNATION
- [Dotted line] EXISTING ENVIRONMENTAL CONSTRAINT DESIGNATION
- [Grey shaded area] POTENTIAL DEVELOPMENT AREA

LOT/BLOCK No.	AREA (sq.m)	FRONTAGE (m)	DESCRIPTION
LOT 1	4783.57	61.15	SINGLE RESIDENTIAL
LOT 2	3408.64	30.00	SINGLE RESIDENTIAL
LOT 3	3300.13	30.00	SINGLE RESIDENTIAL
LOT 4	3301.11	30.00	SINGLE RESIDENTIAL
LOT 5	3314.76	30.29	SINGLE RESIDENTIAL
LOT 6	3237.29	33.01	SINGLE RESIDENTIAL
LOT 7	3339.38	40.02	SINGLE RESIDENTIAL
LOT 8	3270.67	46.71	SINGLE RESIDENTIAL
LOT 9	3388.28	39.18	SINGLE RESIDENTIAL
LOT 10	3466.92	30.00	SINGLE RESIDENTIAL
LOT 11	3453.61	30.74	SINGLE RESIDENTIAL
LOT 12	3365.67	30.00	SINGLE RESIDENTIAL
LOT 13	3306.61	36.28	SINGLE RESIDENTIAL
LOT 14	3858.06	30.00	SINGLE RESIDENTIAL
LOT 15	4263.06	30.00	SINGLE RESIDENTIAL
LOT 16	3558.58	30.00	SINGLE RESIDENTIAL
LOT 17	3012.91	31.56	SINGLE RESIDENTIAL
LOT 18	3000.00	30.00	SINGLE RESIDENTIAL
LOT 19	3613.75	30.00	SINGLE RESIDENTIAL
LOT 20	3084.62	30.50	SINGLE RESIDENTIAL
LOT 21	3000.00	30.00	SINGLE RESIDENTIAL
LOT 22	3211.25	30.00	SINGLE RESIDENTIAL
LOT 23	3229.44	30.00	SINGLE RESIDENTIAL
LOT 24	3023.03	30.00	SINGLE RESIDENTIAL
LOT 25	3187.62	34.00	SINGLE RESIDENTIAL
LOT 26	3282.71	50.00	SINGLE RESIDENTIAL
LOT 27	3456.28	78.29	SINGLE RESIDENTIAL
LOT 28	3001.71	30.00	SINGLE RESIDENTIAL
LOT 29	3042.31	33.51	SINGLE RESIDENTIAL
LOT 30	3008.95	33.00	SINGLE RESIDENTIAL
LOT 31	3040.53	32.00	SINGLE RESIDENTIAL
LOT 32	3001.98	30.00	SINGLE RESIDENTIAL
LOT 33	3325.57	30.00	SINGLE RESIDENTIAL
LOT 34	3494.84	30.00	SINGLE RESIDENTIAL
LOT 35	3099.62	31.00	SINGLE RESIDENTIAL
LOT 36	3058.54	33.00	SINGLE RESIDENTIAL
LOT 37	3013.89	35.00	SINGLE RESIDENTIAL
LOT 38	3152.30	38.00	SINGLE RESIDENTIAL
LOT 39	3038.45	38.00	SINGLE RESIDENTIAL
LOT 40	3464.75	52.02	SINGLE RESIDENTIAL
LOT 41	3990.02	45.00	SINGLE RESIDENTIAL
LOT 42	3830.12	54.95	SINGLE RESIDENTIAL
LOT 43	3387.85	53.32	SINGLE RESIDENTIAL
LOT 44	3221.57	44.47	SINGLE RESIDENTIAL
LOT 45	3189.74	46.11	SINGLE RESIDENTIAL
LOT 46	3161.21	45.60	SINGLE RESIDENTIAL
LOT 47	3802.31	45.29	SINGLE RESIDENTIAL
LOT 48	3021.52	45.98	SINGLE RESIDENTIAL
LOT 49	3049.31	40.00	SINGLE RESIDENTIAL
LOT 50	3145.97	40.00	SINGLE RESIDENTIAL
LOT 51	3165.29	40.00	SINGLE RESIDENTIAL
LOT 52	3128.95	40.00	SINGLE RESIDENTIAL
LOT 53	3311.66	79.55	SINGLE RESIDENTIAL
LOT 54	3460.12	30.00	SINGLE RESIDENTIAL
LOT 55	3683.40	30.71	SINGLE RESIDENTIAL
LOT 56	3168.84	75.20	SINGLE RESIDENTIAL
LOT 57	902930.54	423.24	EXISTING SINGLE RESIDENTIAL
LOT 58	13858.65	111.39	COMMERCIAL
LOT 59	3554.31	50.05	SINGLE RESIDENTIAL
LOT 60	3340.48	46.96	SINGLE RESIDENTIAL
BLOCK 1	34810.91	N/A	R.O.W (20.0m)
BLOCK 2	19530.98	N/A	OPEN SPACE - STORM WATER MANAGEMENT
BLOCK 3	57653.41	N/A	OPEN SPACE - ENVIRONMENTAL CONSTRAINT AREA
BLOCK 4	3059.81	N/A	OPEN SPACE - ENVIRONMENTAL CONSTRAINT AREA
TOTAL	1224918.37		
	121.9ha		

NOTES:
 1. Property boundaries are approximate
 2. Potential development area: ±26.8ha

EcoVue Consulting Services Inc.

 311 George St. N., Suite 200
 Peterborough ON K9J 3H3
 Tel: 705-876-8340 Fax: 705-742-8343
 www.ecovueconsulting.com

DRAWN BY:	PROJECT No.:
MC/TB	21-2207
APPROVED BY:	HORIZ. SCALE:
	1:2000
REVISION DATE:	PLOT DATE:
MAY 02, 2023	MAY 02, 2023

WOODVIEW GOLF SUBDIVISION
 ERIC CHALLENGER
 65 NORTHEY'S BAY ROAD
 PART OF LOTS 6 AND 7, CON 6 SOUTHERN DIVISION
 GEOG. TWP. OF BURLEIGH
 TOWNSHIP OF NORTH KAWARTHA
 COUNTY OF PETERBOROUGH



Appendix B
Test Pit Logs

TABLE 1: TEST PIT LOGS
65 Northeys Bay Road, Township of North Kawartha - Test Pit Investigation
 Technician: James Goodwin
 Cambium Reference No. 15101-001
 Completed: November 4, 2022



Test Pit ID	Depth (mbgs ¹)	Soil Sample	Material Description	Depth (m)	DPT ² (Blows/150 mm)
TP101-22 17T 728027.6 m E, 4941799.3 m N 102.69 m rel	0.0 - 0.30 0.30 - 0.40	GS1 GS2	TOPSOIL: Dark brown silt, some sand, frequent organics, moist Grey weathered/fractured bedrock, interbedded with silt, dry to moist Test pit terminated at 0.40 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	2
				0.15 - 0.30 0.30 - 0.45	4 50/100
TP102-22 17T 727971.8 m E, 4941769.0 m N 104.36 m rel	0.0 - 0.30 0.30 - 0.40 0.40 - 0.43	GS1 GS2	TOPSOIL: Dark brown silt, some sand, frequent organics, moist CLAYEY SILT: Dark brown, clayey silt, trace sand, firm to stiff, DTPL (Grain size analysis (GSA): 0% Gravel, 5% Sand, 69% Silt, 26% Clay) Grey weathered/fractured bedrock, interbedded with silt, dry to moist Test pit terminated at 0.43 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	6
				0.15 - 0.30 0.30 - 0.45	6 50/50
TP103-22 17T 727899.9 m E, 4941716.4 m N 107.69 m rel	0.0 - 0.25 0.25 - 0.50	GS1 GS2	TOPSOIL: Dark brown silt, some sand, frequent organics, moist SANDY SILT: Light brown, sandy silt, some gravel, some clay compact, dry to moist (GSA: 11% Gravel, 26% Sand, 52% Silt, 11% Clay) Test pit terminated at 0.50 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	6
				0.15 - 0.30 0.30 - 0.45	10 50/75
TP104-22 17T 727781.4 m E, 4941659.7 m N 111.70 m rel	0.0		Bedrock was encountered at ground surface -Fissures of up to 0.15 m in width were encountered in the bedrock, resembling karst		N/A
TP105-22 17T 727717.8 m E, 4941638.0 m N 112.14 m rel	0.0		Bedrock was encountered at ground surface -Fissures of up to 0.15 m in width were encountered in the bedrock, resembling karst		N/A
TP106-22 17T 727665.7 m E, 4941562.2 m N 112.71 m rel	0.0		Bedrock was encountered at ground surface -Fissures of up to 0.15 m in width were encountered in the bedrock, resembling karst		N/A
TP107-22 17T 727752.3 m E, 4941538.4 m N 111.70 m rel	0.0		Bedrock was encountered at ground surface -Fissures of up to 0.15 m in width were encountered in the bedrock, resembling karst		N/A
TP108-22 17T 727780.8 m E, 4941462.0 m N 110.73 m rel	0.0 - 0.45	GS1	SILTY SAND: Brown, silty sand, compact to dense, dry to moist -organics encountered to 0.10 mbgs Test pit terminated at 0.45 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	3
				0.15 - 0.30 0.30 - 0.45 0.45 - 0.60	14 29 50/25
TP109-22 17T 727845.4 m E, 4941581.2 m N 111.60 m rel	0.0 - 0.10	GS1	TOPSOIL: Dark brown silt, some sand, frequent organics, moist Test pit terminated at 0.10 mbgs on bedrock Test pit open and dry upon completion		N/A
TP110-22 17T 727894.1 m E, 4941502.8 m N 111.16 m rel	0.0 - 0.10	GS1	TOPSOIL: Dark brown silt, some sand, frequent organics, moist Test pit terminated at 0.10 mbgs on bedrock Test pit open and dry upon completion		N/A
TP111-22 17T 727947.3 m E, 4941440.6 m N 110.15 m rel	0.0 - 0.10	GS1	TOPSOIL: Dark brown, clayey silt, trace sand, frequent organics, APL Test pit terminated at 0.10 mbgs on bedrock Test pit open and dry upon completion		N/A

1. mbgs = metres below ground surface

2. Dynamic probe penetration test, consisting of driving a 19 mm diameter steel rod 150 mm into the soil with an 8 kg hammer falling 750 mm.

TABLE 1: TEST PIT LOGS
65 Northeys Bay Road, Township of North Kawartha - Test Pit Investigation
 Technician: James Goodwin
 Cambium Reference No. 15101-001
 Completed: November 4, 2022



Test Pit ID	Depth (mbgs ¹)	Soil Sample	Material Description	Depth (m)	DPT ² (Blows/150 mm)
Test Pit ID	Depth (mbgs ¹)	Soil Sample	Material Description	Depth (m)	DPT ² (Blows/150 mm)
TP112-22 17T 727944.4 m E, 4941369.3 m N 110.24 m rel	0.0		Bedrock was encountered at ground surface -Fissures of up to 0.20 m in width and at least 1.5 m deep were encountered in the bedrock, resembling karst		N/A
TP113-22 17T 727981.4 m E, 4941281.1 m N 109.90 m rel	0.0 - 0.20	GS1	TOPSOIL: Brown, clayey silt, some gravel, frequent organics, APL Test pit terminated at 0.20 mbgs on bedrock Test pit open and dry upon completion		N/A
TP114-22 17T 727999.6 m E, 4941227.7 m N 109.01 m rel	0.0 - 0.10	GS1	TOPSOIL: Dark brown silt, some sand, frequent organics, moist Test pit terminated at 0.10 mbgs on bedrock -Fissures of up to 0.15 m in width and at least 1.5 m deep were encountered in the bedrock, resembling karst Test pit open and dry upon completion		N/A
TP115-22 17T 728024.4 m E, 4941147.9 m N 108.97 m rel	0.0 - 0.10	GS1	TOPSOIL: Dark brown silt, some sand, frequent organics, moist Test pit terminated at 0.10 mbgs on bedrock -Fissures of up to 0.15 m in width and at least 1.5 m deep were encountered in the bedrock, resembling karst Test pit open and dry upon completion		N/A
TP116-22 17T 728075.2 m E, 4941094.4 m N 103.21 m rel	0.0 - 1.10	GS1	CLAYEY SILT: Brown, clayey silt, trace sand, firm to very stiff, DTPL -organics encountered from surface to 0.15 mbgs -some cobbles and boulders encountered at 0.75 mbgs Test pit terminated at 1.10 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15 0.15 - 0.30 0.30 - 0.45 0.45 - 0.60 0.60 - 0.75 0.75 - 0.90 0.90 - 1.05	1 3 6 9 8 9 50/25
TP117-22 17 T 728095.7 m E, 4941052.3 m N 103.90 m rel	0.0 - 0.30 0.30 - 0.75 0.75 - 1.35	GS1 GS2 GS3	TOPSOIL: Brown, clayey silt, trace sand, frequent organics, moist CLAYEY SILT: Brown, clayey silt, trace sand, trace gravel, stiff to very hard, DTPL SILTY SAND: Brown, silty sand, some gravel, trace clay, compact to dense, dry to moist -cobbles and boulders encountered throughout Test pit terminated at 1.35 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15 0.15 - 0.30 0.30 - 0.45 0.45 - 0.60 0.60 - 0.75 1.20 - 1.35 1.35 - 1.50	3 9 26 23 8 32 50/25
TP118-22 17T 728131.7 m E, 4941104.3 m N 102.97 m rel	0.0 - 0.45 0.45 - 1.20	GS1 GS2	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SANDY SILT: Dark brown, sandy silt, trace clay, trace organics, compact to dense, moist -some cobbles and boulders encountered at 0.90 mbgs Test pit terminated at 1.20 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15 0.15 - 0.30 0.30 - 0.45 0.45 - 0.60 0.60 - 0.75 0.75 - 0.90	1 3 7 20 48 50
TP119-22 17 T 728165.1 m E, 4941218.3 m N 102.00 m rel	0.0 - 0.40 0.40 - 1.00 1.00 - 1.10	GS1 GS2 GS3	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SANDY SILT: Brown, sandy silt, some clay, weathered bedrock/shale throughout Grey weathered/fractured bedrock, interbedded with silt, dry to moist Test pit terminated at 1.10 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15 0.15 - 0.30 0.30 - 0.45 0.45 - 0.60 0.60 - 0.75	3 6 12 30 50/75
TP120-22 17T 728163.6 m E, 4941299.4 m N 102.70 m rel	0.0 - 0.15	GS1	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist Test pit terminated at 0.15 mbgs on bedrock Test pit open and dry upon completion		N/A
TP121-22 17T 4941364.7 m E, 4920940.9 m N 102.18 m rel	0.0 - 0.25	GS1	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist Test pit terminated at 0.25 mbgs on bedrock Test pit open and dry upon completion		N/A
TP122-22 17 T 728235.9 m E, 4941270.6 m N 100.27 m rel	0.0 - 0.25 0.25 - 0.40	GS1 GS2	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SANDY SILT: Brown, sandy silt, trace clay, trace gravel, compact, dry to moist Test pit terminated at 0.40 mbgs on bedrock Test pit open and dry upon completion		N/A
TP123-22 17T 728240.3 m E, 4941353.5 m N 100.17 m rel	0.0 - 0.20 0.20 - 1.30 1.30 - 2.64	GS1	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist Test pit terminated at 0.20 mbgs on bedrock Test pit open and dry upon completion		N/A
TP124-22 17T 728171.7 m E, 4941414.6 m N 103.09 m rel	0.0 - 0.25 0.25 - 1.10	GS1 GS2	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SILTY GRAVEL: Brown, silty gravel, some clay, trace sand, compact to dense, dry to moist (GSA: 50% Gravel, 7% Sand, 26% Silt, 17% Clay) Test pit terminated at 1.10 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15 0.15 - 0.30 0.30 - 0.45 0.45 - 0.60 0.60 - 0.75 0.75 - 0.90 0.90 - 1.05	1 5 10 18 24 35 50/100

1. mbgs = metres below ground surface

2. Dynamic probe penetration test, consisting of driving a 19 mm diameter steel rod 150 mm into the soil with an 8 kg hammer falling 750 mm.

TABLE 1: TEST PIT LOGS
65 Northeys Bay Road, Township of North Kawartha - Test Pit Investigation
 Technician: James Goodwin
 Cambium Reference No. 15101-001
 Completed: November 4, 2022



Test Pit ID	Depth (mbgs) ¹	Soil Sample	Material Description	Depth (m)	DPT ² (Blows/150 mm)
TP125-22 17T 728098.3 m E, 4941459.0 m N 104.94 m rel	0.0 - 0.25 0.25 - 0.65	GS1 GS2	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SILT AND CLAY: Brown, silt and clay, some sand, trace gravel, very stiff to hard, APL (GSA: 1% Gravel, 11% Sand, 46% Silt, 42% Clay) Test pit terminated at 0.65 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	1
				0.15 - 0.30	5
				0.30 - 0.45	30
				0.45 - 0.60	50/125
TP126-22 17T 728080.2 m E, 4941211.9 m N 106.76 m rel	0.0 - 0.25 0.25 - 1.10	GS1 GS2	TOPSOIL: Brown, clayey silt, frequent organics, moist SANDY GRAVEL: Brown, sandy gravel, some silt, trace clay, compact to dense, moist to wet (GSA: 54% Gravel, 28% Sand, 10% Silt, 8% Clay) -cobble and boulders encountered throughout Test pit terminated at 1.10 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	1
				0.15 - 0.30	6
				0.30 - 0.45	10
				0.45 - 0.60	23
				0.60 - 0.75	24
0.75 - 0.90	35				
TP127-22 17T 728072.6 m E, 4941320.4 m N 105.94 m rel	0.0 - 0.25 0.25 - 0.60	GS1 GS2	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SANDY SILT: Brown, sandy silt, trace clay, compact, moist Test pit terminated at 0.60 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	1
				0.15 - 0.30	5
				0.30 - 0.45	8
				0.45 - 0.60	50/125
TP128-22 17T 728041.2 m E, 4941464.4 m N 106.35 m rel	0.0 - 0.95	GS1	SILTY SAND: Brown, silty sand, trace gravel, compact, dry to moist -organics encountered from surface to 0.30 mbgs -cobbles encountered from 0.60 mbgs to 0.85 mbgs Test pit terminated at 0.95 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	1
				0.15 - 0.30	5
				0.30 - 0.45	10
				0.45 - 0.60	50/100
TP129-22 17T 728005.8 m E, 4941556.3 m N 104.10 m rel	0.0 - 0.45	GS1	SANDY SILT: Brown, sandy silt, trace clay, trace gravel, compact to dense, moist to wet (GSA: 1% Gravel, 28% Sand, 63% Silt, 8% Clay) -organics encountered from surface to 0.15 mbgs Test pit terminated at 0.45 mbgs on bedrock Test pit open with minimal water pooling at the base of the test pit upon completion	0.0 - 0.15	1
				0.15 - 0.30	5
				0.30 - 0.45	50
TP130-22 17T 728059.1 m E, 4941628.0 m N 102.46 m rel	0.0 - 0.20 0.20 - 0.40	GS1 GS2	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SANDY SILT: Light brown, sandy silt, some gravel, trace clay, compact, moist to wet Test pit terminated at 0.40 mbgs on bedrock Test pit open and dry upon completion		N/A
TP131-22 17T 728140.1 m E, 4941678.4 m N 101.97 m rel	0.0 - 0.15 0.20 - 0.40	GS1 GS2	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist SILTY SAND: Brown, silty sand, some clay, compact, moist to wet (GSA: 0% Gravel, 51% Sand, 32% Silt, 17% Clay) Test pit terminated at 0.40 mbgs on bedrock Test pit open and dry upon completion		N/A
TP132-22 17 T 728084.3 m E, 4941758.9 m N 105.63 m rel	0.0 0.30 0.30 - 0.75	GS1 GS2	SANDY SILT: Brown, sandy silt, trace clay, trace gravel, loose to compact, moist Grey weathered/fractured bedrock, interbedded with silt, some sand and trace clay, moist to wet Test pit terminated at 0.75 mbgs on bedrock Test pit open and dry upon completion	0.0 - 0.15	1
				0.15 - 0.30	4
				0.30 - 0.45	10
				0.45 - 0.60	37
				0.60 - 0.75	50/100
TP133-22 17T 728084.3 m E, 4941758.9 m N 102.26 m rel	0.0 - 0.20	GS1	TOPSOIL: Dark brown silt, some sand, trace to some clay, frequent organics, moist Test pit terminated at 0.20 mbgs on bedrock Test pit open and dry upon completion		N/A

1. mbgs = metres below ground surface

2. Dynamic probe penetration test, consisting of driving a 19 mm diameter steel rod 150 mm into the soil with an 8 kg hammer falling 750 mm.



Appendix C
Test Well Records

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Help Desk (Toll Free) at 1-888-396-9355.
- **All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Ministry Use Only

Address of Well Location (County/District/Municipality) **PETERBOROUGH** Township **BURLEIGH** Lot **E27** Concession **6**
 RR#/Street Number/Name **37 NORTHYS BAY ROAD** City/Town/Village **WOODVIEW** Site/Compartment/Block/Tract etc.
 GPS Reading NAD **83** Zone **17** Easting **727735** Northing **4991450** Unit Make/Model **ETREX** Mode of Operation: Undifferentiated Averaged
 Differentiated, specify

Log of Overburden and Bedrock Materials (see instructions)

General Colour	Most common material	Other Materials	General Description	Depth	
				From	Metres To
GREY	LIMESTONE		FRACTURED	0	12
GREY	LIMESTONE		HARD	12	37
RED	GRANITE		HARD	37	72
GREY	GRANITE		HARD	72	130
BLACK	GRANITE		HARD	130	155
GREY	GRANITE		HARD	155	200
PINK	GRANITE		POOROUS	200	205
GREY	GRANITE		HARD	205	290

*** ALL MEASUREMENTS IN IMPERIAL ***

Hole Diameter

Depth	Metres	Diameter
From	To	Centimetres
0	20	8 3/4
20	290	6 1/8

Water Record

Water found at **200 m** Kind of Water Fresh Sulphur Gas Salty Minerals Other:

After test of well yield, water was Clear and sediment free Other, specify

Chlorinated Yes No

Construction Record

Inside diam centimetres	Material	Wall thickness centimetres	Depth	
			From	To
6 5/8	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized	188	0	20

Casing

Steel Fibreglass Plastic Concrete Galvanized

Screen

Outside diam Steel Fibreglass Plastic Concrete Galvanized Slot No.

No Casing or Screen

Open hole **20 290**

Test of Well Yield

Pumping test method	Draw Down		Recovery	
	Time min	Water Level Metres	Time min	Water Level Metres
SUBMERSIBLE				
Pump intake set at (metres) 200	Static Level	27		
Pumping rate - (litres/min) 6 gpm	1	30	1	104
Duration of pumping 1 hrs + 0 min	2	34.1	2	102.3
Final water level end of pumping 106.1 metres	3	36.9	3	101.6
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	4	38.2	4	100.1
Recommended pump depth 250 metres	5	40	5	99.8
Recommended pump rate 6 gpm (litres/min)	10	45.1	10	82.2
If flowing give rate - (litres/min)	15	50.4	15	69.6
	20	56.4	20	55.8
	25	63.6	25	44.2
If pumping discontinued, give reason.	30	69.7	30	36.2
	40	83.9	40	31.6
	50	96	50	29.1
	60	106.9	60	27

Plugging and Sealing Record Annular space Abandonment

Depth set at - Metres	Material and type (bentonite slurry, neat cement slurry) etc.	Volume Placed (cubic metres)
From	To	
0	20	NEAT CEMENT & BENTONITE SLURRY
		14 FT ³

Method of Construction

Cable Tool Rotary (air) Diamond Digging Rotary (conventional) Air percussion Jetting Other Rotary (reverse) Boring Driving

Water Use

Domestic Industrial Public Supply Other Stock Commercial Not used Irrigation Municipal Cooling & air conditioning

Final Status of Well

Water Supply Recharge well Unfinished Abandoned, (Other) Observation well Abandoned, insufficient supply Dewatering Test Hole Abandoned, poor quality Replacement well

Location of Well

In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.

Audit No. **Z 73155** Date Well Completed **2007 05 14**

Was the well owner's information package delivered? Yes No

Well Contractor/Technician Information

Name of Well Contractor **WENSLEY WATER WELLS LTD** Well Contractor's Licence No. **6578**
 Business Address (street name, number, city etc.) **1122 LAKEFIELD**
 Name of Well Technician (last name, first name) **ERIC WENSLEY** Well Technician's Licence No. **632**
 Signature of Technician/Contractor **[Signature]** Date Submitted **2007 05 14**

Ministry Use Only

Data Source Contractor **6578**

Date Received **2007 05 14** Date of Inspection **2007 05 14**

Remarks Well Record Number

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Help Desk (Toll Free) at 1-888-396-9355.
- **All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Ministry Use Only

Address of Well Location (County/District/Municipality) **PETERBOROUGH** Township **BURLEIGH** Lot **6-7** Concession **6**
 RR#/Street Number/Name **37 NORTHS BAY ROAD** City/Town/Village **WOODVIEW** Site/Compartment/Block/Tract etc.
 GPS Reading NAD **83** Zone **17** Easting **728097** Northing **4941520** Unit Make/Model **ETREX** Mode of Operation: Undifferentiated Averaged
 Differentiated, specify

Log of Overburden and Bedrock Materials (see instructions)

General Colour	Most common material	Other Materials	General Description	Depth - Metres	
				From	To
GREY	LIMESTONE	CLAY	FRACTURED	0	12
GREY	LIMESTONE		HARD	12	24
RED	GRANITE		HARD	24	40
WHITE	GRANITE		HARD	40	58
WHITE	GRANITE		FRACTURED	58	65

ALL MEASUREMENTS IN IMPERIAL

Hole Diameter			Construction Record				Test of Well Yield					
Depth From	Depth To	Diameter Centimetres	Inside diam centimetres	Material	Wall thickness centimetres	Depth From	Depth To	Pumping test method	Draw Down Time min	Water Level Metres	Recovery Time min	Water Level Metres
0	20	8 3/4	6 5/8	Steel	188	0	20	SUBMERSIBLE				
20	65	6 1/8						Pump intake set at - (metres) 60	Static Level	31.1		
Water Record			Screen				Pumping rate - (litres/min) 18 GPM					
Water found at - Metres / Kind of Water			Outside diam				Duration of pumping 1 hrs + 0 min					
58' m Fresh <input checked="" type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other:			Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized				Final water level end of pumping 51.5 metres					
Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other:			Slot No.				Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep					
After test of well yield, water was <input checked="" type="checkbox"/> Clear and sediment free <input type="checkbox"/> Other, specify			No Casing or Screen				Recommended pump depth 60 metres					
Chlorinated <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			Open hole <input checked="" type="checkbox"/>				Recommended pump rate 16 GPM (litres/min)					
							If flowing give rate - (litres/min)					
							If pumping discontinued, give reason.					

Plugging and Sealing Record Annular space Abandonment

Depth set at - Metres	Material and type (bentonite slurry, neat cement slurry) etc.	Volume Placed (cubic metres)
0	20 BENTONITE SLURRY	7 FT ³

Location of Well

In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.

Audit No. **Z 73144** Date Well Completed **07 08 23**

Was the well owner's information package delivered? Yes No

Method of Construction

Cable Tool Rotary (air) Diamond Digging
 Rotary (conventional) Air percussion Jetting Other
 Rotary (reverse) Boring Driving

Water Use

Domestic Industrial Public Supply Other
 Stock Commercial Not used
 Irrigation Municipal Cooling & air conditioning

Final Status of Well

Water Supply Recharge well Unfinished Abandoned, (Other)
 Observation well Abandoned, insufficient supply Dewatering
 Test Hole Abandoned, poor quality Replacement well

Well Contractor/Technician Information

Name of Well Contractor **WENSLEY WATER WEL** Well Contractor's Licence No. **6578**
 Business Address (street name, number, city etc.) **RR 2 LAKEFIELD**
 Name of Well Technician (last name, first name) **ERIC WENSLEY** Well Technician's Licence No. **632**
 Signature of Technician/Contractor **[Signature]** Date Submitted **2007 09 08**

Ministry Use Only

Data Source Contractor **6578**

Date Received **AUG 09 2007** Date of Inspection **YYYY MM DD**

Remarks Well Record Number

Address of well Location (Street Number/Name, RR) 37 NORTHS BAY ROAD Township BURLEIGH Lot 6-7 Concession 6
 County/District/Municipality PETERBOROUGH City/Town/Village WOOD VIEW Province Ontario Postal Code K0L2H0
 UTM Coordinates Zone 17TQJ115 Northing 4941569 GPS Unit Make CARMIN Model ETREX Mode of Operation: Undifferentiated Averaged
 NAD 83 Differentiated, specify _____

Overburden and Bedrock Materials (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (Metres) From	Depth (Metres) To
GREY	LIMESTONE	CLAY	FRACTURED	0	20
RED	GRANITE		HARD	20	43
BLACK	GRANITE		HARD	43	92
RED	GRANITE		HARD	92	102

*** ALL MEASUREMENTS IN IMPERIAL ***

Annular Space/Abandonment Sealing Record

Depth Set at (Metres) From	Depth Set at (Metres) To	Type of Sealant Used (Material and Type)	Volume Placed (Cubic Metres)
0	20	BENTONITE SLURRY	7 FT ³

Results of Well Yield Testing

Time (Min)	Draw Down		Recovery	
	Water Level (Metres)	Time (Min)	Water Level (Metres)	Time (Min)
Static Level	14.6	Static Level		
1	19.1	1	99.3	
2	26.5	2	99	
3	29	3	98.4	
4	30	4	97.9	
5	41.3	5	97.1	
10	52.7	10	94.3	
15	61	15	91.8	
20	70.9	20	87	
25	81.6	25	84.3	
30	86.7	30	81.9	
40	90.1	40	76.1	
50	95.1	50	71.3	
60	99.6	60	68.7	

Check box if after test of well yield, water was:
 Clear and sand free
 Cannot develop to sand-free state
 If pumping discontinued, give reason: _____
 Pumping test method SUBMERSIBLE
 Pump intake set at (metres) 100'
 Pumping rate (Litres/min) 0.56 gpm
 Duration of pumping 1 hrs + min
 Final water level end of pumping (Metres) 99.6
 Recommended pump type Shallow Deep
 Recommended pump depth 100 Metres
 Recommended pump rate (Litres/min) 0.56 gpm
 If flowing give rate (Litres/min) _____

Method of Construction


<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring
<input type="checkbox"/> Rotary (Air)	<input type="checkbox"/> Digging	<input checked="" type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning	
<input checked="" type="checkbox"/> Air percussion	<input type="checkbox"/> Boring	<input type="checkbox"/> Industrial		
<input type="checkbox"/> Other, specify _____				

Status of Well

<input checked="" type="checkbox"/> Water Supply	<input type="checkbox"/> Dewatering Well	<input type="checkbox"/> Observation and/or Monitoring Hole
<input type="checkbox"/> Replacement Well	<input type="checkbox"/> Abandoned, Insufficient Supply	<input type="checkbox"/> Alteration (Construction)
<input type="checkbox"/> Test Hole	<input type="checkbox"/> Abandoned, Poor Water Quality	<input type="checkbox"/> Other, specify _____
<input type="checkbox"/> Recharge Well	<input type="checkbox"/> Abandoned; other, specify _____	

Location of Well

Please provide a map below showing:
 - all property boundaries, and measurements sufficient to locate the well in relation to fixed points,
 - an arrow indicating the North direction
 - detailed drawings can be provided as attachments no larger than legal size (8.5" by 14")
 - digital pictures of inside of well can also be provided



Water Details

Water found at Depth <u>100</u> Metres	Kind of Water <input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals
Water found at Depth _____ Metres	Kind of Water <input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals
Water found at Depth _____ Metres	Kind of Water <input type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals

Casing and Screen Used

<input type="checkbox"/> Galvanized	<input type="checkbox"/> Galvanized	Casing and Well Details Diameter of the Hole (Centimetres) <u>6 1/8</u> Depth of the Hole (Metres) <u>102'</u> Wall Thickness (Metres) <u>188</u> Inside Diameter of the Casing (Metres) <u>6 5/8</u> Depth of the Casing (Metres) <u>20'</u>
<input checked="" type="checkbox"/> Steel	<input type="checkbox"/> Steel	
<input type="checkbox"/> Fibreglass	<input type="checkbox"/> Fibreglass	
<input type="checkbox"/> Plastic	<input type="checkbox"/> Plastic	
<input type="checkbox"/> Concrete	<input type="checkbox"/> Concrete	

No Casing and Screen Used

Open Hole

Disinfected? Yes No

Date Well Completed (yyyy/mm/dd) 2007/12/03 Was the well owner's information package delivered? Yes No Date the Well Record and Package Delivered to Well Owner (yyyy/mm/dd) 2007/12/20

Well Contractor and Well Technician Information

Business Name of Well Contractor WENSLEY WATER WELL LTD Well Contractor's Licence No. 6578
 Business Address (Street No./Name, number, RR) RR 2 LAKEFIELD Municipality PETERBOROUGH
 Province ONT Postal Code K0L2H0 Business E-mail Address _____
 Bus. Telephone No. (inc. area code) 705 652 1629 Name of Well Technician (Last Name, First Name) ERIC WENSLEY
 Well Technician's Licence No. 0632 Signature of Technician _____ Date Submitted (yyyy/mm/dd) 2007/12/20

Ministry Use Only

Audit No. 269758 Well Contractor No. _____
 Date Received (yyyy/mm/dd) JAN 28 2008 Date of Inspection (yyyy/mm/dd) _____
 Remarks _____

Tag#: A328193

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: ERIC Last Name/Organization: CHALLENGER E-mail Address: ECHALLENGER@GMAIL.COM
 Mailing Address (Street Number/Name): 37 Northways Bay Rd Municipality: North Kawartha Province: ON Postal Code: K0L2W0 Telephone No. (inc. area code): 2893149947

Well Location

Address of Well Location (Street Number/Name): 65 Northways Bay Rd Township: North Kawartha Lot: Concession:
 County/District/Municipality: Peterborough County City/Town/Village: Lakefield Province: Ontario Postal Code: K0L2W0
 UTM Coordinates Zone: Easting: Northing: NAD 83 17 72 81 24 49 41 11 15
 Municipal Plan and Sublot Number: Other:

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	Depth (m/ft) To
Brown	Sandy loam	stones	Dry	0	3'
Gray	Limestone		Hard / Fractures	3'	19'
Red/green	Granite		Soft / Fractures	19	35
Pink/Red	Granite		Hard / Soft Seams	35	60
Pink/white	Granite		Hard	60	100

Annular Space		
Depth Set at (m/ft) From	To	Type of Sealant Used (Material and Type)
0	20'	3/8 Bentonite chip Quick Grout
		Volume Placed (m³/ft³): 3 Bags 140 L

Results of Well Yield Testing					
After test of well yield, water was:		Draw Down		Recovery	
<input checked="" type="checkbox"/> Clear and sand free	<input type="checkbox"/> Other, specify	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
If pumping discontinued, give reason:		Static Level	14'		
Pump intake set at (m/ft): 100'		1	15'	1	18
Pumping rate (l/min / GPM): 10 gal/min		2	16'	2	18'10"
Duration of pumping: 1 hrs + min		3	16'4"	3	14
Final water level end of pumping (m/ft): 19'8"		4	16'9"	4	
If flowing give rate (l/min/GPM):		5	17'2"	5	
Recommended pump depth (m/ft): 90'		10	17'7"	10	
Recommended pump rate (l/min/GPM): 8 gal/min		15	18'	15	
Well production (l/min/GPM): 10+ gal/min		20	18'6"	20	
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		25	18'9"	25	
		30	18'11"	30	
		40	19'	40	
		50	19'4"	50	
		60	19'8"	60	

Method of Construction		Well Use		
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input checked="" type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input type="checkbox"/> Domestic	<input type="checkbox"/> Municipal	<input type="checkbox"/> Dewatering
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input checked="" type="checkbox"/> Test Hole	<input type="checkbox"/> Monitoring
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning	
<input type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial		
<input type="checkbox"/> Other, specify		<input type="checkbox"/> Other, specify		


Construction Record - Casing				Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		<input type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input checked="" type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify <input type="checkbox"/> Other, specify
			From	To	
6 1/4"	steel	0.88	+2'	20'	

Construction Record - Screen				
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

Water Details		Hole Diameter	
Water found at Depth (m/ft): 25'	Kind of Water: <input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m/ft) From: 0	To: 20' Diameter (cm/in): 10"
Water found at Depth (m/ft): 60'	Kind of Water: <input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m/ft) From: 20	To: 100' Diameter (cm/in): 6"
Water found at Depth (m/ft):	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify		

Well Contractor and Well Technician Information

Business Name of Well Contractor: Business Address (Street Number/Name): Province: Postal Code: Business E-mail Address: Well Contractor's Licence No.: Municipality: Bus. Telephone No. (inc. area code): Name of Well Technician (Last Name, First Name): Well Technician's Licence No.: Signature of Technician and/or Contractor: Date Submitted:



Comments: 90m south on Northways Bay rd 375m East to well

Well owner's information package delivered: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered: 2/28/2020	Date Work Completed: 2/28/2020
Ministry Use Only		Received
Audit No. Z390218		

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent legal document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- **All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

Ministry Use Only			
MUN		CON	LOT

PETER BORDUGH **SOUTH BURLEIGH 7 6**
 RR#/Street Number/Name **# 37 NORTHEYS BAY ROAD** City/Town/Village **WOODUIEW** Site/Compartment/Block/Tract etc.
 GPS Reading NAD Zone Easting Northing Unit Make/Model Mode of Operation:
 8.3 17 727680 4941793 **GARMIN** Undifferentiated Averaged
 Differentiated, specify

Log of Overburden and Bedrock Materials (see instructions)


General Colour	Most common material	Other Materials	General Description	Depth From	Metres To
GREY	LIMESTONE	BOULDERSS	FILL	0	.5
GREY	LIMESTONE	RED SHALE	BEDROCK	.5	7
GREY	GRANITE		BEDROCK	7	73
BLACK	GRANITE			73	80
GREY	GRANITE		BEDROCK	80	91

**TOTAL WELL CAPACITY 12 GPM
RECOMENDED PUMP SETTING 120 FEET**

Hole Diameter			Construction Record				Test of Well Yield																																																												
Depth From	Metres To	Diameter Centimetres	Inside diam centimetres	Material	Wall thickness centimetres	Depth From	Metres To	Pumping test method	Time min	Draw Down Water Level Metres	Time min	Recovery Water Level Metres																																																							
0	7.9	23						PUMP																																																											
7.9	91	15	16	Steel <input checked="" type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized <input type="checkbox"/>	4.77	0	7.9	Pump intake set at - (metres) 12	1	8.63	1	12.0																																																							
Water Record			Screen				Test of Well Yield																																																												
Water found at Metres	Kind of Water		Outside diam	Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized <input type="checkbox"/>	Slot No.	<table border="1"> <thead> <tr> <th>Time min</th> <th>Draw Down Water Level Metres</th> <th>Time min</th> <th>Recovery Water Level Metres</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>8.41</td> <td>1</td> <td>10.17</td> </tr> <tr> <td>2</td> <td>9.12</td> <td>2</td> <td>9.21</td> </tr> <tr> <td>3</td> <td>9.73</td> <td>3</td> <td>8.63</td> </tr> <tr> <td>4</td> <td>10.47</td> <td>4</td> <td>8.11</td> </tr> <tr> <td>5</td> <td>11.01</td> <td>5</td> <td>8.01</td> </tr> <tr> <td>10</td> <td>12.0</td> <td>10</td> <td>7.92</td> </tr> <tr> <td>15</td> <td>12.0</td> <td>15</td> <td>7.84</td> </tr> <tr> <td>20</td> <td>12.0</td> <td>20</td> <td>7.77</td> </tr> <tr> <td>25</td> <td>12.0</td> <td>25</td> <td>7.71</td> </tr> <tr> <td>30</td> <td>12.0</td> <td>30</td> <td>7.67</td> </tr> <tr> <td>40</td> <td>12.0</td> <td>40</td> <td>7.65</td> </tr> <tr> <td>50</td> <td>12.0</td> <td>50</td> <td>7.64</td> </tr> <tr> <td>60</td> <td>12.0</td> <td>60</td> <td>7.64</td> </tr> </tbody> </table>						Time min	Draw Down Water Level Metres	Time min	Recovery Water Level Metres	1	8.41	1	10.17	2	9.12	2	9.21	3	9.73	3	8.63	4	10.47	4	8.11	5	11.01	5	8.01	10	12.0	10	7.92	15	12.0	15	7.84	20	12.0	20	7.77	25	12.0	25	7.71	30	12.0	30	7.67	40	12.0	40	7.65	50	12.0	50	7.64	60	12.0	60	7.64
Time min	Draw Down Water Level Metres	Time min	Recovery Water Level Metres																																																																
1	8.41	1	10.17																																																																
2	9.12	2	9.21																																																																
3	9.73	3	8.63																																																																
4	10.47	4	8.11																																																																
5	11.01	5	8.01																																																																
10	12.0	10	7.92																																																																
15	12.0	15	7.84																																																																
20	12.0	20	7.77																																																																
25	12.0	25	7.71																																																																
30	12.0	30	7.67																																																																
40	12.0	40	7.65																																																																
50	12.0	50	7.64																																																																
60	12.0	60	7.64																																																																
91	Fresh <input checked="" type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: _____	Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized <input type="checkbox"/>				Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep																																																													
After test of well yield, water was	Clear and sediment free <input type="checkbox"/> Other, specify _____		No Casing or Screen			Recommended pump rate (litres/min) 40																																																													
Chlorinated <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			<input checked="" type="checkbox"/> Open hole			If flowing give rate - (litres/min) 20																																																													

Plugging and Sealing Record Annular space Abandonment

Depth set at - Metres From	To	Material and type (bentonite slurry, neat cement slurry) etc.	Volume Placed (cubic metres)
0	7.9	NEAT CEMENT	0.31



Method of Construction

Cable Tool Rotary (air) Diamond Digging
 Rotary (conventional) Air percussion Jetting Other
 Rotary (reverse) Boring Driving

Water Use

Domestic Industrial Public Supply Other
 Stock Commercial Not used
 Irrigation Municipal Cooling & air conditioning

Final Status of Well

Water Supply Recharge well Unfinished Abandoned, (Other)
 Observation well Abandoned, insufficient supply Dewatering
 Test Hole Abandoned, poor quality Replacement well

Well Contractor/Technician Information

Name of Well Contractor **JOE LEGGER SONS DRILLING** Well Contractor's Licence No. **7052**
 Business Address (street name, number, city etc.) **RR #3 BANCROFT KOC 1C0**
 Name of Well Technician (last name, first name) **LEGG JOE** Well Technician's Licence No. **7-1879**
 Signature of Technician/Contractor **Joe Legger** Date Submitted _____

Ministry Use Only

Data Source _____ Contractor **7052**
 Date Received **JAN 18 2005** Date of Inspection _____
 Remarks _____ Well Record Number _____

found

Well 3



Ministry of the Environment

Well Tag No. (Place Sticker and/or Print Below) A 062849

Well Record Regulation 903 Ontario Water Resources Act Page 1 of 1

Well Owner's Information: First Name ERIC, Last Name CHALLENGER, E-mail Address, Well Constructed by Well Owner

Mailing Address (Street Number/Name, RR) 63 JAMIESON CRES, Municipality WINDYBROOK, Province ONT, Postal Code M1A 1M1, Telephone No. (inc. area code) 905-461-1100

Part A Construction and/or Major Alteration of a Well: Address of Well Location (Street Number/Name, RR) 37 NORWICH BAY ROAD, Township GUELPH, Lot 7, Concession 2

Country/District/Municipality PETERBOROUGH, City/Town/Village USSOUVEREUX, Province Ontario, Postal Code K9C 4Z1

UTM Coordinates: Zone 18Q, Easting 1177219, Northing 4994157, GPS Unit Make GARMIN, Model UTE 4, Mode of Operation: Undifferentiated, Averaged

Overburden and Bedrock Materials table with columns: General Colour, Most Common Material, Other Materials, General Description, Depth (Metres) From, To. Includes handwritten entries like GREY LIMONITE CLAY, SAND, SILT, and FRACTURED.


Annular Space/Abandonment Sealing Record table with columns: Depth Set at (Metres) From, To, Type of Sealant Used (Material and Type), Volume Placed (Cubic Metres). Includes handwritten entry: 0 to 20 BLU-GRADE SURS 10 LITERS.

Results of Well Yield Testing table with columns: Draw Down (Time, Water Level, Recovery), Pumping rate (Litres/min), Duration of pumping, Final water level end of pumping (Metres), Recommended pump type, Recommended pump depth, Recommended pump rate (Litres/min), If flowing give rate (Litres/min).

Method of Construction and Water Use checkboxes: Cable Tool, Rotary, Air percussion, Diamond, Jetting, Driving, Digging, Boring, Public, Domestic, Livestock, Irrigation, Industrial, Commercial, Municipal, Test Hole, Monitoring, Not used, Dewatering, Cooling & Air Conditioning.

Status of Well checkboxes: Water Supply, Replacement Well, Test Hole, Recharge Well, Dewatering Well, Abandoned, Insufficient Supply, Abandoned, Poor Water Quality, Abandoned, other, specify, Observation and/or Monitoring Hole, Alteration (Construction), Other, specify.

Location of Well: Please provide a map below showing: all property boundaries, and measurements sufficient to locate the well in relation to fixed points, an arrow indicating the North direction, detailed drawings can be provided as attachments no larger than legal size (8.5" by 14"), vicinal pictures of inside of well can also be provided.



Water Details checkboxes: Water found at Depth (Metres), Kind of Water (Fresh, Salty, Sulphur, Minerals, Gas).

Casing Used, Screen Used, Casing and Well Details checkboxes: Galvanized, Steel, Fibreglass, Plastic, Concrete, Diameter of the Hole (Centimetres), Depth of the Hole (Metres), Wall Thickness (Metres).

Date Well Completed (yyyy/mm/dd) 2007/12/19, Was the well owner's information package delivered? Yes [x] No, Date the Well Record and Package Delivered to Well Owner (yyyy/mm/dd) 2007/12/18

Well Contractor and Well Technician Information: Business Name of Well Contractor WEAVER WATER WELL, Well Contractor's Licence No. 615 17 18, Business Address (Street No./Name, number, RR) RR #2 LARLICO, Municipality PETERBORO, Province ONT, Postal Code K9C 1A9, Business E-mail Address

No Casing and Screen Used checkboxes: Open Hole, Disinfected? Yes [x] No

Bus. Telephone No. (inc. area code) 705-771-1229, Name of Well Technician (Last Name, First Name) ERIC WEAVER, Well Technician's Licence No. K161312, Signature of Technician, Date Submitted (yyyy/mm/dd) 2007/12/20

Ministry Use Only: Audit No. 269759, Well Contractor No., Date Received (yyyy/mm/dd), Date of Inspection (yyyy/mm/dd), Remarks




Appendix D
Grain Size Analysis



Grain Size Distribution Chart

Project Number: 15101-001 **Client:** Woodview Golf - Eric Challenger
Project Name: Hydrogeological & Geotechnical Assessment- Woodview Golf Subdivision
Sample Date: November 4, 2022 **Sampled By:** James Goodwin - Cambium Inc.
Location: TP 102-22 GS 2 **Depth:** 0.3 m to 0.4 m **Lab Sample No:** S-22-1677

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
TP 102-22	GS 2	0.3 m to 0.4 m	0	5	69	26	23.6
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Clayey Silt trace Sand		ML	0.0190	0.0044	-	-	-

Additional information available upon request

Issued By: *John Bind*
 (Senior Project Manager)


Date Issued: January 9, 2023



Grain Size Distribution Chart

Project Number: 15101-001 **Client:** Woodview Golf - Eric Challenger
Project Name: Hydrogeological & Geotechnical Assessment- Woodview Golf Subdivision
Sample Date: November 4, 2022 **Sampled By:** James Goodwin - Cambium Inc.
Location: TP 103-22 GS 2 **Depth:** 0.3 m to 0.5 m **Lab Sample No:** S-22-1678

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
TP 103-22	GS 2	0.3 m to 0.5 m	11	26	52	11	8.8
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Sandy Silt some Gravel some Clay		ML	0.0700	0.0330	0.0018	38.89	8.64

Additional information available upon request

Issued By: *John Baird*
 (Senior Project Manager)

Date Issued: January 9, 2023




Grain Size Distribution Chart



Project Number: 15101-001 **Client:** Woodview Golf - Eric Challenger
Project Name: Hydrogeological & Geotechnical Assessment- Woodview Golf Subdivision
Sample Date: November 4, 2022 **Sampled By:** James Goodwin - Cambium Inc.
Location: TP 124-22 GS 2 **Depth:** 25.3 m to 1.1 m **Lab Sample No:** S-22-1680

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
TP 124-22	GS 2	25.3 m to 1.1 m	50	7	26	17	10.0
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Silty Gravel some Clay trace Sand		GM	30.000	0.019	-	-	-

Additional information available upon request

Issued By: *John Bind*
 (Senior Project Manager)


Date Issued: January 9, 2023



Grain Size Distribution Chart

Project Number: 15101-001 **Client:** Woodview Golf - Eric Challenger
Project Name: Hydrogeological & Geotechnical Assessment- Woodview Golf Subdivision
Sample Date: November 4, 2022 **Sampled By:** James Goodwin - Cambium Inc.
Location: TP 125-22 GS 2 **Depth:** 0.3 m to 0.7 m **Lab Sample No:** S-22-1681

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
TP 125-22	GS 2	0.3 m to 0.7 m	1	11	46	42	34.4
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Silt and Clay some Sand trace Gravel		ML	0.012	-	-	-	-

Additional information available upon request

Issued By: 
 (Senior Project Manager)

Date Issued: January 9, 2023




Grain Size Distribution Chart



Project Number: 15101-001 **Client:** Woodview Golf - Eric Challenger
Project Name: Hydrogeological & Geotechnical Assessment- Woodview Golf Subdivision
Sample Date: November 4, 2022 **Sampled By:** James Goodwin - Cambium Inc.
Location: TP 126-22 GS 2 **Depth:** 0.3 m to 1.1 m **Lab Sample No:** S-22-1682

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
TP 126-22	GS 2	0.3 m to 1.1 m	54	28	10	8	9.5
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Sandy Gravel some Silt trace Clay		GM	9.6000	1.4000	0.0047	2042.55	43.44

Additional information available upon request

Issued By: *John Baird*
 (Senior Project Manager)


Date Issued: January 9, 2023



Grain Size Distribution Chart

Project Number: 15101-001 **Client:** Woodview Golf - Eric Challenger
Project Name: Hydrogeological & Geotechnical Assessment- Woodview Golf Subdivision
Sample Date: November 4, 2022 **Sampled By:** James Goodwin - Cambium Inc.
Location: TP 129-22 GS 1 **Depth:** 0 m to 0.5 m **Lab Sample No:** S-22-1683

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
TP 129-22	GS 1	0 m to 0.5 m	1	28	63	8	9.3
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Sandy Silt trace Clay trace Gravel		ML	0.049	0.018	0.003	16.33	2.20

Additional information available upon request

Issued By: *John Bind*
 (Senior Project Manager)


Date Issued: January 9, 2023



Grain Size Distribution Chart

Project Number: 15101-001 **Client:** Woodview Golf - Eric Challenger
Project Name: Hydrogeological & Geotechnical Assessment- Woodview Golf Subdivision
Sample Date: November 4, 2022 **Sampled By:** James Goodwin - Cambium Inc.
Location: TP 131-22 GS 2 **Depth:** 0.2 m to 0.4 m **Lab Sample No:** S-22-1684

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
TP 131-22	GS 2	0.2 m to 0.4 m	0	51	32	17	20.9
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Silty Sand some Clay		SM	0.145	0.022	-	-	-

Additional information available upon request

Issued By: *John Bind*
 (Senior Project Manager)

Date Issued: January 9, 2023



Appendix E
MECP Well Records

Water Well Records Summary Report

Produced by Cambium Inc. using MOECP Water Well Information System (WWIS)

All units in meters unless otherwise specified



Well ID: 5100489 **Easting:** 727541 **UTM Zone** 17
Construction Date: 1964-05-25 **Northing:** 4941447 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 14.0 **Water Kind** FRESH **Pump Rate (LPM):** 32
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 32
Water First Found: 12.2 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 1 : 0
Static Level: 9

Layer:	Driller's Description:	Top:	Bottom:
1	MEDIUM SAND	0	0.91
2	LIMESTONE	0.91	14.0

Well ID: 5100493 **Easting:** 727436 **UTM Zone** 17
Construction Date: 1956-01-13 **Northing:** 4941613 **Positional Accuracy:** unknown UTM

Well Depth: 18.3 **Water Kind** FRESH **Pump Rate (LPM):** 5
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:**
Water First Found: 15.9 **Primary Water Use:** Public **Pumping Duration (h:m):** 1 : 0
Static Level: 9

Layer:	Driller's Description:	Top:	Bottom:
1	LIMESTONE	0	18.3

Well ID: 5105607 **Easting:** 727605 **UTM Zone** 17
Construction Date: 1971-06-21 **Northing:** 4942063 **Positional Accuracy:** margin of error : 30 m - 100 m

Well Depth: 18.6 **Water Kind** FRESH **Pump Rate (LPM):** 91
Well Diameter (cm): **Final Status** Water Supply **Recommended Pump Rate:**
Water First Found: 18.6 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 72 : 0
Static Level: 17

Layer:	Driller's Description:	Top:	Bottom:
1	DOLOMITE	0	18.6
1	DOLOMITE	0	18.6

Well ID: 5107514 **Easting:** 727165 **UTM Zone** 17
Construction Date: 1975-07-23 **Northing:** 4941673 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 46.6 **Water Kind** FRESH **Pump Rate (LPM):** 18
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 18
Water First Found: 40.5 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 2 : 30
Static Level: 8

Layer:	Driller's Description:	Top:	Bottom:
1	TOPSOIL	0	0.30
2	CLAY	0.30	4.27
3	LIMESTONE	4.27	17.4
4	GRANITE	17.4	46.6

Well ID: 5107643 **Easting:** 727515 **UTM Zone** 17
Construction Date: 1975-10-20 **Northing:** 4941623 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 44.2 **Water Kind** FRESH **Pump Rate (LPM):** 5
Well Diameter (cm): **Final Status** Water Supply **Recommended Pump Rate:** 5
Water First Found: 38.1 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 1 : 30
Static Level: 12

Layer:	Driller's Description:	Top:	Bottom:
1	PREV. DRILLED	0	13.7
2	LIMESTONE	13.7	44.2

Well ID: 5107704 **Easting:** 727165 **UTM Zone** 17
Construction Date: 1975-12-09 **Northing:** 4941573 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 52.4 **Water Kind** FRESH **Pump Rate (LPM):** 5
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 5
Water First Found: 25.6 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 2 : 0
Static Level: 6

Layer:	Driller's Description:	Top:	Bottom:
1	SAND	0	0.91
2	GRANITE	0.91	25.6
3	GRANITE	25.6	52.4

Well ID: 5107705 **Easting:** 727165 **UTM Zone** 17
Construction Date: 1975-12-09 **Northing:** 4941523 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 83.8 **Water Kind** **Pump Rate (LPM):**
Well Diameter (cm): **Final Status** Abandoned-Su **Recommended Pump Rate:**
Water First Found: **Primary Water Use:** **Pumping Duration (h:m):**
Static Level:

Layer:	Driller's Description:	Top:	Bottom:
1	TOPSOIL	0	0.30
2	LIMESTONE	0.30	6.40
3	GRANITE	6.40	25.6
4	GRANITE	25.6	83.8

Well ID: 5108131 **Easting:** 727165 **UTM Zone** 17
Construction Date: 1976-09-16 **Northing:** 4941573 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 12.2 **Water Kind** FRESH **Pump Rate (LPM):** 23
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 23
Water First Found: 6.71 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 2 : 0
Static Level: 3

Layer:	Driller's Description:	Top:	Bottom:
1	TOPSOIL	0	0.30
2	CLAY	0.30	0.91
3	LIMESTONE	0.91	12.2

Well ID: 5108546 **Easting:** 727915 **UTM Zone** 17
Construction Date: 1977-08-31 **Northing:** 4942323 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 10.1 **Water Kind** FRESH **Pump Rate (LPM):** 114
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 23
Water First Found: 9.75 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 3 : 0
Static Level: 4

Layer:	Driller's Description:	Top:	Bottom:
1	TOPSOIL	0	0.30
2	GRANITE	0.30	2.74
3	GRANITE	2.74	10.1

Well ID: 5110164 **Easting:** 727515 **UTM Zone** 17
Construction Date: 1981-03-13 **Northing:** 4941573 **Positional Accuracy:** margin of error : 100 m - 300 m

Well Depth: 22.9 **Water Kind** FRESH **Pump Rate (LPM):** 36
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 36
Water First Found: 22 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 3 : 10
Static Level: 12

Layer:	Driller's Description:	Top:	Bottom:
1	TOPSOIL	0	0.30
2	CLAY	0.30	3.05
3	LIMESTONE	3.05	19.8
4	GRANITE	19.8	22.9

Well ID: 5112348 **Easting:** 728294 **UTM Zone** 17
Construction Date: 1987-06-02 **Northing:** 4942017 **Positional Accuracy:** unknown UTM

Well Depth: 19.8 **Water Kind** FRESH **Pump Rate (LPM):** 23
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 27
Water First Found: 17.7 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 1 : 0
Static Level: 0

Layer:	Driller's Description:	Top:	Bottom:
1	PEAT	0	1.22
2	DOLOMITE	1.22	19.8

Well ID: 5116135 **Easting:** 728074 **UTM Zone** 17
Construction Date: 1993-03-04 **Northing:** 4942561 **Positional Accuracy:** unknown UTM

Well Depth: 17.4 **Water Kind** FRESH **Pump Rate (LPM):** 68
Well Diameter (cm): 15.2 **Final Status** Water Supply **Recommended Pump Rate:** 45
Water First Found: 15.2 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 1 : 0
Static Level: 2

Layer:	Driller's Description:	Top:	Bottom:
1	UNKNOWN TYPE	0	0.30
2	CLAY	0.30	3.66
3	BOULDERS	3.66	9.14
4	GRANITE	9.14	17.4

Well ID: 5118187
Construction Date: 1999-08-16

Easting: 728294
Northing: 4942017

UTM Zone 17
Positional Accuracy: unknown UTM

Well Depth: 91.4
Well Diameter (cm):
Water First Found: 57.9
Static Level: 6

Water Kind FRESH
Final Status Water Supply
Primary Water Use: Domestic

Pump Rate (LPM): 45
Recommended Pump Rate: 45
Pumping Duration (h:m): 1 : 0

Layer:	Driller's Description:	Top:	Bottom:
1	LIMESTONE	0	1.22
2	LIMESTONE	1.22	13.7
	8k° V@-		
	8k° V@-		

Well ID: 5119939
Construction Date: 2004-07-09

Easting: 727984
Northing: 4941050

UTM Zone 17
Positional Accuracy: margin of error : 10 - 30 m

Well Depth: 30.5
Well Diameter (cm): 15.9
Water First Found:
Static Level: 4

Water Kind
Final Status Water Supply
Primary Water Use: Domestic

Pump Rate (LPM): 18
Recommended Pump Rate: 18
Pumping Duration (h:m): 1 : 0

Layer:	Driller's Description:	Top:	Bottom:
1		0	1.5
2	LIMESTONE	1.5	14
3	LIMESTONE	14	24.1
4	GRANITE	24.1	30.5

Well ID: 5120069
Construction Date: 2004-12-20

Easting: 727478
Northing: 4941692

UTM Zone 17
Positional Accuracy: margin of error : 10 - 30 m

Well Depth: 67
Well Diameter (cm): 16
Water First Found: 65
Static Level: 10

Water Kind FRESH
Final Status Water Supply
Primary Water Use: Domestic

Pump Rate (LPM): 30
Recommended Pump Rate: 45
Pumping Duration (h:m): 1 : 0

Layer:	Driller's Description:	Top:	Bottom:
1	CLAY	0	2
	⊙ - ou\ V-		
8k° V@-		

Well ID: 5120141
Construction Date: 2005-01-18

Easting: 727680
Northing: 4941793

UTM Zone 17
Positional Accuracy: unknown UTM

Well Depth: 91
Well Diameter (cm):
Water First Found: 91
Static Level: 8

Water Kind FRESH
Final Status Water Supply
Primary Water Use: Domestic

Pump Rate (LPM): 40
Recommended Pump Rate: 40
Pumping Duration (h:m): 1 :

Layer:	Driller's Description:	Top:	Bottom:
1	LIMESTONE	0	0.5
	LIMESTONE	0	
	8k° V@-		
	8k° V@-		
	GRANITE		

Well ID: 5120788
Construction Date: 2006-07-24

Easting: 727793
Northing: 4941883

UTM Zone 17
Positional Accuracy: margin of error : 10 - 30 m

Well Depth: 48.8
Well Diameter (cm):
Water First Found: 44.8
Static Level: 5

Water Kind FRESH
Final Status Water Supply
Primary Water Use: Domestic

Pump Rate (LPM): 68
Recommended Pump Rate: 45
Pumping Duration (h:m): 1 : 0

Layer:	Driller's Description:	Top:	Bottom:
1	CLAY	0	0.91
	8k° V@-	0	
	8k° V@-		
	8k° V@-		

Well ID: 7045863
Construction Date: 2007-06-29

Easting: 727735
Northing: 4941450

UTM Zone 17
Positional Accuracy: margin of error : 10 - 30 m

Well Depth: 88.4
Well Diameter (cm): 16.8
Water First Found: 61
Static Level: 8

Water Kind FRESH
Final Status Water Supply
Primary Water Use: Commerical

Pump Rate (LPM): 27
Recommended Pump Rate: 27
Pumping Duration (h:m): 1 :

Layer:	Driller's Description:	Top:	Bottom:
1	LIMESTONE	0	3.66

GRANITE
 GRANITE
 GRANITE 39.6
 GRANITE
 GRANITE
 GRANITE
 GRANITE

Well ID: 7047985
Construction Date: 2007-08-09

Easting: 728097
Northing: 4941520

UTM Zone 17
Positional Accuracy: margin of error : 10 - 30 m

Well Depth: 19.8 **Water Kind** FRESH **Pump Rate (LPM):** 82
Well Diameter (cm): **Final Status** Water Supply **Recommended Pump Rate:** 73
Water First Found: 17.7 **Primary Water Use:** Commerical **Pumping Duration (h:m):** 1 :
Static Level: 9

Layer:	Driller's Description:	Top:	Bottom:
1	LIMESTONE	0	3.66
	LIMESTONE		
	8k° V@-		
	8k° V@-		
	GRANITE		

Well ID: 7101360
Construction Date: 2008-01-28

Easting: 728115
Northing: 4941569

UTM Zone 17
Positional Accuracy: margin of error : 10 - 30 m

Well Depth: 31.1 **Water Kind** FRESH **Pump Rate (LPM):** 2
Well Diameter (cm): 16.8 **Final Status** Water Supply **Recommended Pump Rate:** 2
Water First Found: 30.5 **Primary Water Use:** Irrigation **Pumping Duration (h:m):** 1 : 0
Static Level: 4

Layer:	Driller's Description:	Top:	Bottom:
1	LIMESTONE	0	6.1
2	GRANITE	6.1	13.1
3	GRANITE	13.1	28.0
4	GRANITE	28.0	31.1

Well ID: 7101361 **Easting:** 728077 **UTM Zone** 17
Construction Date: 2008-01-28 **Northing:** 4941597 **Positional Accuracy:** margin of error : 10 - 30 m

Well Depth: 13.1 **Water Kind** FRESH **Pump Rate (LPM):** 55
Well Diameter (cm): 16.8 **Final Status** Water Supply **Recommended Pump Rate:** 55
Water First Found: 11 **Primary Water Use:** Irrigation **Pumping Duration (h:m):** 1 : 0
Static Level: 5

Layer:	Driller's Description:	Top:	Bottom:
1	LIMESTONE	0	6.1
2	GRANITE	6.1	11
3	GRANITE	11	13.1

Well ID: 7225245 **Easting:** 727535 **UTM Zone** 17
Construction Date: 2014-08-11 **Northing:** 4941636 **Positional Accuracy:** margin of error : 30 m - 100 m

Well Depth: 61 **Water Kind** Untested **Pump Rate (LPM):** 36
Well Diameter (cm): 15.9 **Final Status** Water Supply **Recommended Pump Rate:** 36
Water First Found: 57.9 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 1 :
Static Level: 14

Layer:	Driller's Description:	Top:	Bottom:
1	TOPSOIL	0	0.61
2	LIMESTONE	0.61	44.2
3	GRANITE	44.2	61

Well ID: 7352477 **Easting:** 727616 **UTM Zone** 17
Construction Date: 2020-01-30 **Northing:** 4941716 **Positional Accuracy:** margin of error : 30 m - 100 m

Well Depth: 85.3 **Water Kind** FRESH **Pump Rate (LPM):** 45
Well Diameter (cm): 15.9 **Final Status** Water Supply **Recommended Pump Rate:** 45
Water First Found: 83.8 **Primary Water Use:** Domestic **Pumping Duration (h:m):** 1 :
Static Level: 8

Layer:	Driller's Description:	Top:	Bottom:
1	TOPSOIL	0	0.30
2	SHALE	0.30	4.88
3	ROCK	4.88	48.8
4	GRANITE	48.8	79.3
5	GRANITE	79.3	85.3



Appendix F

Water Budget



Water Balance Calculations

THORNTHWAITE-TYPE MONTHLY WATER-BALANCE MODEL												
<i>modified from Dingman 2002: Box 7-3 (pg 315) using ET model of Hamon (1963)</i>												
	Input Data					Computed Values						
											Surplus 355 mm/yr	
Weather Station Location:	Peterborough Trent U					Latitude:	44.2 degree					
Solar Declination (degree)	-20.6	-12.6	-1.5	10.0	19.0	23.1	21.0	13.4	2.6	-9.0	-18.5	-23.0
DayLength (hr)*	9.1	10.3	11.8	13.3	14.6	15.3	14.9	13.8	12.3	10.8	9.5	8.7
Available Water Storage Capacity	0.18 m/m				Root Depth	460 mm			SOILmax	82.8 mm		

MONTHLY WATER BALANCE DATA													
Temperatures in C, water-balance terms in mm.													
Month:	J	F	M	A	M	J	J	A	S	O	N	D	Year
TEMPERATURE (T)	-8.4	-6.5	-1.3	6.3	12.8	18.0	20.7	19.4	15.0	8.4	2.4	-4.0	
PRECIPITATION (P)	57.3	48.8	56.5	66.4	88.7	83.0	73.6	87.0	92.4	77.0	85.5	66.0	882
RAIN	22.4	23.1	34.0	60.9	88.7	83.0	73.6	87.0	92.4	75.7	73.3	35.0	749
SNOW	35	26	23	6	0	0	0	0	0	1	12	31	133
MELT FACTOR (F)	0.00	0.00	0.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.40	0.00	
PACK	73	99	121	0	0	0	0	0	0	0	7	38	
MELT	0	0	0	127	0	0	0	0	0	1	5	0	133
INPUT (W)	22	23	34	188	89	83	74	87	92	77	78	35	882
POTENTIAL ET (PET)	0	0	0	41	70	97	115	98	65	39	22	0	548
NET INPUT (ΔW)	22	23	34	147	19	-14	-41	-11	27	38	56	35	
SOIL MOISTURE (SOIL)	83	83	83	83	83	70	42	37	64	83	83	83	
ΔSOIL	0	0	0	0	0	-13	-27	-5	27	19	0	0	
ET	0	0	0	41	70	96	101	92	65	39	22	0	527
SURPLUS=W-ET- Δ SOIL	22	23	34	147	19	0	0	0	0	19	56	35	355

Notes:													
Precipitation, Rain, Temperature, and Latitude are inputted parameters													
SOILmax = available water storage capacity * root depth													
m = month													
D = Day length (hrs) = $2 \cdot \cos^{-1}(-\tan(\text{Latitude}) \cdot \tan(\text{Declination}))/0.2618$ [calculation is in radians]													
$SNOW_m = P_m - RAIN_m$													
$F_m = 0$ if $T_m \leq 0^\circ C$; $F_m = 0.167 \cdot T_m$ if $0^\circ C < T_m < 6^\circ C$; $F_m = 1$ if $T_m \geq 6^\circ C$													
$PACK_m = (1 - F_m) \cdot (SNOW_m + PACK_{m-1})$													
$MELT = F_m \cdot (SNOW_m + PACK_{m-1})$													
$W_m = RAIN_m + MELT_m$													
$PET = 0$ if $T_m < 0$; otherwise $PET = 2.98 \cdot 0.611 \cdot \exp(17.3 \cdot T_m / (T_m + 237)) / (T_m + 237.2) \cdot \text{Number of days in month}$ [Hamon ET model (1963)]													
$\Delta W_m = W_m - PET_m$													
$SOIL = \min\{\Delta W_m + SOIL_{m-1}, SOIL_{max}\}$, if $\Delta W_m > 0$; otherwise $SOIL = SOIL_{m-1} \cdot \exp(\Delta W / SOIL_{max})$													
$\Delta SOIL = SOIL_{m-1} - SOIL_m$													
ET = PET if $W_m > PET$; otherwise, $ET = W_m - \Delta SOIL$													

<u>Areas</u>	Development Area		Nondevelopment Site Area		*Total area
SITE AREA (m ²)	268000	26.8	951083.4	95.108336	1219083 (m ²)
WETLAND AREA (m ²)	4792	0.4792	478158	47.8158	
PAVED AREA (m ²)	34810.91	3.481091	0	0	
LANDSCAPED AREA (m ²)	228397.1	22.83971	472925.4	47.292536	

Total Infiltration Factors

Development area 0.65 (Flat 0.3, Medium combinations of clay and loam 0.2, Cultivated woodland mix 0.15)
 Nondevelopment area 0.5 (Flat 0.3, Tight impervious clay 0.1, Cultivated 0.1)

* This is the total infiltration of which some discharges back to the stream as base flow. The infiltration factor is determined by summing a factor for topography, soils and cover.

<u>Topography</u>	Flat Land, average slope < 0.6 m/km	0.3
	Rolling Land, average slope 2.8 m to 3.8 m/km	0.2
	Hilly Land, average slope 28 m to 47 m/km	0.1
<u>Soils</u>	Tight impervious clay	0.1
	Medium combinations of clay and loam	0.2
	Open Sandy loam	0.4
<u>Cover</u>	Cultivated Land	0.1
	Woodland	0.2

Source: ON stormwater planning and design manual 2003

Development Area

<u>Surplus water</u>		<u>Infiltrated water</u>			
Depth from surplus	0.355 m/yr	Depth from surplus	0.23075 m/yr		
	0.0009726 m/day		0.000632 m/day		
From Landscape	81080.97 m ³ /yr	Infiltrated from landscape	52702.63 m ³ /yr		
	222.1396 m ³ /day	Total Water	144.3908 m ³ /day	runoff	77.74887 m ³ /day

Nondevelopment area

<u>Surplus water</u>		<u>Infiltrated water</u>			
Depth from surplus	0.355 m/yr	Depth from surplus	0.1775 m/yr		
	9.73E-04 m/day		0.000486 m/day		
From Landscape	167888.5 m ³ /yr	Infiltrated from landscape	83944.25 m ³ /yr		
	459.9685 m ³ /day	Total Water	229.9843 m ³ /day	runoff	229.9843 m ³ /day
		Sum of Total Water	374.375 m ³ /day		

Predicted Nitrate Concentrations

Projected Lots maintaining Nitrate Concentrations 10 mg/L

# Lots	60
Qe	60000
Ce	40
Qi	374375
Ci	0.1
Qt	434375
mg/L	5.61



Appendix G Water Quality Sampling Results



FINAL REPORT

CA14820-OCT22 R

15101-001, Woodview Golf

Prepared for

Cambium Inc.

First Page

CLIENT DETAILS		LABORATORY DETAILS	
Client	Cambium Inc.	Project Specialist	Maarit Wolfe, Hon.B.Sc
Address	194 Sophia Street Peterborough, ON K9H 1E5, Canada	Laboratory	SGS Canada Inc.
Contact	Kevin Warner	Address	185 Concession St., Lakefield ON, K0L 2H0
Telephone	705-742-7900	Telephone	705-652-2000
Facsimile		Facsimile	705-652-6365
Email	kevin.warner@cambium-inc.com	Email	Maarit.Wolfe@sgs.com
Project	15101-001, Woodview Golf	SGS Reference	CA14820-OCT22
Order Number		Received	10/31/2022
Samples	Ground Water (1)	Approved	11/14/2022
		Report Number	CA14820-OCT22 R
		Date Reported	11/14/2022

COMMENTS

MAC - Maximum Acceptable Concentration
 AO/OG - Aesthetic Objective / Operational Guideline
 MDL - SGS Method Detection Limit

Temperature of Sample upon Receipt: 9 degrees C
 Cooling Agent Present: Yes
 Custody Seal Present: Yes

Chain of Custody Number: 029831

SIGNATORIES


Maarit Wolfe, Hon.B.Sc


TABLE OF CONTENTS

First Page.....	1
Index.....	2
Results.....	3-5
Exceedance Summary.....	6
QC Summary.....	7-13
Legend.....	14
Annexes.....	15-16



FINAL REPORT

CA14820-OCT22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8
Sample Name Neighbours
House
Sample Matrix Ground Water
Sample Date 31/10/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

General Chemistry

Conductivity	uS/cm	2			1190
Alkalinity	mg/L as CaCO3	2	500		305
Colour	TCU	3	5		< 3
Turbidity	NTU	0.10	5	1	0.30
Dissolved Oxygen	mg/L	1			6.3

Metals and Inorganics

Sulphate	mg/L	2	500		51
Nitrite (as N)	as N mg/L	0.003		1	0.003#<MDL
Nitrate (as N)	as N mg/L	0.006		10	1.42
Nitrate + Nitrite (as N)	as N mg/L	0.006			1.42
Hardness	mg/L as CaCO3	0.05	100		531
Aluminum	µg/L	1	100		3
Silver	µg/L	0.05			< 0.05
Arsenic	µg/L	0.2		10	< 0.2
Barium	µg/L	0.02		1000	367
Beryllium	µg/L	0.007			0.007
Boron	µg/L	2		5000	92
Bismuth	µg/L	0.01			< 0.01
Calcium	mg/L	0.01			156
Cadmium	µg/L	0.003		5	0.011
Chromium	µg/L	0.08		50	0.29



FINAL REPORT

CA14820-OCT22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8
Sample Name Neighbours House
Sample Matrix Ground Water
Sample Date 31/10/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1.2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
Metals and Inorganics (continued)					
Cobalt	µg/L	0.004			0.231
Copper	µg/L	0.2	1000		1.5
Iron	ug/L	7	300		20
Potassium	mg/L	0.009			3.44
Lithium	µg/L	0.1			7.7
Sodium	mg/L	0.01	200	20	56.9
Nickel	µg/L	0.1			0.7
Magnesium	mg/L	0.001			34.5
Manganese	µg/L	0.01	50		0.90
Molybdenum	µg/L	0.04			2.98
Phosphorus	mg/L	0.003			< 0.003
Lead	µg/L	0.01		10	0.10
Antimony	µg/L	0.6		6	< 0.6
Selenium	µg/L	0.04		50	0.23
Silicon	ug/L	20			1120
Tin	µg/L	0.06			< 0.06
Strontium	µg/L	0.02			12800
Titanium	ug/L	0.05			0.26
Thallium	µg/L	0.005			0.020
Uranium	µg/L	0.002		20	5.74
Vanadium	µg/L	0.01			0.43



FINAL REPORT

CA14820-OCT22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8
Sample Name Neighbours
House
Sample Matrix Ground Water
Sample Date 31/10/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
Metals and Inorganics (continued)					
Tungsten	µg/L	0.02			< 0.02
Yttrium	µg/L	0.02			0.05
Zinc	µg/L	2	5000		6
Microbiology					
Total Coliform	cfu/100mL	0		0	0
E. Coli	cfu/100mL	0		0	0
Other (ORP)					
pH	No unit	5	8.5		7.86
Chloride	mg/L	1	250		210

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG /	ODWS_MAC /
				WATER / - - Table 4	WATER / - - Table
				- Drinking Water -	1,2 and 3 -
				Reg O.169_03	Drinking Water -
					Reg O.169_03
				L1	L2

Neighbours House

Hardness	SM 3030/EPA 200.8	mg/L as CaCO3	531	100	
Sodium	SM 3030/EPA 200.8	mg/L	56.9		20



FINAL REPORT

CA14820-OCT22 R

QC SUMMARY

QCR_SubCategory

Method: SM 2130 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Turbidity	EWL0031-NOV22	NTU	0.10	< 0.10	0	10	96	90	110	NA		

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0020-NOV22	mg/L as CaCO3	2	< 2	0	20	100	80	120	NA		

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO5051-NOV22	mg/L	1	<1	0	20	106	80	120	95	75	125
Sulphate	DIO5051-NOV22	mg/L	2	<2	2	20	111	80	120	89	75	125

Anions by IC

Method: EPA300/MA300-Ions1.3 | Internal ref.: ME-CA-IENVIIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Nitrate + Nitrite (as N)	DIO0088-NOV22	mg/L	0.006	<0.006	NA		NA			NA		
Nitrite (as N)	DIO0088-NOV22	mg/L	0.003	<0.003	ND	20	97	90	110	98	75	125
Nitrate (as N)	DIO0088-NOV22	mg/L	0.006	<0.006	ND	20	102	90	110	103	75	125

QC SUMMARY

Colour

Method: SM 2120 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Colour	EWL0035-NOV22	TCU	3	< 3	0	10	100	80	120	NA		

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0020-NOV22	uS/cm	2	< 2	0	20	96	90	110	NA		



FINAL REPORT

CA14820-OCT22 R

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Silver	EMS0010-NOV22	ug/L	0.05	<0.00005	ND	20	105	90	110	105	70	130
Aluminum	EMS0010-NOV22	ug/L	1	<0.001	1	20	105	90	110	123	70	130
Arsenic	EMS0010-NOV22	ug/L	0.2	<0.0002	3	20	102	90	110	111	70	130
Barium	EMS0010-NOV22	ug/L	0.02	<0.00002	1	20	100	90	110	125	70	130
Beryllium	EMS0010-NOV22	ug/L	0.007	<0.000007	0	20	107	90	110	101	70	130
Boron	EMS0010-NOV22	ug/L	2	<0.002	1	20	106	90	110	101	70	130
Bismuth	EMS0010-NOV22	ug/L	0.01	<0.00001	0	20	96	90	110	94	70	130
Calcium	EMS0010-NOV22	mg/L	0.01	<0.01	1	20	102	90	110	105	70	130
Cadmium	EMS0010-NOV22	ug/L	0.003	<0.000003	0	20	105	90	110	97	70	130
Cobalt	EMS0010-NOV22	ug/L	0.004	<0.000004	3	20	106	90	110	116	70	130
Chromium	EMS0010-NOV22	ug/L	0.08	<0.00008	2	20	102	90	110	121	70	130
Copper	EMS0010-NOV22	ug/L	0.2	<0.0002	18	20	105	90	110	116	70	130
Iron	EMS0010-NOV22	ug/L	7	<0.007	0	20	100	90	110	125	70	130
Potassium	EMS0010-NOV22	mg/L	0.009	<0.009	3	20	100	90	110	110	70	130
Lithium	EMS0010-NOV22	ug/L	0.1	<0.0001	2	20	110	90	110	104	70	130
Magnesium	EMS0010-NOV22	mg/L	0.001	<0.001	1	20	98	90	110	93	70	130
Manganese	EMS0010-NOV22	ug/L	0.01	<0.00001	1	20	105	90	110	107	70	130
Molybdenum	EMS0010-NOV22	ug/L	0.04	<0.00004	0	20	103	90	110	118	70	130
Sodium	EMS0010-NOV22	mg/L	0.01	<0.01	3	20	103	90	110	108	70	130
Nickel	EMS0010-NOV22	ug/L	0.1	<0.0001	4	20	105	90	110	107	70	130

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Lead	EMS0010-NOV22	ug/L	0.01	<0.00001	12	20	100	90	110	101	70	130
Phosphorus	EMS0010-NOV22	mg/L	0.003	<0.003	4	20	103	90	110	NV	70	130
Antimony	EMS0010-NOV22	ug/L	0.6	<0.0009	ND	20	105	90	110	124	70	130
Selenium	EMS0010-NOV22	ug/L	0.04	<0.00004	6	20	106	90	110	107	70	130
Silicon	EMS0010-NOV22	ug/L	20	<0.02	4	20	95	90	110	NV	70	130
Tin	EMS0010-NOV22	ug/L	0.06	<0.00006	8	20	108	90	110	NV	70	130
Strontium	EMS0010-NOV22	ug/L	0.02	<0.00002	0	20	102	90	110	102	70	130
Titanium	EMS0010-NOV22	ug/L	0.05	<0.00005	5	20	104	90	110	NV	70	130
Thallium	EMS0010-NOV22	ug/L	0.005	<0.000005	0	20	98	90	110	100	70	130
Uranium	EMS0010-NOV22	ug/L	0.002	<0.000002	3	20	98	90	110	98	70	130
Vanadium	EMS0010-NOV22	ug/L	0.01	<0.00001	15	20	104	90	110	115	70	130
Tungsten	EMS0010-NOV22	ug/L	0.02	<0.00002	ND	20	102	90	110	NV	70	130
Yttrium	EMS0010-NOV22	ug/L	0.02	<0.00002	2	20	104	90	110	NV	70	130
Zinc	EMS0010-NOV22	ug/L	2	<0.002	5	20	100	90	110	111	70	130

QC SUMMARY

Microbiology

Method: OMOE MICROMFDC-E3407A | Internal ref.: ME-CA-IENVIMIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
E. Coli	BAC9011-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							
Total Coliform	BAC9011-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0020-NOV22	No unit	5	NA	0		100			NA		

QC SUMMARY

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND

FOOTNOTES

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY

Industries & Environment - Lakefield: 185 Concession St., Lakefield, ON K0L 2H0 Phone: 705-652-2000 Fax: 705-652-6365 Web: www.sgs.com/environment
 - London: 657 Consortium Court, London, ON, N6E 2S8 Phone: 519-672-4500 Toll Free: 877-848-8060 Fax: 519-672-0361

No: **029831**
 Page **1** of **1**

Received By: **Latie Marchand**
 Received Date: **OCT 31 2022** (mm/dd/yy)
 Received Time: **18:27** (hr : min)

Laboratory Information Section - Lab use only

Received By (signature): *[Signature]*
 Custody Seal Present: Yes No
 Custody Seal Intact: Yes No
 Cooling Agent Present: Yes No Type: **Ice**
 Temperature Upon Receipt (°C): **9.9.9**

LAB LIMS #: **CA14820-oct22**

REPORT INFORMATION
 Company: **Cambium Inc**
 Contact: **Kevin Warner**
 Address: **194 Sophia Street, Peterborough, ON K9H 1E3**
 Phone: **705 742 7900**
 Fax:
 Email: **Kevin.Warner@Cambium-inc.com**

INVOICE INFORMATION
 (same as Report Information)
 Company:
 Contact:
 Address:
 Phone:

Quotation #: _____ P.O. #: **15101-001**
 Project #: **Woodview Golf** Site Location/ID: _____

TURNAROUND TIME (TAT) REQUIRED
 Regular TAT (5-7 days) TAT's are quoted in business days (exclude statutory holidays & weekends). Samples received after 6pm or on weekends: TAT begins next business day
 RUSH TAT (Additional Charges May Apply): 1 Day 2 Days 3 Days 4 Days
PLEASE CONFIRM RUSH FEASIBILITY WITH SGS REPRESENTATIVE PRIOR TO SUBMISSION
 Specify Due Date: _____ *NOTE: DRINKING (POTABLE) WATER SAMPLES FOR HUMAN CONSUMPTION MUST BE SUBMITTED WITH SGS DRINKING WATER CHAIN OF CUSTODY

REGULATIONS
 O.Reg 153/04 O.Reg 406/19
 Table 1 Res/Park Soil Texture:
 Table 2 Ind/Com Coarse
 Table 3 Agri/Other Medium/Fine
 Table _____ Appx. _____
 Soil Volume <350m3 >350m3
 Other Regulations:
 Reg 347/558 (3 Day min TAT)
 PWQO MMER
 CCME Other:
 MISA
 ODWS Not Reportable *See note
 Sewer By-Law:
 Sanitary
 Storm
 Municipality: _____

ANALYSIS REQUESTED

M & I		SVOC	PCB	PHC	VOC	Pest	Other (please specify)		SPLP	TCLP	COMMENTS:
Field Filtered (Y/N)	Metals & Inorganics <small>(incl. Cr, Ni, Cu, Pb, Mo, Ni, Se, Ag, Tl, U, V, Zn)</small>	PAHs only	PCBs <small>Total</small>	F1-F4 + BTEX	F1-F4 only <small>no BTEX</small>	VOCs <small>all incl. BTEX</small>	BTEX only	Pesticides <small>Organochlorine or specify other</small>	Specify tests	Specify tests	
N	Metals & Inorganics <small>(incl. Cr, Ni, Cu, Pb, Mo, Ni, Se, Ag, Tl, U, V, Zn)</small>	PAHs only	PCBs <small>Total</small>	F1-F4 + BTEX	F1-F4 only <small>no BTEX</small>	VOCs <small>all incl. BTEX</small>	BTEX only	Pesticides <small>Organochlorine or specify other</small>	<input type="checkbox"/> Metals <input type="checkbox"/> VOC <input type="checkbox"/> 1,4-Dioxane <input type="checkbox"/> PCB <input type="checkbox"/> B(a)P <input type="checkbox"/> ABN <input type="checkbox"/> Ignit.	<input type="checkbox"/> Metals <input type="checkbox"/> VOC <input type="checkbox"/> PCB <input type="checkbox"/> B(a)P <input type="checkbox"/> ABN <input type="checkbox"/> Ignit.	
	Full Metals Suite <small>(ICP metals plus B(W/S-soil only) Hg, Cr, V)</small>	ICP Metals only <small>Sb, As, Ba, Be, B, Cd, Cr, Co, Cu, Pb, Mo, Ni, Se, Ag, Tl, U, V, Zn</small>	PCBs <small>Total</small>	F1-F4 + BTEX	F1-F4 only <small>no BTEX</small>	VOCs <small>all incl. BTEX</small>	BTEX only	Pesticides <small>Organochlorine or specify other</small>	<input type="checkbox"/> Metals <input type="checkbox"/> VOC <input type="checkbox"/> 1,4-Dioxane <input type="checkbox"/> PCB <input type="checkbox"/> B(a)P <input type="checkbox"/> ABN <input type="checkbox"/> Ignit.	<input type="checkbox"/> Metals <input type="checkbox"/> VOC <input type="checkbox"/> PCB <input type="checkbox"/> B(a)P <input type="checkbox"/> ABN <input type="checkbox"/> Ignit.	

RECORD OF SITE CONDITION (RSC)
 YES NO

SAMPLE IDENTIFICATION	DATE SAMPLED	TIME SAMPLED	# OF BOTTLES	MATRIX
1 Neighbours House	Oct 31/22	4:20	9	SW B
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				

By (NAME): **Warren Young** Signature: *[Signature]* Date: **31/10/22** (mm/dd/yy) Pink Copy - Client
 Issued by (NAME): **Warren Young** Signature: *[Signature]* Date: **31/10/22** (mm/dd/yy) Yellow & White Copy - SGS

I hereby acknowledge that you have been provided direction on sample collection/handling and transportation of samples. (2) Submission of samples to SGS is considered authorization for completion of work. Signatures may appear on this form or be retained on file in electronic form. This document may be sent by email to an unlimited number of addresses for no additional cost. Fax is available upon request. This document is issued by the Company under its General Conditions of Service accessible at www.sgs.com. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.



Cambium Inc.
Peterborough | Barrie
Oshawa | Kingston | Calgary
(866) 217.7900
cambium-inc.com

Project: Woodview Golf (15101-001) Date: Oct 31/22

Subject: Parameter List for SG-5

Contact: Warren Young

Parameter List

- Total Coliform
- E. Coli
- Alkalinity
- pH
- Conductivity
- Chloride
- Nitrite (as N)
- Nitrate (as N)
- Nitrate + Nitrite (as N)
- Sulphate
- Colour
- Turbidity
- Dissolved Oxygen Content
- Hardness
- Silver (total)
- Aluminum (total)
- Arsenic (total)
- Barium (total)
- Beryllium (total)
- Boron (total)
- Bismuth (total)
- Calcium (total)
- Cadmium (total)
- Cobalt (total)
- Chromium (total)
- Copper (total)
- Iron (total)
- Potassium (total)
- Lithium (total)
- Magnesium (total)
- Manganese (total)
- Molybdenum (total)
- Sodium (total)
- Nickel (total)
- Phosphorus (total)
- Lead (total)
- Antimony (total)
- Selenium (total)
- Silicon (total)
- Tin (total)
- Strontium (total)
- Titanium (total)
- Thallium (total)
- Uranium (total)
- Vanadium (total)
- Tungsten (total)
- Yttrium (total)
- Zinc (total)



FINAL REPORT

CA16229-NOV22 R

15101-001, Woodview Golf

Prepared for

Cambium Inc.

First Page

CLIENT DETAILS		LABORATORY DETAILS	
Client	Cambium Inc.	Project Specialist	Jill Campbell, B.Sc.,GISAS
Address	194 Sophia Street Peterborough, ON K9H 1E5, Canada	Laboratory Address	SGS Canada Inc. 185 Concession St., Lakefield ON, K0L 2H0
Contact	Kevin Warner	Telephone	2165
Telephone	705-742-7900	Facsimile	705-652-6365
Facsimile		Email	jill.campbell@sgs.com
Email	kevin.warner@cambium-inc.com	SGS Reference	CA16229-NOV22
Project	15101-001, Woodview Golf	Received	11/01/2022
Order Number		Approved	11/14/2022
Samples	Ground Water (1)	Report Number	CA16229-NOV22 R
		Date Reported	11/14/2022

COMMENTS
<p>MAC - Maximum Acceptable Concentration AO/OG - Aesthetic Objective / Operational Guideline MDL - SGS Method Detection Limit</p> <p>Temperature of Sample upon Receipt: 10 degrees C Cooling Agent Present: Yes Custody Seal Present: Yes Chain of Custody Number: 033288</p>


SIGNATORIES
<p>Jill Campbell, B.Sc.,GISAS</p> 

TABLE OF CONTENTS

First Page.....	1-2
Index.....	3
Results.....	4-6
Exceedance Summary.....	7
QC Summary.....	8-14
Legend.....	15
Annexes.....	16-17



FINAL REPORT

CA16229-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name Pro Shop

Sample Matrix Ground Water

Sample Date 01/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

General Chemistry

Alkalinity	mg/L as CaCO3	2	500		335
Colour	TCU	3	5		< 3
Conductivity	uS/cm	2			1140
Turbidity	NTU	0.10	5	1	0.25
Total Dissolved Solids	mg/L	30	500		743
Ammonia+Ammonium (N)	as N mg/L	0.04			< 0.04
Dissolved Organic Carbon	mg/L	1	5		2

Metals and Inorganics

Sulphate	mg/L	2	500		98
Nitrite (as N)	as N mg/L	0.003		1	0.008
Nitrate (as N)	as N mg/L	0.006		10	2.89
Nitrate + Nitrite (as N)	as N mg/L	0.006			2.90
Hardness	mg/L as CaCO3	0.05	100		515
Silver	µg/L	0.05			< 0.05
Aluminum	µg/L	1	100		7
Arsenic	µg/L	0.2		10	< 0.2
Barium	µg/L	0.02		1000	252
Beryllium	µg/L	0.007			0.018
Boron	µg/L	2		5000	123
Bismuth	µg/L	0.01			< 0.01
Calcium	mg/L	0.01			163
Cadmium	µg/L	0.003		5	0.008



FINAL REPORT

CA16229-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name Pro Shop

Sample Matrix Ground Water

Sample Date 01/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
Metals and Inorganics (continued)					
Chromium	µg/L	0.08		50	0.57
Cobalt	µg/L	0.004			0.352
Copper	µg/L	0.2	1000		2.9
Iron	ug/L	7	300		20
Potassium	mg/L	0.009			2.11
Lithium	µg/L	0.1			9.0
Sodium	mg/L	0.01	200	20	64.2
Magnesium	mg/L	0.001			26.1
Manganese	µg/L	0.01	50		1.27
Molybdenum	µg/L	0.04			2.56
Nickel	µg/L	0.1			0.7
Phosphorus	mg/L	0.003			< 0.003
Lead	µg/L	0.01		10	0.04
Antimony	µg/L	0.6		6	< 0.6
Selenium	µg/L	0.04		50	0.26
Silicon	ug/L	20			2992
Tin	µg/L	0.06			< 0.06
Strontium	µg/L	0.02			11100
Titanium	ug/L	0.05			0.42
Thallium	µg/L	0.005			0.006
Uranium	µg/L	0.002		20	2.80
Vanadium	µg/L	0.01			0.10



FINAL REPORT

CA16229-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name Pro Shop

Sample Matrix Ground Water

Sample Date 01/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

Metals and Inorganics (continued)

Tungsten	µg/L	0.02			< 0.02
Yttrium	µg/L	0.02			0.14
Zinc	µg/L	2	5000		5

Microbiology

Total Coliform	cfu/100mL	0		0	0
E. Coli	cfu/100mL	0		0	0

Other (ORP)

pH	No unit	5	8.5		7.54
Chloride	mg/L	1	250		180

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG /	ODWS_MAC /
				WATER / - - Table 4	WATER / - - Table
				- Drinking Water -	1,2 and 3 -
				Reg O.169_03	Drinking Water -
					Reg O.169_03
				L1	L2

Pro Shop

Total Dissolved Solids	SM 2540C	mg/L	743	500	
Hardness	SM 3030/EPA 200.8	mg/L as CaCO3	515	100	
Sodium	SM 3030/EPA 200.8	mg/L	64.2		20



FINAL REPORT

CA16229-NOV22 R

QC SUMMARY

QCR_SubCategory

Method: SM 2130 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Turbidity	EWL0068-NOV22	NTU	0.10	< 0.10	0	10	100	90	110	NA		

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0070-NOV22	mg/L as CaCO3	2	< 2	2	20	100	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-IENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0067-NOV22	mg/L	0.04	<0.04	ND	10	101	90	110	91	75	125

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO5053-NOV22	mg/L	1	<1	0	20	101	80	120	94	75	125
Sulphate	DIO5053-NOV22	mg/L	2	<2	1	20	108	80	120	79	75	125

Anions by IC

Method: EPA300/MA300-Ions1.3 | Internal ref.: ME-CA-IENVIIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Nitrate + Nitrite (as N)	DIO0111-NOV22	mg/L	0.006	<0.006	NA		NA			NA		
Nitrite (as N)	DIO0111-NOV22	mg/L	0.003	<0.003	18	20	98	90	110	107	75	125
Nitrate (as N)	DIO0111-NOV22	mg/L	0.006	<0.006	0	20	100	90	110	92	75	125

QC SUMMARY

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0076-NOV22	mg/L	1	<1	4	10	100	90	110	93	75	125

Colour

Method: SM 2120 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Colour	EWL0083-NOV22	TCU	3	< 3	ND	10	105	80	120	NA		

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0070-NOV22	uS/cm	2	< 2	0	20	100	90	110	NA		



FINAL REPORT

CA16229-NOV22 R

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Silver	EMS0034-NOV22	ug/L	0.05	< 0.05	ND	20	102	90	110	101	70	130
Aluminum	EMS0034-NOV22	ug/L	1	< 1	0	20	105	90	110	79	70	130
Arsenic	EMS0034-NOV22	ug/L	0.2	< 0.2	3	20	102	90	110	107	70	130
Barium	EMS0034-NOV22	ug/L	0.02	< 0.02	2	20	105	90	110	101	70	130
Beryllium	EMS0034-NOV22	ug/L	0.007	< 0.07	ND	20	99	90	110	97	70	130
Boron	EMS0034-NOV22	ug/L	2	< 2	5	20	104	90	110	NV	70	130
Bismuth	EMS0034-NOV22	ug/L	0.01	< 0.01	ND	20	104	90	110	94	70	130
Calcium	EMS0034-NOV22	mg/L	0.01	< 0.02	1	20	102	90	110	101	70	130
Cadmium	EMS0034-NOV22	ug/L	0.003	< 0.003	ND	20	101	90	110	103	70	130
Cobalt	EMS0034-NOV22	ug/L	0.004	< 0.004	0	20	99	90	110	96	70	130
Chromium	EMS0034-NOV22	ug/L	0.08	< 0.08	ND	20	103	90	110	108	70	130
Copper	EMS0034-NOV22	ug/L	0.2	< 0.2	0	20	99	90	110	99	70	130
Iron	EMS0034-NOV22	ug/L	7	< 7	ND	20	104	90	110	75	70	130
Potassium	EMS0034-NOV22	mg/L	0.009	< 0.009	0	20	109	90	110	NV	70	130
Lithium	EMS0034-NOV22	ug/L	0.1	< 0.1	3	20	100	90	110	93	70	130
Magnesium	EMS0034-NOV22	mg/L	0.001	< 0.001	2	20	101	90	110	102	70	130
Manganese	EMS0034-NOV22	ug/L	0.01	< 0.01	1	20	103	90	110	94	70	130
Molybdenum	EMS0034-NOV22	ug/L	0.04	< 0.04	16	20	103	90	110	96	70	130
Sodium	EMS0034-NOV22	mg/L	0.01	< 0.01	0	20	102	90	110	100	70	130
Nickel	EMS0034-NOV22	ug/L	0.1	< 0.1	ND	20	102	90	110	97	70	130

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Lead	EMS0034-NOV22	ug/L	0.01	< 0.01	12	20	104	90	110	99	70	130
Phosphorus	EMS0034-NOV22	mg/L	0.003	< 0.003	ND	20	101	90	110	NV	70	130
Antimony	EMS0034-NOV22	ug/L	0.6	< 0.09	ND	20	106	90	110	101	70	130
Selenium	EMS0034-NOV22	ug/L	0.04	< 0.04	2	20	102	90	110	118	70	130
Silicon	EMS0034-NOV22	ug/L	20	< 0.02	0	20	102	90	110	NV	70	130
Tin	EMS0034-NOV22	ug/L	0.06	< 0.06	ND	20	101	90	110	NV	70	130
Strontium	EMS0034-NOV22	ug/L	0.02	< 0.02	0	20	100	90	110	100	70	130
Titanium	EMS0034-NOV22	ug/L	0.05	< 0.05	ND	20	103	90	110	NV	70	130
Thallium	EMS0034-NOV22	ug/L	0.005	< 0.005	ND	20	102	90	110	98	70	130
Uranium	EMS0034-NOV22	ug/L	0.002	< 0.002	12	20	101	90	110	100	70	130
Vanadium	EMS0034-NOV22	ug/L	0.01	< 0.01	2	20	101	90	110	100	70	130
Tungsten	EMS0034-NOV22	ug/L	0.02	< 0.02	ND	20	98	90	110	NV	70	130
Yttrium	EMS0034-NOV22	ug/L	0.02	< 0.02	ND	20	100	90	110	NV	70	130
Zinc	EMS0034-NOV22	ug/L	2	< 2	1	20	101	90	110	104	70	130

QC SUMMARY

Microbiology

Method: OMOE MICROMFDC-E3407A | Internal ref.: ME-CA-IENVIMIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
E. Coli	BAC9064-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							
Total Coliform	BAC9064-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0070-NOV22	No unit	5	NA	0		100			NA		

QC SUMMARY

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0129-NOV22	mg/L	30	<30	2	20	98	90	110	NA		

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND**FOOTNOTES**

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY

No: **033288**

Page **1** of **1**

Laboratory Information Section - Lab use only

Received By: Kate Marchand
 Received Date: 11/01/22 (mm/dd/yy)
 Received Time: 17:33 (hr:min)

Received By (signature): [Signature]
 Custody Seal Present: Yes No
 Custody Seal Intact: Yes No

Cooling Agent Present: Yes No Type: Ice
 Temperature Upon Receipt (°C) 9, 10, 10

LAB LIMS #: CA-16229-Nov2

REPORT INFORMATION	INVOICE INFORMATION
Company: <u>Cambium Inc</u>	<input checked="" type="checkbox"/> (same as Report Information)
Contact: <u>Kevin Warner</u>	Company: _____
Address: <u>194 Sophia Street, Peterborough, ON K9H 1E3</u>	Contact: _____
Phone: <u>705 742 7900</u>	Address: _____
Fax: _____	Phone: _____
Email: <u>Kevin.Warner@Cambium-inc.com</u>	Email: _____

Quotation #: _____ P.O. #: 15101-001
 Project #: Woodview Golf Site Location/ID: _____

TURNAROUND TIME (TAT) REQUIRED
 Regular TAT (5-7days) TAT's are quoted in business days (exclude statutory holidays & weekends). Samples received after 6pm or on weekends: TAT begins next business day

RUSH TAT (Additional Charges May Apply): 1 Day 2 Days 3 Days 4 Days
PLEASE CONFIRM RUSH FEASIBILITY WITH SGS REPRESENTATIVE PRIOR TO SUBMISSION

Specify Due Date: _____ *NOTE: DRINKING (POTABLE) WATER SAMPLES FOR HUMAN CONSUMPTION MUST BE SUBMITTED WITH SGS DRINKING WATER CHAIN OF CUSTODY

REGULATIONS

O.Reg 153/04 O.Reg 406/19

Other Regulations: Reg 347/558 (3 Day min TAT) Sanitary
 PWQO MMER Storm
 CCME Other: _____ Municipality: _____
 MISA ODWS Not Reportable *See note

Sewer By-Law: _____

ANALYSIS REQUESTED

M & I	SVOC	PCB	PHC	VOC	Pest	Other (please specify)	SPLP	TCLP
Field Filtered (Y/N)	all incl PAHs, ABNs, CPs	Total <input type="checkbox"/> Aroclor <input type="checkbox"/>	F1-F4 + BTEX	F1-F4 only no BTEX	VOCs all incl BTEX	BTEX only	Pesticides Organochlorine or specify other	See Attached Parameters
Metals & Inorganics (incl. CVI, CN, Hg, pH, (B)(H)(S), (EC, SAR, soil) (Cl, Na-water)	Full Metals Suite (ICP metals plus B(H)(S)-soil only) Hg, CrVI	ICP Metals only (Sb, As, Ba, Be, B, Cd, Cr, Co, Cu, Pb, Mo, Ni, Se, Ag, Tl, U, V, Zn)	PAHs only	SVOCs	PCBs	F1-F4 + BTEX	F1-F4 only no BTEX	VOCs
Metals	VOCs	PCBs	F1-F4 + BTEX	F1-F4 only no BTEX	VOCs	BTEX only	Pesticides	Other

RECORD OF SITE CONDITION (RSC) YES NO

SAMPLE IDENTIFICATION	DATE SAMPLED	TIME SAMPLED	# OF BOTTLES	MATRIX
1 Pro Shop	Nov 1/22	3:10	9	GW
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				

Field Filtered (Y/N)	Metals & Inorganics	Full Metals Suite	ICP Metals only	PAHs only	SVOCs	PCBs	F1-F4 + BTEX	F1-F4 only no BTEX	VOCs	BTEX only	Pesticides	Other	SPLP	TCLP
N														

COMMENTS:

Observations/Comments/Special Instructions

Sampled By (NAME): Warren Young Signature: [Signature] Date: 11/01/22 (mm/dd/yy) Pink Copy - Client
 Relinquished by (NAME): Warren Young Signature: [Signature] Date: 11/01/22 (mm/dd/yy) Yellow & White Copy - SGS

Parameter List

Total Coliform
E. Coli
Alkalinity
pH
Conductivity
Chloride
Nitrite (as N)
Nitrate (as N)
Nitrate + Nitrite (as N)
Sulphate
Colour
Turbidity
Dissolved Organic Carbon
Ammonia+Ammonium (N)
Total Dissolved Solids
Hardness
Silver (total)
Aluminum (total)
Arsenic (total)
Barium (total)
Beryllium (total)
Boron (total)
Bismuth (total)
Calcium (total)
Cadmium (total)
Cobalt (total)
Chromium (total)
Copper (total)
Iron (total)
Potassium (total)
Lithium (total)
Magnesium (total)
Manganese (total)
Molybdenum (total)
Sodium (total)
Nickel (total)
Phosphorus (total)
Lead (total)
Antimony (total)
Selenium (total)
Silicon (total)
Tin (total)
Strontium (total)
Titanium (total)
Thallium (total)
Uranium (total)
Vanadium (total)
Tungsten (total)
Yttrium (total)
Zinc (total)



FINAL REPORT

CA14054-NOV22 R

15101-001, Woodview Golf

Prepared for

Cambium Inc.

First Page

CLIENT DETAILS		LABORATORY DETAILS	
Client	Cambium Inc.	Project Specialist	Jill Campbell, B.Sc.,GISAS
Address	194 Sophia Street Peterborough, ON K9H 1E5, Canada	Laboratory Address	SGS Canada Inc. 185 Concession St., Lakefield ON, K0L 2H0
Contact	Kevin Warner	Telephone	2165
Telephone	705-742-7900	Facsimile	705-652-6365
Facsimile		Email	jill.campbell@sgs.com
Email	kevin.warner@cambium-inc.com	SGS Reference	CA14054-NOV22
Project	15101-001, Woodview Golf	Received	11/02/2022
Order Number		Approved	11/14/2022
Samples	Ground Water (1)	Report Number	CA14054-NOV22 R
		Date Reported	11/14/2022

COMMENTS
<p>MAC - Maximum Acceptable Concentration AO/OG - Aesthetic Objective / Operational Guideline MDL - SGS Method Detection Limit</p> <p>Total and/or Free Residual Chlorine was not analyzed by SGS Environmental Services. Temperature of Sample upon Receipt: 10 degrees C Cooling Agent Present: Yes Custody Seal Present: Yes Chain of Custody Number: 024629</p>


SIGNATORIES
<p>Jill Campbell, B.Sc.,GISAS</p> 

TABLE OF CONTENTS

First Page.....	1-2
Index.....	3
Results.....	4-6
Exceedance Summary.....	7
QC Summary.....	8-14
Legend.....	15
Annexes.....	16



FINAL REPORT

CA14054-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name North Well

Sample Matrix Ground Water

Sample Date 02/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

General Chemistry

Alkalinity	mg/L as CaCO3	2	500		331
Colour	TCU	3	5		< 3
Conductivity	uS/cm	2			627
Turbidity	NTU	0.10	5	1	< 0.10
Total Dissolved Solids	mg/L	30	500		420
Ammonia+Ammonium (N)	as N mg/L	0.04			< 0.04
Dissolved Organic Carbon	mg/L	1	5		2

Metals and Inorganics

Sulphate	mg/L	2	500		13
Nitrite (as N)	as N mg/L	0.003		1	0.003#<MDL
Nitrate (as N)	as N mg/L	0.006		10	1.98
Nitrate + Nitrite (as N)	as N mg/L	0.006			1.98
Hardness	mg/L as CaCO3	0.05	100		345
Silver	µg/L	0.05			< 0.05
Aluminum	µg/L	1	100		< 1
Arsenic	µg/L	0.2		10	< 0.2
Barium	µg/L	0.02		1000	428
Beryllium	µg/L	0.007			0.008
Bismuth	µg/L	0.01			< 0.01
Boron	µg/L	2		5000	41
Calcium	mg/L	0.01			98.4
Cadmium	µg/L	0.003		5	0.004



FINAL REPORT

CA14054-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name North Well

Sample Matrix Ground Water

Sample Date 02/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
Metals and Inorganics (continued)					
Cobalt	µg/L	0.004			0.022
Chromium	µg/L	0.08		50	0.24
Copper	µg/L	0.2	1000		1.4
Iron	ug/L	7	300		< 7
Potassium	mg/L	0.009			1.46
Lithium	µg/L	0.1			6.1
Sodium	mg/L	0.01	200	20	3.12
Magnesium	mg/L	0.001			24.1
Manganese	µg/L	0.01	50		0.09
Molybdenum	µg/L	0.04			0.22
Nickel	µg/L	0.1			0.2
Phosphorus	mg/L	0.003			< 0.003
Lead	µg/L	0.01		10	0.02
Antimony	µg/L	0.6		6	< 0.6
Selenium	µg/L	0.04		50	0.14
Silicon	ug/L	20			3470
Tin	µg/L	0.06			< 0.06
Strontium	µg/L	0.02			1440
Titanium	ug/L	0.05			< 0.05
Thallium	µg/L	0.005			0.026
Uranium	µg/L	0.002		20	1.30
Vanadium	µg/L	0.01			0.45



FINAL REPORT

CA14054-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name North Well

Sample Matrix Ground Water

Sample Date 02/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

Metals and Inorganics (continued)

Tungsten	µg/L	0.02			< 0.02
Yttrium	µg/L	0.02			0.06
Zinc	µg/L	2	5000		3

Microbiology

Total Coliform	cfu/100mL	0		0	0
E. Coli	cfu/100mL	0		0	0

Other (ORP)

pH	No unit	5	8.5		7.88
Chloride	mg/L	1	250		15

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG /	ODWS_MAC /
				WATER / - - Table 4	WATER / - - Table
				- Drinking Water -	1,2 and 3 -
				Reg O.169_03	Drinking Water -
					Reg O.169_03
				L1	L2

North Well

Hardness	SM 3030/EPA 200.8	mg/L as CaCO3	345	100
----------	-------------------	---------------	-----	-----

QC SUMMARY

QCR_SubCategory

Method: SM 2130 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Turbidity	EWL0095-NOV22	NTU	0.10	< 0.10	0	10	96	90	110	NA		

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0080-NOV22	mg/L as CaCO3	2	< 2	ND	20	104	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-IENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0069-NOV22	mg/L	0.04	0.05	ND	10	97	90	110	88	75	125

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO5050-NOV22	mg/L	1	<1	0	20	106	80	120	82	75	125
Sulphate	DIO5050-NOV22	mg/L	2	<2	3	20	111	80	120	91	75	125

Anions by IC

Method: EPA300/MA300-Ions1.3 | Internal ref.: ME-CA-IENVIIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Nitrate + Nitrite (as N)	DIO0114-NOV22	mg/L	0.006	<0.006	NA		NA			NA		
Nitrite (as N)	DIO0114-NOV22	mg/L	0.003	<0.003	ND	20	96	90	110	99	75	125
Nitrate (as N)	DIO0114-NOV22	mg/L	0.006	<0.006	0	20	100	90	110	95	75	125

QC SUMMARY

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0076-NOV22	mg/L	1	<1	4	10	100	90	110	93	75	125

Colour

Method: SM 2120 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Colour	EWL0083-NOV22	TCU	3	< 3	ND	10	105	80	120	NA		

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0080-NOV22	uS/cm	2	< 2	1	20	100	90	110	NA		



FINAL REPORT

CA14054-NOV22 R

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Silver	EMS0052-NOV22	ug/L	0.05	<0.00005	ND	20	101	90	110	98	70	130
Aluminum	EMS0052-NOV22	ug/L	1	<0.001	2	20	101	90	110	102	70	130
Arsenic	EMS0052-NOV22	ug/L	0.2	<0.0002	ND	20	101	90	110	104	70	130
Barium	EMS0052-NOV22	ug/L	0.02	<0.00002	1	20	99	90	110	85	70	130
Beryllium	EMS0052-NOV22	ug/L	0.007	<0.000007	13	20	102	90	110	87	70	130
Boron	EMS0052-NOV22	ug/L	2	<0.002	1	20	100	90	110	103	70	130
Bismuth	EMS0052-NOV22	ug/L	0.01	<0.00001	0	20	97	90	110	71	70	130
Calcium	EMS0052-NOV22	mg/L	0.01	<0.01	0	20	96	90	110	92	70	130
Cadmium	EMS0052-NOV22	ug/L	0.003	<0.000003	5	20	99	90	110	98	70	130
Cobalt	EMS0052-NOV22	ug/L	0.004	<0.000004	1	20	98	90	110	95	70	130
Chromium	EMS0052-NOV22	ug/L	0.08	<0.00008	14	20	98	90	110	106	70	130
Copper	EMS0052-NOV22	ug/L	0.2	<0.0002	0	20	102	90	110	99	70	130
Iron	EMS0052-NOV22	ug/L	7	<0.007	ND	20	93	90	110	100	70	130
Potassium	EMS0052-NOV22	mg/L	0.009	<0.009	1	20	91	90	110	87	70	130
Lithium	EMS0052-NOV22	ug/L	0.1	<0.0001	11	20	101	90	110	87	70	130
Magnesium	EMS0052-NOV22	mg/L	0.001	<0.001	2	20	91	90	110	87	70	130
Manganese	EMS0052-NOV22	ug/L	0.01	<0.00001	0	20	101	90	110	95	70	130
Molybdenum	EMS0052-NOV22	ug/L	0.04	<0.00004	8	20	102	90	110	105	70	130
Sodium	EMS0052-NOV22	mg/L	0.01	<0.01	4	20	91	90	110	89	70	130
Nickel	EMS0052-NOV22	ug/L	0.1	<0.0001	2	20	99	90	110	96	70	130

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Lead	EMS0052-NOV22	ug/L	0.01	<0.00001	2	20	98	90	110	86	70	130
Phosphorus	EMS0052-NOV22	mg/L	0.003	<0.003	20	20	93	90	110	NV	70	130
Antimony	EMS0052-NOV22	ug/L	0.6	<0.0009	ND	20	104	90	110	112	70	130
Selenium	EMS0052-NOV22	ug/L	0.04	<0.00004	5	20	102	90	110	95	70	130
Silicon	EMS0052-NOV22	ug/L	20	<0.02	2	20	99	90	110	NV	70	130
Tin	EMS0052-NOV22	ug/L	0.06	<0.00006	14	20	101	90	110	NV	70	130
Strontium	EMS0052-NOV22	ug/L	0.02	<0.00002	0	20	99	90	110	95	70	130
Titanium	EMS0052-NOV22	ug/L	0.05	<0.00005	0	20	99	90	110	NV	70	130
Thallium	EMS0052-NOV22	ug/L	0.005	<0.000005	15	20	98	90	110	83	70	130
Uranium	EMS0052-NOV22	ug/L	0.002	<0.000002	2	20	98	90	110	86	70	130
Vanadium	EMS0052-NOV22	ug/L	0.01	<0.00001	11	20	99	90	110	95	70	130
Tungsten	EMS0052-NOV22	ug/L	0.02	<0.00002	ND	20	104	90	110	NV	70	130
Yttrium	EMS0052-NOV22	ug/L	0.02	<0.00002	6	20	101	90	110	NV	70	130
Zinc	EMS0052-NOV22	ug/L	2	<0.002	1	20	110	90	110	100	70	130

QC SUMMARY

Microbiology

Method: OMOE MICROMFDC-E3407A | Internal ref.: ME-CA-IENVIMIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
E. Coli	BAC9066-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							
Total Coliform	BAC9066-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0080-NOV22	No unit	5	NA	0		100			NA		

QC SUMMARY

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0141-NOV22	mg/L	30	<30	7	20	94	90	110	NA		

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND

FOOTNOTES

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY

Laboratory Information Section - Lab use only

Received By: Emily Lawrence
 Received Date: 11/02/22 (mm/dd/yy)
 Received Time: 17:34 (hr:min)

Received By (signature): [Signature]
 Custody Seal Present: Yes No
 Custody Seal Intact: Yes No
 Cooling Agent Present: Yes No Type: ICE
 Temperature Upon Receipt (°C): 11.10.9

LAB LIMS #: CA14054-NOV22

REPORT INFORMATION	INVOICE INFORMATION
Company: <u>Cambium Inc</u>	<input checked="" type="checkbox"/> (same as Report Information)
Contact: <u>Kevin Warner</u>	Company: _____
Address: <u>194 Sophia Street, Peterborough, ON K9H 1B3</u>	Contact: _____
Phone: <u>705 742 7900</u>	Address: _____
Fax: _____	Phone: _____
Email: <u>Kevin.Warner@Cambium-Inc.com</u>	Email: _____

Quotation #: _____ P.O. #: 15101-001

Project #: Woodview Golf Site Location/ID: _____

TURNAROUND TIME (TAT) REQUIRED

Regular TAT (5-7 days) TAT's are quoted in business days (exclude statutory holidays & weekends). Samples received after 6pm or on weekends: TAT begins next business day

RUSH TAT (Additional Charges May Apply): 1 Day 2 Days 3 Days 4 Days

PLEASE CONFIRM RUSH FEASIBILITY WITH SGS REPRESENTATIVE PRIOR TO SUBMISSION

Specify Due Date: _____ *NOTE: DRINKING (POTABLE) WATER SAMPLES FOR HUMAN CONSUMPTION MUST BE SUBMITTED WITH SGS DRINKING WATER CHAIN OF CUSTODY

REGULATIONS

O.Reg 153/04 O.Reg 406/19

Other Regulations: Reg 347/558 (3 Day min TAT) Sanitary Storm Sewer By-Law: _____
 PWQO MMER CCME Other: _____
 MISA ODWS Not Reportable *See note

Soil Volume <350m3 >350m3

ANALYSIS REQUESTED

SAMPLE IDENTIFICATION	DATE SAMPLED	TIME SAMPLED	# OF BOTTLES	MATRIX	Field Filtered (Y/N)	ANALYSIS REQUESTED										SPLP	TCLP	COMMENTS:							
						M & I	SVOC	PCB	PHC	VOC	Pest	Other (please specify)	Specify tests	Specify tests											
1	North Well	Nov 2/22	3:45	9	GW	N	Metals & Inorganics (incl Cu, V, CN, Hg, pH, (B)(HWS), (EC), (SAR), (soil) (Cl, Ni, water))	Full Metals Suite (ICP metals plus B)(HWS-soil only) Hg, Cr, V	ICP Metals only Sb, As, Ba, Be, B, Cd, Cr, Co, Cu, Pb, Mo, Ni	PAHs only	SVOCs all incl PAHs, ABNs, CPS	PCBs Total <input type="checkbox"/> Aroclor <input type="checkbox"/>	F1-F4 + BTEX	F1-F4 only no BTEX	VOCs all incl BTEX	BTEX only	Pesticides Organochlorine or specify other	Other (please specify)	Specify tests	Specify tests					
2																									
3																									
4																									
5																									
6																									
7																									
8																									
9																									
10																									
11																									
12																									

Observations/Comments/Special Instructions

Sampled By (NAME): Warren Young Signature: [Signature] Date: 11/02/22 (mm/dd/yy) Pink Copy - Client
 Relinquished by (NAME): Warren Young Signature: [Signature] Date: 11/02/22 (mm/dd/yy) Yellow & White Copy - SGS



FINAL REPORT

CA14067-NOV22 R

15101-001, Woodview Golf

Prepared for

Cambium Inc.

First Page

CLIENT DETAILS

LABORATORY DETAILS

Client	Cambium Inc.	Project Specialist	Jill Campbell, B.Sc.,GISAS
Address	194 Sophia Street Peterborough, ON K9H 1E5, Canada	Laboratory	SGS Canada Inc.
Contact	Kevin Warner	Address	185 Concession St., Lakefield ON, K0L 2H0
Telephone	705-742-7900	Telephone	2165
Facsimile		Facsimile	705-652-6365
Email	kevin.warner@cambium-inc.com	Email	jill.campbell@sgs.com
Project	15101-001, Woodview Golf	SGS Reference	CA14067-NOV22
Order Number		Received	11/03/2022
Samples	Ground Water (1)	Approved	11/15/2022
		Report Number	CA14067-NOV22 R
		Date Reported	11/15/2022

COMMENTS

MAC - Maximum Acceptable Concentration
 AO/OG - Aesthetic Objective / Operational Guideline
 MDL - SGS Method Detection Limit

Temperature of Sample upon Receipt: 11 degrees C
 Cooling Agent Present: Yes
 Custody Seal Present: Yes
 Chain of Custody Number: 033289

SIGNATORIES

Jill Campbell, B.Sc.,GISAS



TABLE OF CONTENTS

First Page.....	1-2
Index.....	3
Results.....	4-6
Exceedance Summary.....	7
QC Summary.....	8-14
Legend.....	15
Annexes.....	16-17



FINAL REPORT

CA14067-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name West Pond

Sample Matrix Ground Water

Sample Date 03/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

General Chemistry

Alkalinity	mg/L as CaCO ₃	2	500		281
Colour	TCU	3	5		3
Conductivity	uS/cm	2			708
Turbidity	NTU	0.10	5	1	0.25
Total Dissolved Solids	mg/L	30	500		477
Ammonia+Ammonium (N)	as N mg/L	0.04			< 0.04
Dissolved Organic Carbon	mg/L	1	5		2

Metals and Inorganics

Sulphate	mg/L	2	500		84
Nitrite (as N)	as N mg/L	0.003		1	<0.003
Nitrate (as N)	as N mg/L	0.006		10	0.072
Nitrate + Nitrite (as N)	as N mg/L	0.006			0.072
Hardness	mg/L as CaCO ₃	0.05	100		375
Silver	µg/L	0.05			< 0.05
Aluminum	µg/L	1	100		1
Arsenic	µg/L	0.2		10	< 0.2
Barium	µg/L	0.02		1000	70.9
Beryllium	µg/L	0.007			0.012
Bismuth	µg/L	0.01			< 0.01
Boron	µg/L	2		5000	176
Calcium	mg/L	0.01			114
Cadmium	µg/L	0.003		5	< 0.003



FINAL REPORT

CA14067-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name West Pond

Sample Matrix Ground Water

Sample Date 03/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
Metals and Inorganics (continued)					
Cobalt	µg/L	0.004			0.156
Chromium	µg/L	0.08		50	0.24
Copper	µg/L	0.2	1000		2.7
Iron	ug/L	7	300		12
Potassium	mg/L	0.009			3.73
Lithium	µg/L	0.1			20.4
Sodium	mg/L	0.01	200	20	8.50
Magnesium	mg/L	0.001			21.8
Manganese	µg/L	0.01	50		5.45
Molybdenum	µg/L	0.04			0.62
Nickel	µg/L	0.1			< 0.1
Phosphorus	mg/L	0.003			0.015
Lead	µg/L	0.01		10	0.04
Antimony	µg/L	0.6		6	< 0.6
Selenium	µg/L	0.04		50	0.16
Silicon	ug/L	20			3778
Tin	µg/L	0.06			< 0.06
Strontium	µg/L	0.02			5050
Titanium	ug/L	0.05			0.08
Thallium	µg/L	0.005			0.025
Uranium	µg/L	0.002		20	7.55
Vanadium	µg/L	0.01			0.21



FINAL REPORT

CA14067-NOV22 R

Client: Cambium Inc.

Project: 15101-001, Woodview Golf

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 8

Sample Name West Pond

Sample Matrix Ground Water

Sample Date 03/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

Metals and Inorganics (continued)

Tungsten	µg/L	0.02			0.03
Yttrium	µg/L	0.02			0.07
Zinc	µg/L	2	5000		3

Microbiology

Total Coliform	cfu/100mL	0		0	0
E. Coli	cfu/100mL	0		0	0

Other (ORP)

pH	No unit	5	8.5		7.93
Chloride	mg/L	1	250		20

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG /	ODWS_MAC /
				WATER / - - Table 4	WATER / - - Table
				- Drinking Water -	1,2 and 3 -
				Reg O.169_03	Drinking Water -
					Reg O.169_03
				L1	L2

West Pond

Hardness	SM 3030/EPA 200.8	mg/L as CaCO3	375	100
----------	-------------------	---------------	-----	-----



FINAL REPORT

CA14067-NOV22 R

QC SUMMARY

QCR_SubCategory

Method: SM 2130 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Turbidity	EWL0130-NOV22	NTU	0.10	< 0.10	0	10	98	90	110	NA		

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0103-NOV22	mg/L as CaCO3	2	< 2	0	20	102	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-IENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0072-NOV22	mg/L	0.04	<0.04	ND	10	99	90	110	94	75	125

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO5049-NOV22	mg/L	1	<1	ND	20	106	80	120	106	75	125
Sulphate	DIO5049-NOV22	mg/L	2	<2	ND	20	111	80	120	109	75	125

Anions by IC

Method: EPA300/MA300-Ions1.3 | Internal ref.: ME-CA-IENVIIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Nitrate + Nitrite (as N)	DIO0233-NOV22	mg/L	0.006	<0.006	NA		NA			NA		
Nitrite (as N)	DIO0233-NOV22	mg/L	0.003	<0.003	5	20	99	90	110	97	75	125
Nitrate (as N)	DIO0233-NOV22	mg/L	0.006	<0.006	2	20	100	90	110	92	75	125

QC SUMMARY

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0076-NOV22	mg/L	1	<1	4	10	100	90	110	93	75	125

Colour

Method: SM 2120 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Colour	EWL0180-NOV22	TCU	3	< 3	ND	10	115	80	120	NA		

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0103-NOV22	uS/cm	2	< 2	0	20	99	90	110	NA		



FINAL REPORT

CA14067-NOV22 R

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Silver	EMS0048-NOV22	ug/L	0.05	<0.00005	ND	20	102	90	110	106	70	130
Aluminum	EMS0048-NOV22	ug/L	1	<0.001	0	20	102	90	110	115	70	130
Arsenic	EMS0048-NOV22	ug/L	0.2	<0.0002	ND	20	100	90	110	104	70	130
Barium	EMS0048-NOV22	ug/L	0.02	<0.00002	0	20	99	90	110	97	70	130
Beryllium	EMS0048-NOV22	ug/L	0.007	<0.000007	9	20	92	90	110	90	70	130
Boron	EMS0048-NOV22	ug/L	2	<0.002	1	20	99	90	110	99	70	130
Bismuth	EMS0048-NOV22	ug/L	0.01	<0.00001	ND	20	97	90	110	88	70	130
Calcium	EMS0048-NOV22	mg/L	0.01	<0.01	0	20	93	90	110	95	70	130
Cadmium	EMS0048-NOV22	ug/L	0.003	< 0.003	ND	20	100	90	110	99	70	130
Cobalt	EMS0048-NOV22	ug/L	0.004	<0.000004	ND	20	102	90	110	104	70	130
Chromium	EMS0048-NOV22	ug/L	0.08	<0.00008	20	20	102	90	110	107	70	130
Copper	EMS0048-NOV22	ug/L	0.2	<0.0002	0	20	104	90	110	122	70	130
Iron	EMS0048-NOV22	ug/L	7	<0.007	5	20	93	90	110	NV	70	130
Potassium	EMS0048-NOV22	mg/L	0.009	<0.009	0	20	97	90	110	86	70	130
Lithium	EMS0048-NOV22	ug/L	0.1	<0.0001	2	20	94	90	110	91	70	130
Magnesium	EMS0048-NOV22	mg/L	0.001	<0.001	2	20	95	90	110	96	70	130
Manganese	EMS0048-NOV22	ug/L	0.01	<0.00001	1	20	101	90	110	112	70	130
Molybdenum	EMS0048-NOV22	ug/L	0.04	<0.00004	ND	20	103	90	110	105	70	130
Sodium	EMS0048-NOV22	mg/L	0.01	<0.01	1	20	91	90	110	102	70	130
Nickel	EMS0048-NOV22	ug/L	0.1	<0.0001	9	20	94	90	110	100	70	130

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Lead	EMS0048-NOV22	ug/L	0.01	<0.00001	0	20	100	90	110	100	70	130
Phosphorus	EMS0048-NOV22	mg/L	0.003	<0.003	2	20	91	90	110	NV	70	130
Antimony	EMS0048-NOV22	ug/L	0.6	<0.0009	ND	20	105	90	110	118	70	130
Selenium	EMS0048-NOV22	ug/L	0.04	<0.00004	ND	20	99	90	110	110	70	130
Silicon	EMS0048-NOV22	ug/L	20	<0.02	2	20	101	90	110	NV	70	130
Tin	EMS0048-NOV22	ug/L	0.06	<0.00006	ND	20	96	90	110	NV	70	130
Strontium	EMS0048-NOV22	ug/L	0.02	0.000114	0	20	100	90	110	101	70	130
Titanium	EMS0048-NOV22	ug/L	0.05	<0.00005	ND	20	97	90	110	NV	70	130
Thallium	EMS0048-NOV22	ug/L	0.005	<0.000005	ND	20	99	90	110	99	70	130
Uranium	EMS0048-NOV22	ug/L	0.002	<0.000002	15	20	101	90	110	100	70	130
Vanadium	EMS0048-NOV22	ug/L	0.01	<0.00001	0	20	102	90	110	103	70	130
Tungsten	EMS0048-NOV22	ug/L	0.02	<0.00002	ND	20	97	90	110	NV	70	130
Yttrium	EMS0048-NOV22	ug/L	0.02	<0.00002	12	20	101	90	110	NV	70	130
Zinc	EMS0048-NOV22	ug/L	2	<0.002	ND	20	105	90	110	122	70	130

QC SUMMARY

Microbiology

Method: SM 9222D | Internal ref.: ME-CA-~~I~~ENVIMIC-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
E. Coli	BAC9086-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							
Total Coliform	BAC9086-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							

pH

Method: SM 4500 | Internal ref.: ME-CA-~~I~~ENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0103-NOV22	No unit	5	NA	0		99			NA		

QC SUMMARY

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0189-NOV22	mg/L	30	<30	0	20	102	90	110	NA		

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND

FOOTNOTES

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY

No: 033289

Page 1 of 1

Received By: Kelly Clarkson Received By (signature): [Signature]
 Received Date: 11/03/22 (mm/dd/yy) Custody Seal Present: Yes No Cooling Agent Present: Yes No Type: ICE
 Received Time: 17:30 (hr:min) Custody Seal Intact: Yes No Temperature Upon Receipt (°C) 11, 11, 11 LAB LIMS #: CA14067-NOV22

REPORT INFORMATION	INVOICE INFORMATION	TURNAROUND TIME (TAT) REQUIRED	
Company: <u>Cambium Inc</u> Contact: <u>Kevin Warner</u> Address: <u>1914 Sophia Street, Peterborough, ON K9H 1E3</u> Phone: <u>705 742 7900</u> Fax: _____ Email: <u>Kevin.Warner@Cambium-inc.com</u>	<input checked="" type="checkbox"/> (same as Report Information) Company: _____ Contact: _____ Address: _____ Phone: _____ Email: _____	Quotation #: _____ Project #: <u>Woodview GOLF</u>	P.O. #: <u>15101-001</u> Site Location/ID: _____
		<input checked="" type="checkbox"/> Regular TAT (5-7 days) TAT's are quoted in business days (exclude statutory holidays & weekends). Samples received after 6pm or on weekends: TAT begins next business day RUSH TAT (Additional Charges May Apply): <input type="checkbox"/> 1 Day <input type="checkbox"/> 2 Days <input type="checkbox"/> 3 Days <input type="checkbox"/> 4 Days PLEASE CONFIRM RUSH FEASIBILITY WITH SGS REPRESENTATIVE PRIOR TO SUBMISSION	
REGULATIONS		ANALYSIS REQUESTED	

REGULATIONS		ANALYSIS REQUESTED																
<input type="checkbox"/> O.Reg 153/04	<input type="checkbox"/> O.Reg 406/19	Other Regulations:	Sewer By-Law:	M & I	SVOC	PCB	PHC	VOC	Pest	Other (please specify)			SPLP	TCLP				
<input type="checkbox"/> Table 1	<input type="checkbox"/> Res/Park	<input type="checkbox"/> Reg 347/558 (3 Day min TAT)	<input type="checkbox"/> Sanitary	Field Filtered (Y/N)	Metals & Inorganics <small>Incl CrVI, CN, Hg, pH, (B)(HWS) (EG, SAR, soil) (Cl, Na-water)</small>	Full Metals Suite <small>ICP metals plus B(HWS-soil only) Hg, CrVI</small>	ICP Metals only <small>Sb, As, Ba, Be, B, Cd, Cr, Co, Cu, Pb, Mo, Ni, Se, Ag, Tl, U, V, Zn</small>	PAHs only	SVOCs <small>all incl PAHs, ABNs, CPs</small>	PCBs Total <input type="checkbox"/> Arochlor <input type="checkbox"/>	F1-F4 + BTEX	F1-F4 only no BTEX	VOCs all incl BTEX	BTEX only	Pesticides <small>Organochlorine or specify other</small>	Sewer Use: Specify pkg: Water Characterization Pkg General <input type="checkbox"/> Extended <input type="checkbox"/>	Specify tests	Specify tests
<input type="checkbox"/> Table 2	<input type="checkbox"/> Ind/Com	<input type="checkbox"/> PWQO	<input type="checkbox"/> Storm															
<input type="checkbox"/> Table 3	<input type="checkbox"/> Agri/Other	<input type="checkbox"/> CCME	Municipality: _____															
<input type="checkbox"/> Table _____	Soil Volume <input type="checkbox"/> <350m3 <input type="checkbox"/> >350m3	<input type="checkbox"/> MISA	<input checked="" type="checkbox"/> ODWS Not Reportable *See note															

RECORD OF SITE CONDITION (RSC)					DATE SAMPLED	TIME SAMPLED	# OF BOTTLES	MATRIX	Field Filtered (Y/N)	Metals & Inorganics <small>Incl CrVI, CN, Hg, pH, (B)(HWS) (EG, SAR, soil) (Cl, Na-water)</small>	Full Metals Suite <small>ICP metals plus B(HWS-soil only) Hg, CrVI</small>	ICP Metals only <small>Sb, As, Ba, Be, B, Cd, Cr, Co, Cu, Pb, Mo, Ni, Se, Ag, Tl, U, V, Zn</small>	PAHs only	SVOCs <small>all incl PAHs, ABNs, CPs</small>	PCBs Total <input type="checkbox"/> Arochlor <input type="checkbox"/>	F1-F4 + BTEX	F1-F4 only no BTEX	VOCs all incl BTEX	BTEX only	Pesticides <small>Organochlorine or specify other</small>	Sewer Use: Specify pkg: Water Characterization Pkg General <input type="checkbox"/> Extended <input type="checkbox"/>	Specify tests	Specify tests	COMMENTS:		
O.Reg 153/04		O.Reg 406/19		Other Regulations:																					Sewer By-Law:	
1	West Pond	Nov 3/22	2:10	9	GW	N																				
2																										
3																										
4																										
5																										
6																										
7																										
8																										
9																										
10																										
11																										
12																										

Observations/Comments/Special Instructions

Sampled By (NAME): <u>Warren Young</u>	Signature: <u>[Signature]</u>	Date: <u>11/03/22</u> (mm/dd/yy)	Pink Copy - Client
Relinquished by (NAME): <u>Warren Young</u>	Signature: <u>[Signature]</u>	Date: <u>11/03/22</u> (mm/dd/yy)	Yellow & White Copy - SGS

Project: Woodview Golf, Project Number:15101-001 , November 3, 2022

Parameter List

Total Coliform
E. Coli
Alkalinity
pH
Conductivity
Chloride
Nitrite (as N)
Nitrate (as N)
Nitrate + Nitrite (as N)
Sulphate
Colour
Turbidity
Dissolved Organic Carbon
Ammonia+Ammonium (N)
Total Dissolved Solids
Hardness
Silver (total)
Aluminum (total)
Arsenic (total)
Barium (total)
Beryllium (total)
Boron (total)
Bismuth (total)
Calcium (total)
Cadmium (total)
Cobalt (total)
Chromium (total)
Copper (total)
Iron (total)
Potassium (total)
Lithium (total)
Magnesium (total)
Manganese (total)
Molybdenum (total)
Sodium (total)
Nickel (total)
Phosphorus (total)
Lead (total)
Antimony (total)
Selenium (total)
Silicon (total)
Tin (total)
Strontium (total)
Titanium (total)
Thallium (total)
Uranium (total)
Vanadium (total)
Tungsten (total)
Yttrium (total)
Zinc (total)



FINAL REPORT

CA40287-NOV22 R

15101-001 Woodview Golf Subdivision, Woodview ON

Prepared for

Cambium Inc.

First Page

CLIENT DETAILS

Client Cambium Inc.
 Address 194 Sophia Street
 Peterborough, ON
 K9H 1E5, Canada
 Contact Kevin Warner
 Telephone 705-742-7900
 Facsimile
 Email kevin.warner@cambium-inc.com
 Project 15101-001 Woodview Golf Subdivision, Woodview ON
 Order Number
 Samples Ground Water (1)

LABORATORY DETAILS

Project Specialist Brad Moore Hon. B.Sc
 Laboratory SGS Canada Inc.
 Address 185 Concession St., Lakefield ON, K0L 2H0
 Telephone 705-652-2143
 Facsimile 705-652-6365
 Email brad.moore@sgs.com
 SGS Reference CA40287-NOV22
 Received 11/23/2022
 Approved 12/05/2022
 Report Number CA40287-NOV22 R
 Date Reported 12/05/2022

COMMENTS

Note: Unionized ammonia calculated using lab results for pH and temperature.

Temperature of Sample upon Receipt: 11 degrees C

Cooling Agent Present: Yes

Custody Seal Present: Yes

Chain of Custody Number: 030112

SIGNATORIES

Brad Moore Hon. B.Sc



TABLE OF CONTENTS

First Page.....	1
Index.....	2
Results.....	3-5
Exceedance Summary.....	6
QC Summary.....	7-14
Legend.....	15
Annexes.....	16-17



FINAL REPORT

CA40287-NOV22 R

Client: Cambium Inc.

Project: 15101-001 Woodview Golf Subdivision, Woodview ON

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 6
Sample Name TW 5
Sample Matrix Ground Water
Sample Date 23/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

General Chemistry

Alkalinity	mg/L as CaCO3	2	500		351
Colour	TCU	3	5		< 3
Conductivity	uS/cm	2			820
Total Dissolved Solids	mg/L	30	500		494
Turbidity	NTU	0.10	5	1	0.45
Dissolved Organic Carbon	mg/L	1	5		< 1
Ammonia+Ammonium (N)	as N mg/L	0.1			< 0.1

Metals and Inorganics

Sulphate	mg/L	2	500		13
Nitrite (as N)	as N mg/L	0.03		1	< 0.03
Nitrate (as N)	as N mg/L	0.06		10	0.22
Nitrate + Nitrite (as N)	as N mg/L	0.06			0.22
Hardness	mg/L as CaCO3	0.05	100		38.3
Aluminum (total)	mg/L	0.001	0.1		< 0.001
Antimony (total)	mg/L	0.0009		0.006	< 0.0009
Arsenic (total)	mg/L	0.0002		0.01	< 0.0002
Barium (total)	mg/L	0.00008		1	0.0493
Beryllium (total)	mg/L	0.000007			< 0.000007
Boron (total)	mg/L	0.002		5	0.014
Bismuth (total)	mg/L	0.00001			0.00003
Cadmium (total)	mg/L	0.000003		0.005	< 0.000003
Calcium (total)	mg/L	0.01			11.1



FINAL REPORT

CA40287-NOV22 R

Client: Cambium Inc.

Project: 15101-001 Woodview Golf Subdivision, Woodview ON

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 6
Sample Name TW 5
Sample Matrix Ground Water
Sample Date 23/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
Metals and Inorganics (continued)					
Chromium (total)	mg/L	0.00008		0.05	< 0.00008
Cobalt (total)	mg/L	0.000004			< 0.000004
Copper (total)	mg/L	0.0002	1		0.0003
Iron (total)	mg/L	0.007	0.3		< 0.007
Lead (total)	mg/L	0.00009		0.01	< 0.00009
Lithium (total)	mg/L	0.0001			0.0004
Magnesium (total)	mg/L	0.001			2.59
Manganese (total)	mg/L	0.00001	0.05		0.00005
Molybdenum (total)	mg/L	0.00004			0.00079
Nickel (total)	mg/L	0.0001			< 0.0001
Phosphorus (total)	mg/L	0.003			< 0.003
Potassium (total)	mg/L	0.009			0.210
Selenium (total)	mg/L	0.00004		0.05	< 0.00004
Silicon (total)	mg/L	0.02			0.55
Silver (total)	mg/L	0.00005			< 0.00005
Sodium (total)	mg/L	0.01			2.67
Strontium (total)	mg/L	0.00008			0.09007
Thallium (total)	mg/L	0.000005			< 0.000005
Tin (total)	mg/L	0.00006			< 0.00006
Titanium (total)	mg/L	0.00005			< 0.00005
Vanadium (total)	mg/L	0.00001			0.00003
Zinc (total)	mg/L	0.002	5		0.002



FINAL REPORT

CA40287-NOV22 R

Client: Cambium Inc.

Project: 15101-001 Woodview Golf Subdivision, Woodview ON

Project Manager: Kevin Warner

Samplers: Warren Young

MATRIX: WATER

Sample Number 6
Sample Name TW 5
Sample Matrix Ground Water
Sample Date 23/11/2022

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result
-----------	-------	----	----	----	--------

Metals and Inorganics (continued)

Uranium (total)	mg/L	0.000002		0.02	0.000082
Tungsten (total)	mg/L	0.00002			< 0.00002
Yttrium (total)	mg/L	0.00002			< 0.00002

Microbiology

Total Coliform	cfu/100mL	0		0	0
E. Coli	cfu/100mL	0		0	0

Other (ORP)

pH	No unit	0.05	8.5		7.87
Chloride	mg/L	1	250		78

EXCEEDANCE SUMMARY

No exceedances are present above the regulatory limit(s) indicated



FINAL REPORT

CA40287-NOV22 R

QC SUMMARY

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-1ENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0551-NOV22	mg/L as CaCO3	2	< 2	1	20	104	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-1ENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0249-NOV22	as N mg/L	0.1	<0.1	ND	10	98	90	110	96	75	125

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO5116-NOV22	mg/L	1	<1	ND	20	105	80	120	114	75	125
Sulphate	DIO5116-NOV22	mg/L	2	<2	ND	20	109	80	120	116	75	125

Anions by IC

Method: EPA300/MA300-Ions1.3 | Internal ref.: ME-CA-IENVIIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Nitrate + Nitrite (as N)	DIO0633-NOV22	mg/L	0.06	<0.06	NA		NA			NA		
Nitrite (as N)	DIO0633-NOV22	mg/L	0.03	<0.03	ND	20	93	90	110	95	75	125
Nitrate (as N)	DIO0633-NOV22	mg/L	0.06	<0.06	19	20	98	90	110	98	75	125

QC SUMMARY

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0259-NOV22	mg/L	1	<1	ND	20	101	90	110	116	75	125

Colour

Method: SM 2120 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Colour	EWL0564-NOV22	TCU	3	< 3	ND	10	105	80	120	NA		

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0551-NOV22	uS/cm	2	< 2	1	20	99	90	110	NA		



FINAL REPORT

CA40287-NOV22 R

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Silver (total)	EMS0247-NOV22	mg/L	0.00005	<0.00005	ND	20	100	90	110	89	70	130
Aluminum (total)	EMS0247-NOV22	mg/L	0.001	<0.001	NV	20	NV	90	110	93	70	130
Arsenic (total)	EMS0247-NOV22	mg/L	0.0002	<0.0002	ND	20	100	90	110	107	70	130
Barium (total)	EMS0247-NOV22	mg/L	0.00008	<0.00002	4	20	99	90	110	107	70	130
Beryllium (total)	EMS0247-NOV22	mg/L	0.000007	<0.000007	0	20	102	90	110	103	70	130
Boron (total)	EMS0247-NOV22	mg/L	0.002	<0.002	2	20	95	90	110	89	70	130
Bismuth (total)	EMS0247-NOV22	mg/L	0.00001	<0.00001	0	20	97	90	110	94	70	130
Calcium (total)	EMS0247-NOV22	mg/L	0.01	<0.01	18	20	94	90	110	98	70	130
Cadmium (total)	EMS0247-NOV22	mg/L	0.000003	<0.000003	9	20	102	90	110	100	70	130
Cobalt (total)	EMS0247-NOV22	mg/L	0.000004	<0.000004	13	20	98	90	110	103	70	130
Chromium (total)	EMS0247-NOV22	mg/L	0.00008	<0.00008	ND	20	96	90	110	110	70	130
Copper (total)	EMS0247-NOV22	mg/L	0.0002	<0.0002	9	20	99	90	110	121	70	130
Iron (total)	EMS0247-NOV22	mg/L	0.007	<0.007	2	20	102	90	110	111	70	130
Potassium (total)	EMS0247-NOV22	mg/L	0.009	<0.009	10	20	92	90	110	107	70	130
Lithium (total)	EMS0247-NOV22	mg/L	0.0001	<0.0001	8	20	103	90	110	99	70	130
Magnesium (total)	EMS0247-NOV22	mg/L	0.001	<0.001	12	20	102	90	110	105	70	130
Manganese (total)	EMS0247-NOV22	mg/L	0.00001	<0.00001	18	20	101	90	110	118	70	130
Molybdenum (total)	EMS0247-NOV22	mg/L	0.00004	<0.00004	15	20	94	90	110	98	70	130
Sodium (total)	EMS0247-NOV22	mg/L	0.01	<0.01	1	20	92	90	110	100	70	130
Nickel (total)	EMS0247-NOV22	mg/L	0.0001	<0.0001	8	20	95	90	110	106	70	130

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Lead (total)	EMS0247-NOV22	mg/L	0.00009	<0.00001	6	20	101	90	110	101	70	130
Phosphorus (total)	EMS0247-NOV22	mg/L	0.003	<0.003	ND	20	93	90	110	NV	70	130
Antimony (total)	EMS0247-NOV22	mg/L	0.0009	<0.0009	ND	20	100	90	110	117	70	130
Selenium (total)	EMS0247-NOV22	mg/L	0.00004	<0.00004	ND	20	95	90	110	103	70	130
Silicon (total)	EMS0247-NOV22	mg/L	0.02	<0.02	5	20	95	90	110	NV	70	130
Tin (total)	EMS0247-NOV22	mg/L	0.00006	<0.00006	3	20	95	90	110	NV	70	130
Strontium (total)	EMS0247-NOV22	mg/L	0.00008	<0.00002	17	20	98	90	110	105	70	130
Titanium (total)	EMS0247-NOV22	mg/L	0.00005	<0.00005	5	20	95	90	110	NV	70	130
Thallium (total)	EMS0247-NOV22	mg/L	0.000005	<0.000005	0	20	99	90	110	96	70	130
Uranium (total)	EMS0247-NOV22	mg/L	0.000002	<0.000002	2	20	100	90	110	98	70	130
Vanadium (total)	EMS0247-NOV22	mg/L	0.00001	<0.00001	7	20	98	90	110	100	70	130
Tungsten (total)	EMS0247-NOV22	mg/L	0.00002	<0.00002	ND	20	96	90	110	NV	70	130
Yttrium (total)	EMS0247-NOV22	mg/L	0.00002	<0.00002	ND	20	98	90	110	NV	70	130
Zinc (total)	EMS0247-NOV22	mg/L	0.002	<0.002	4	20	106	90	110	NV	70	130

QC SUMMARY

Microbiology

Method: OMOE MICROMFDC-E3407A | Internal ref.: ME-CA-IENVIMIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
E. Coli	BAC9418-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							
Total Coliform	BAC9418-NOV22	cfu/100mL	-	ACCEPTED	ACCEPTED							

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0551-NOV22	No unit	0.05	NA	1		100			NA		



FINAL REPORT

CA40287-NOV22 R

QC SUMMARY

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0553-NOV22	mg/L	30	<30	4	20	99	80	120	NA		

Turbidity

Method: SM 2130 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Turbidity	EWL0545-NOV22	NTU	0.10	< 0.10	0	10	101	90	110	NA		

QC SUMMARY

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND**FOOTNOTES**

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY

Industries & Environment - Lakefield: 185 Concession St., Lakefield, ON K0L 2H0 Phone: 705-652-2000 Fax: 705-652-6365 Web: www.sgs.com/environment

- London: 657 Consortium Court, London, ON, N6E 2S8 Phone: 519-672-4500 Toll Free: 877-848-8060 Fax: 519-672-0361

No: 030112

Page 1 of 1

Laboratory Information Section - Lab use only

Received By: nata sham
Received Date: 11/23/22 (mm/dd/yy)
Received Time: 20:10 (hr:min)

Received By (signature): [Signature]
Custody Seal Present: Yes No
Custody Seal Intact: Yes No
Cooling Agent Present: Yes No Type: ice
Temperature Upon Receipt (°C) 11, 11, 11

LAB LIMS #: CC40287-NOV 22

REPORT INFORMATION
Company: Cambium Inc
Contact: Kevin Warner
Address: 194 Sophia Street, Peterborough, ON, K9H1E3
Phone: 705 742 7900
Fax:
Email: Kevin.Warner@cambium-inc.com

INVOICE INFORMATION
 (same as Report Information)
Company:
Contact:
Address:
Phone:

Quotation #: _____ P.O. #: _____
Project #: 15101-001 Woodview Golf Subdivision Site Location/ID: Woodview ON /

TURNAROUND TIME (TAT) REQUIRED
 Regular TAT (5-7 days) TAT's are quoted in business days (exclude statutory holidays & weekends). Samples received after 6pm or on weekends: TAT begins next business day
RUSH TAT (Additional Charges May Apply): 1 Day 2 Days 3 Days 4 Days
PLEASE CONFIRM RUSH FEASIBILITY WITH SGS REPRESENTATIVE PRIOR TO SUBMISSION
Specify Due Date: _____ *NOTE: DRINKING (POTABLE) WATER SAMPLES FOR HUMAN CONSUMPTION MUST BE SUBMITTED WITH SGS DRINKING WATER CHAIN OF CUSTODY

REGULATIONS
 O.Reg 153/04 O.Reg 406/19
Other Regulations:
 Table 1 Res/Park Soil Texture:
 Table 2 Ind/Com Coarse
 Table 3 Agri/Other Medium/Fine
 Table _____ Appx. _____
Soil Volume <350m3 >350m3
Sewer By-Law:
 Sanitary
 Storm
Municipality:
 Reg 347/558 (3 Day min TAT)
 PWQO MMER
 CCME Other:
 MISA
 ODWS Not Reportable *See note

ANALYSIS REQUESTED

M & I	SVOC	PCB	PHC	VOC	Pest	Other (please specify)	SPLP	TCLP
Field Filtered (Y/N)	PAHs only	PCBs Total <input type="checkbox"/> Aroclor <input type="checkbox"/>	F1-F4 + BTEX	VOCs all incl BTEX	Pesticides Organochlorine or specify other	<u>See Attached Parameters</u>	Specify tests <input type="checkbox"/> Metals <input type="checkbox"/> VOC <input type="checkbox"/> PCB <input type="checkbox"/> B(a)P <input type="checkbox"/> ABN <input type="checkbox"/> Ignit.	Specify tests <input type="checkbox"/> M&I <input type="checkbox"/> VOC <input type="checkbox"/> PCB <input type="checkbox"/> B(a)P <input type="checkbox"/> ABN <input type="checkbox"/> Ignit.

RECORD OF SITE CONDITION (RSC) YES NO

SAMPLE IDENTIFICATION	DATE SAMPLED	TIME SAMPLED	# OF BOTTLES	MATRIX	Field Filtered (Y/N)	Metals & Inorganics <small>incl CVI, CN, Hg, pH, (B)(HWS), (EC, SAR, soil) (Cl, Na-water)</small>	Full Metals Suite <small>ICP, metals plus B(HWS-soil only) Hg, CVI</small>	ICP Metals only <small>Cr, Co, Cu, Pb, Mo, Ni, Se, Ag, Tl, U, V, Zn</small>	PAHs only	SVOCs <small>all incl PAHs, ABNs, CPs</small>	PCBs <small>Total</small>	PHC <small>F1-F4 + BTEX</small>	VOC <small>F1-F4 only no BTEX</small>	Pest <small>VOCs all incl BTEX</small>	Other (please specify)	SPLP <small>General</small>	TCLP <small>Extended</small>	COMMENTS:
1 TW5	Nov 23/22	4:55	9	GW	N													
2																		
3																		
4																		
5																		
6																		
7																		
8																		
9																		
10																		
11																		
12																		

Observations/Comments/Special Instructions

Sampled By (NAME): Warren Young Signature: [Signature] Date: 11/23/22 (mm/dd/yy) Pink Copy - Client
Relinquished by (NAME): Warren Young Signature: [Signature] Date: 11/23/22 (mm/dd/yy) Yellow & White Copy - SGS

Revision #: 1.6
Note: Submission of samples to SGS is acknowledgement that you have been provided direction on sample collection/handling and transportation of samples. (2) Submission of samples to SGS is considered authorization for completion of work. Signatures may appear on this form or be retained on file in the contract, or in an alternative format (e.g. shipping documents). (3) Results may be sent by email to an unlimited number of addresses for no additional cost. Fax is available upon request. This document is issued by the Company under its General Conditions of Service accessible at http://www.sgs.com/terms_and_conditions.htm. (Printed copies are available upon request.) Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.

15101-001 analysis
parameters list

Nov 3 23/22

Total Coliform
E. Coli
Alkalinity
pH
Conductivity
Chloride
Nitrite (as N)
Nitrate (as N)
Nitrate + Nitrite (as N)
Sulphate
Colour
Turbidity
Dissolved Organic Carbon
Ammonia+Ammonium (N)
Total Dissolved Solids
Hardness
Silver (total)
Aluminum (total)
Arsenic (total)
Barium (total)
Beryllium (total)
Boron (total)
Bismuth (total)
Calcium (total)
Cadmium (total)
Cobalt (total)
Chromium (total)
Copper (total)
Iron (total)
Potassium (total)
Lithium (total)
Magnesium (total)
Manganese (total)
Molybdenum (total)
Sodium (total)
Nickel (total)
Phosphorus (total)
Lead (total)
Antimony (total)
Selenium (total)
Silicon (total)
Tin (total)
Strontium (total)
Titanium (total)
Thallium (total)
Uranium (total)
Vanadium (total)
Tungsten (total)
Yttrium (total)
Zinc (total)